# **City of San Diego**

**CITY CONTACT:** Juan E. Espindola, Senior Contract Specialist, Email: JEEspindola@sandiego.gov Phone No. (619) 533-4491

## **ADDENDUM A**





## FOR

### NIMITZ BRIDGE AT NTC REHABILITATION

BID No:	K-20-1901-DBB-2
SAP NO. (WBS/IO/CC):	B-15198
CLIENT DEPARTMENT:	2116
COUNCIL DISTRICT:	2
PROJECT TYPE:	IC

#### **BID DUE DATE**:

2:00 PM MAY 7, 2020

#### **CITY OF SAN DIEGO'S ELECTRONIC BIDDING SITE, PLANETBIDS**

http://www.sandiego.gov/cip/bidopps/index.shtml

#### A. CHANGES TO CONTRACT DOCUMENTS

The following changes to the Contract Documents are hereby made effective as though originally issued with the bid package. Bidders are reminded that all previous requirements to this solicitation remain in full force and effect.

#### B. BIDDER's QUESTIONS

- Q1. Will concrete truck be allowed to drive on the bridge?
- A1. Maximum allowable live load on the bridge is 215 PLF per Record Drawings. Any operations on the bridge shall adhere to this maximum loading condition. Record Drawings are available for reference in the following link: <u>https://filecloud.sandiego.gov/url/1901a</u>
- Q2. The 4" repaired expansion joint in the sidewalk and curb area may present a trip hazard unless properly addressed/covered. Has the city considered a cover of some kind? If so, please provide those details.
- A2. The strip seal shall be ADA compliant per plan details and a cover is not necessary.
- Q3. Is there a detail to add the new pole to the existing guardrail concrete, ie: bolt hole diameter, depth, bonding material, strength, special inspections?
- A3. See pole specifications on E-4. Existing pole specifications shall be field verified and the new pole shall match the existing. Inspection shall be per contract documents. Record Drawings are available for reference in the following link: <u>https://filecloud.sandiego.gov/url/1901a</u>
- Q4. Same Question for electrical conduit, hole size, dry packing, hole penetration direction etc?
- A4. Existing conduit sizes and approximate conduit directions are provided on plans and details are to be field verified. Record Drawings are available for reference in the following link: <u>https://filecloud.sandiego.gov/url/1901a</u>

James Nagelvoort, Director Public Works Department

Dated: *April 30, 2020* San Diego, California JN/EW/rd