SHEET INDEX

- MECHANICAL LEAD SHEET MECHANICAL LEAD SHEET CONT. M0.03 MECHANICAL SCHEDULES
- M1.00 MECHANICAL DEMOLITION OVERALL PLAN
- MECHANICAL DEMOLITION PLAN
- MECHANICAL OVERALL PLAN MECHANICAL PLAN
- MECHANICAL HEATING HOT WATER PIPING PLAN M2.02
- M3.01 MECHANICAL ENLARGED PLANS MECHANICAL ENLARGED PLANS CONT.
- M3.03 MECHANICAL ENLARGED PLANS CONT.
- M5 01 MECHANICAL DETAILS M5.02 MECHANICAL DETAILS CONT
- CONTROLS SYSTEM ARCHITECTURE M6.02 **CONTROLS**
- M6.03 CONTROLS CONT. CONTROLS CONT. M6.04
- MECHANICAL SHEET SPECIFICATIONS M7.02
- MECHANICAL SHEET SPECIFICATIONS CONT MECHANICAL SHEET SPECIFICATIONS CONT. TITLF 24

M7.05 TITLE 24 CONT.

DEMOLITION NOTES

- 1. THE MECHANICAL DRAWINGS ARE DIAGRAMMATIC ONLY. DO NOT SCALE THE DRAWINGS TO DETERMINE THE LOCATION OF EQUIPMENT OR UTILITIES. SEE ARCHITECTURAL PLANS, WHERE PROVIDED ON PROJECT, FOR EXTENT OF DEMOLITION.
- 2. ITEMS NOT INDICATED TO BE REMOVED SHALL BE PROTECTED IN PLACE.
- OWNER SHALL HAVE FIRST RIGHT OF REFUSAL FOR ALL ITEMS INDICATED TO BE REMOVED. PENDING OWNER'S INSPECTION AND REVIEW, ALL SUCH ITEMS SHALL BE REMOVED INTACT, FULLY FUNCTIONAL AND SUITABLE FOR REUSE, AND SHALL BE PROTECTED FROM DAMAGE. CONTRACTOR SHALL CONFIRM WITH THE OWNER'S REPRESENTATIVE ACCEPTANCE OR REFUSAL OF SUCH ITEMS. ALL ITEMS ACCEPTED BY THE OWNER SHALL BE DELIVERED BY THE CONTRACTOR TO ONSITE STORAGE LOCATIONS AS DIRECTED BY THE OWNER'S REPRESENTATIVE. ALL ITEMS REFUSED BY THE OWNER SHALL BE DISPOSED OF BY THE CONTRACTOR IN AN APPROVED MANNER.
- 4. NO EXISTING EQUIPMENT OR MATERIAL SHALL BE REUSED WITHOUT THE SPECIFIC APPROVAL OF THE OWNER'S REPRESENTATIVE.
- 5. REMOVAL OF CERTAIN EXISTING WORK WILL BE NECESSARY FOR THE SATISFACTORY PERFORMANCE OF THE GENERAL WORK. NOT ALL EXISTING CONDITIONS ARE DETAILED ON THE DRAWINGS. CONTRACTOR SHALL SURVEY THE SITE AND MAKE ALL NECESSARY CHANGES REQUIRED BASED ON THE EXISTING CONDITIONS FOR THE PROPER INSTALLATION OF NEW WORK.
- 6. REMOVE AND/OR RELOCATE EXISTING FIXTURES AND EQUIPMENT AS INDICATED. EXISTING HOT WATER, COLD WATER, GAS AND/OR VENT PIPING SERVING SUCH ITEMS SHALL BE REMOVED TO A SUITABLE CONCEALED LOCATION WITHIN EXISTING TO REMAIN WALL OR ABOVE CEILING AND CAPPED WATERTIGHT. SOIL/WASTE PIPING SERVING SUCH FIXTURES SHALL BE REMOVED TO A SUITABLE CONCEALED LOCATION BELOW FINISHED FLOOR OR WITHIN EXISTING TO REMAIN WALL AND CAPPED WATERTIGHT.
- UNLESS NOTED OTHERWISE, EXISTING PIPING AND COMPONENTS RENDERED DEFUNCT AS PART OF THIS PROJECT SHALL BE ADDRESSED IN THE FOLLOWING MANNER: DEFUNCT PIPING LOCATED IN CONCEALED AREAS WITHIN EXISTING TO REMAIN WALLS, BELOW SLAB, OR BELOW GRADE SHALL BE ABANDONED IN PLACE OR REMOVED AS NECESSARY TO AVOID INTERFERENCE WITH NEW WORK. EXISTING DEFUNCT PIPING AND COMPONENTS LOCATED IN EXPOSED AREAS AND IN ATTIC SPACE SHALL BE REMOVED TO THE NEAREST OPERATIONAL PIPING MAIN AND CAPPED, INCLUDING ALL ASSOCIATED HANGERS AND STRUCTURAL SUPPORTS. EXISTING DEFUNCT VENTS THROUGH ROOF SHALL BE CAPPED ABOVE ROOF.
- CONTRACTOR SHALL FIELD VERIFY EXISTING PIPING & DUCT RUNS, REUSE AS REQUIRED AND REMOVE ALL UNUSED DUCT AND PIPING. UNUSED PIPING & DUCT IN INACCESSIBLE LOCATIONS (WALLS/SHAFTS TO CAN BE ABANDONED IN PLACE
- THE EXISTING CONDITIONS SHOWN ARE FROM AVAILABLE RECORD DRAWINGS AND SHOWN FOR REFERENCE CONTRACTOR SHALL VERIFY ACTUAL EXISTING CONDITIONS AT SITE PRIOR TO SUBMITTING BID. ALL DEMOLITION, ALTERATION, EXTENSION, RELOCATION, REHABILITATION WORK SHALL BE INCLUDED IN CONTRACT. NO ADDITIONAL ALLOWANCE OR CHANGE ORDERS WILL BE ACCEPTED.
- CONTRACTOR IS RESPONSIBLE TO RELOCATE OR REMOVE FROM WALLS, CEILINGS, FLOOR SPACES, ETC. ANY EXISTING PIPING, DUCT, FIRE-SMOKE DAMPERS, OR OTHER MECHANICAL EQUIPMENT WHICH INTERFERES WITH PLANNED REMODEL WORK.
- 11. NOTIFY THE ENGINEER IMMEDIATELY WHEREVER EXISTING EQUIPMENT IS ENCOUNTERED WHICH MUST BE RELOCATED DUE TO THE NEW CONSTRUCTION, OR NOT INDICATED ON "AS-BUILT" DRAWINGS OR WAS BURIED UNDERGROUND OR EMBEDDED IN STRUCTURE WALLS.
- 12. CAREFULLY PROTECT ALL WALLS, TRIM, FLOORS, EQUIPMENT, UTILITY LINES AND MATERIALS. WHEN WORKING ON FINISHED SURFACES, LIMIT DAMAGE TO THE SMALLEST AREA POSSIBLE AND RESTORE TO THE ORIGINAL CONDITION ALL SURFACES WHICH ARE DAMAGED BECAUSE OF THE INSTALLATION OF THIS WORK.
- 13. EQUIPMENT, MATERIALS AND SUPPLIES TEMPORARILY REMOVED FOR PROTECTION SHALL BE REPLACED IN ORIGINAL LOCATIONS. ANY MATERIALS DAMAGED SHALL BE REPLACED WITH NEW MATERIALS OF LIKE KIND AND QUALITY.
- 14. DEMOLITION WORK SHALL BE DONE IN A MANNER WHICH WILL NOT CAUSE UNNECESSARY INCONVENIENCE OR DANGER TO USERS OF THE PREMISES AND ADJACENT SITE, AND NOT INTERFERE WITH ITS OPERATION. ANY DEMOLITION WORK TO BE PERFORMED MUST BE PLANNED IN ADVANCE.
- 15. RESEAL ALL PENETRATIONS OR OPENING THROUGH WALLS, CEILING, FLOORS, ETC., TO MAINTAIN THE RATING OF STRUCTURE.
- 16. ALL REMOVED MATERIALS AND EQUIPMENT WHICH ARE SALVAGED MATERIALS SHALL REMAIN IN THE PROPERTY OF THE OWNER. DELIVER SUCH SALVAGED MATERIALS AND EQUIPMENT ON THE PREMISES AS DIRECTED BY OWNER AND NEATLY PILE OR STORE AND PROTECT FROM DAMAGE. DISPOSE OF ALL HAZARDOUS MATERIAL PER FEDERAL, 3. VIBRATION & SEISMIC DELEGATED-DESIGN SUBMITTALS: FOR EACH VIBRATION STATE AND LOCAL REGULATIONS AND OTHER AGENCIES HAVING JURISDICTION.
- 17. ALL DEMOED, ALTERED AND RELOCATED COMPONENTS SHALL BE REFLECTED ON THE AS-BUILT RECORD DOCUMENTS.

CAL GREEN NOTES

- HVAC. REFRIGERATION AND FIRE SUPPRESSION EQUIPMENT SHALL NOT CONTAIN CFC'S OR HALONS. (CALGREEN 5.508.1)
- 2. PROVIDE MERV 8 (OR BETTER) FILTRATION FOR MECHANICALLY VENTILATED SPACES, OUTSIDE AIR, AND RETURN AIR. (CALGREEN 5.504.5.3)
- 3. CALGREEN COMMISSIONING IS ONLY REQUIRED FOR NEW BUILDINGS 10,000SF AND GREATER. (CALGREEN 5.410.2)
- ALL ENVELOPE AND MECHANICAL CERTIFICATE OF ACCEPTANCE FORMS AND ALL RELATED ACCEPTANCE DOCUMENTS SHALL BE SUBMITTED TO THE FIELD INSPECTOR DURING CONSTRUCTION. CERTIFICATE OF OCCUPANCY WILL NOT BE ISSUED UNTIL THESE FORMS ARE REVIEWED AND APPROVED. PER CALGREEN 5.714.4
- PERMANENT HVAC SYSTEMS SHALL ONLY BE USED DURING CONSTRUCTION IF NECESSARY TO CONDITION THE BUILDING WITHIN THE REQUIRED TEMPERATURE RANGE FOR MATERIAL AND EQUIPMENT INSTALLATION. IF THE HVAC SYSTEM IS USED DURING CONSTRUCTION. USE RETURN AIR FILTERS WITH A MINIMUM EFFICIENCY REPORTING VALUE (MERV) OF 8, BASED ON ASHRAE 52.2 1999, OR AN AVERAGE EFFICIENCY OF 30% BASED ON ASHRAE 52.1 1992. REPLACE ALL FILTERS IMMEDIATELY PRIOR TO OCCUPANCY.
- DURING CONSTRUCTION (AT TIME OF INSTALLATION AND WHILE BEING STORED ON SITE) AND UNTIL FINAL STARTUP OF HEATING AND COOLING EQUIPMENT, ENDS OF DUCT OPENINGS ARE TO BE SEALED, AND MECHANICAL EQUIPMENT IS TO BE COVERED PER CALGREEN SECTION 5.714.4.3.
- ALL ADHESIVES, SEALANTS, CAULKS, PAINTS AND COATINGS, AEROSOL PAINTS AND COATINGS SHALL COMPLY WITH VOC LIMITS PER CALGREEN 5.714.4.4.1.

EQUIPMENT ANCHORAGE AND SYSTEM BRACING

- 1. ALL MECHANICAL, PLUMBING, AND ELECTRICAL COMPONENTS SHALL BE ANCHORED AND INSTALLED PER THE DETAILS ON THE APPROVED CONSTRUCTION DOCUMENTS. WHERE NO DETAIL IS INDICATED, THE FOLLOWING COMPONENTS SHALL BE ANCHORED OR BRACED TO MEET THE FORCE AND DISPLACEMENT REQUIREMENTS PRESCRIBED IN THE 2016 CALIFORNIA BUILDING CODE REQUIREMENTS IN ACCORDANCE WITH THE AMERICAN SOCIETY OF CIVIL ENGINEERS - ASCE 7-10, SECTION 13.6 AND TABLE 13.6-1.
 - a. ALL PERMANENT EQUIPMENT AND COMPONENTS.
- b. TEMPORARY OR MOVABLE EQUIPMENT THAT IS PERMANENTLY ATTACHED (E.G. HARD WIRED) TO THE BUILDING UTILITY SERVICE SUCH AS ELECTRICITY, GAS OR WATER.
- c. MOVABLE EQUIPMENT WHICH IS STATION IN ONE PLACE FOR MORE THAN 8 HOURS AND HEAVIER THAN 400 POUNDS ARE REQUIRED TO BE ANCHORED WITH TEMPORARY ATTACHMENTS.
- THE FOLLOWING MECHANICAL AND ELECTRICAL COMPONENTS SHALL BE POSITIVELY ATTACHED TO THE STRUCTURE, BUT THE ATTACHMENT NEED NOT TO BE DETAILED ON PLAN. THESE COMPONENTS SHALL HAVE FLEXIBLE CONNECTIONS PROVIDED BETWEEN THE COMPONENT AND ASSOCIATED DUCTWORK, PIPING AND CONDUIT.
 - a. COMPONENTS WEIGHING LESS THAN 400 POUNDS AND HAVE A CENTER OF MASS LOCATED 4 FEET OR LESS ABOVE THE ADJACENT FLOOR OR ROOF LEVEL THAT DIRECTLY SUPPORT THE
 - b. COMPONENTS WEIGHING LESS THAN 20 POUNDS, OR IN THE CASE OF DISTRIBUTED SYSTEMS, LESS THAN 5 POUNDS PER FOOT, WHICH ARE SUSPENDED FROM A ROOF OR FLOOR HUNG FROM WALL.
- FOR THOSE ELEMENTS THAT DO NOT REQUIRE DETAILS ON THE APPROVED DRAWINGS, THE INSTALLATION SHALL BE INSTALLED PER SMACNA GUIDELINES AND/OR MANUFACTURER'S
- SEISMIC ANCHORAGE OF EQUIPMENT AND BRACING OF PIPING/DUCTWORK SYSTEMS SHALL BE PROVIDED IN ACCORDANCE WITH THE AMERICAN SOCIETY OF CIVIL ENGINEERS - ASCE 7-10, SECTION 13.6 AND TABLE 13.6-1.

APPLICABLE CODES

- 2019 CALIFORNIA BUILDING CODE
- 2019 CALIFORNIA MECHANICAL CODE 2019 CALIFORNIA PLUMBING CODE
- 2019 CALIFORNIA ELECTRICAL CODE
- 2019 CALIFORNIA FIRE CODE
- 2019 CALIFORNIA ENERGY STANDARDS
- 2019 CAL GREEN CODE ALL OTHER APPLICABLE LOCAL AND STATE LAWS AND REGULATIONS

DELEGATED DESIGN NOTES

- 1. THERMAL EXPANSION DELEGATED-DESIGN SUBMITTALS: FOR EACH ANCHOR AND ALIGNMENT GUIDE, INCLUDING ANALYSIS DATA, SIGNED AND SEALED BY THE QUALIFIED PROFESSIONAL ENGINEER RESPONSIBLE FOR THEIR PREPARATION.
- 1.1. DESIGN CALCULATIONS: CALCULATE REQUIREMENTS FOR THERMAL EXPANSION OF PIPING SYSTEMS AND FOR SELECTING AND DESIGNING EXPANSION JOINTS, LOOPS, AND SWING CONNECTIONS.
- 1.2. ANCHOR DETAILS: DETAIL FABRICATION OF EACH ANCHOR INDICATED. SHOW DIMENSIONS AND METHODS OF ASSEMBLY AND ATTACHMENT TO BUILDING STRUCTURE
- 1.3. ALIGNMENT GUIDE DETAILS: DETAIL FIELD ASSEMBLY AND ATTACHMENT TO
- BUILDING STRUCTURE. 1.4. SCHEDULE: INDICATE TYPE, MANUFACTURER'S NUMBER, SIZE, MATERIAL.
- PRESSURE RATING, END CONNECTIONS, AND LOCATION FOR EACH EXPANSION
- HANGERS & SUPPORTS DELEGATED-DESIGN SUBMITTALS: FOR HANGERS, TRAPEZE HANGERS, ROOF/FLOOR SUPPORTS, WALL SUPPORTS, AND EQUIPMENT SUPPORTS FOR HVAC PIPING, DUCTWORK, AND EQUIPMENT SHALL COMPLY WITH PERFORMANCE REQUIREMENTS AND DESIGN CRITERIA, INCLUDING ANALYSIS DATA SIGNED AND SEALED BY THE QUALIFIED PROFESSIONAL ENGINEER RESPONSIBLE FOR THEIR PREPARATION.
- 2.1. DETAIL FABRICATION AND ASSEMBLY OF HANGERS. TRAPEZE HANGERS. ROOF/FLOOR SUPPORTS, WALL SUPPORTS, AND EQUIPMENT SUPPORTS FOR HVAC PIPING, DUCTWORK, AND EQUIPMENT.
- 2.2. INCLUDE DESIGN CALCULATIONS FOR DESIGNING HANGERS, TRAPEZE HANGERS, ROOF/FLOOR SUPPORTS, WALL SUPPORTS, AND EQUIPMENT SUPPORTS FOR HVAC PIPING, DUCTWORK, AND EQUIPMENT.
- ISOLATION AND SEISMIC-RESTRAINT DEVICE.
- 3.1. INCLUDE DESIGN CALCULATIONS AND DETAILS FOR SELECTING VIBRATION ISOLATORS, SEISMIC RESTRAINTS, AND VIBRATION ISOLATION BASES COMPLYING WITH PERFORMANCE REQUIREMENTS, DESIGN CRITERIA, AND ANALYSIS DATA
- SIGNED AND SEALED BY THE QUALIFIED PROFESSIONAL ENGINEER RESPONSIBLE FOR THE PREPARATION. 3.2. DESIGN CALCULATIONS: CALCULATE STATIC AND DYNAMIC LOADING DUE TO EQUIPMENT WEIGHT, OPERATION, AND SEISMIC FORCES REQUIRED TO SELECT VIBRATION ISOLATORS AND SEISMIC RESTRAINTS AND FOR DESIGNING VIBRATION
- ISOLATION BASES. COORDINATE DESIGN CALCULATIONS WITH WIND LOAD CALCULATIONS 3.2.1. REQUIRED FOR EQUIPMENT MOUNTED OUTDOORS. COMPLY WITH
- REQUIREMENTS IN OTHER SECTIONS FOR EQUIPMENT MOUNTED OUTDOORS. RISER SUPPORTS: INCLUDE RISER DIAGRAMS AND CALCULATIONS SHOWING ANTICIPATED EXPANSION AND CONTRACTION AT EACH SUPPORT POINT, INITIAL AND FINAL LOADS ON BUILDING STRUCTURE, SPRING DEFLECTION CHANGES, AND SEISMIC LOADS. INCLUDE CERTIFICATION THAT RISER SYSTEM WAS EXAMINED FOR EXCESSIVE STRESS AND THAT NONE EXISTS.
- 3.4. SEISMIC-RESTRAINT DETAILS: 3.4.1. DESIGN ANALYSIS: TO SUPPORT SELECTION AND ARRANGEMENT OF SEISMIC RESTRAINTS. INCLUDE CALCULATIONS OF COMBINED TENSILE AND SHEAR
- DETAILS: INDICATED FABRICATION AND ARRANGEMENT. DETAIL ATTACHMENTS OF RESTRAINTS TO THE RESTRAINED ITEMS AND TO THE STRUCTURE. SHOW ATTACHMENT LOCATIONS, METHODS, AND SPACINGS. IDENTIFY COMPONENTS, LIST THEIR STRENGTHS, AND INDICATE DIRECTIONS AND VALUES OF FORCES TRANSMITTED TO THE STRUCTURE DURING SEISMIC EVENTS. INDICATE ASSOCIATION WITH VIBRATION ISOLATION DEVICES.
- COORDINATE SEISMIC-RESTRAINT AND VIBRATION ISOLATION DETAILS WITH WIND-RESTRAINT DETAILS REQUIRED FOR EQUIPMENT MOUNTED OUTDOORS, COMPLY WITH REQUIREMENTS IN OTHER SECTIONS FOR EQUIPMENT MOUNTED OUTDOORS.
- PREAPPROVAL AND EVALUATION DOCUMENTATION: BY AN AGENCY ACCEPTABLE TO AUTHORITIES HAVING JURISDICTION, SHOWING MAXIMUM RATINGS OF RESTRAINT ITEMS AND THE BASIS OF APPROVAL (TESTS OR CALCULATIONS).

MECHANICAL GENERAL NOTES

- 1. ALL DRAWINGS ARE CONSIDERED TO BE PART OF THE CONTRACT DOCUMENT. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE REVIEW AND COORDINATION OF ALL DRAWINGS PRIOR TO ANY CONSTRUCTION, INCLUDING STRUCTURAL, PLUMBING, AIR CONDITIONING AND ELECTRICAL. ANY DISCREPANCIES THAT OCCUR SHALL BE BROUGHT TO THE ATTENTION OF THE ENGINEER PRIOR TO THE START OF CONSTRUCTION SO THAT A CLARIFICATION CAN BE ISSUED. ANY WORK PERFORMED IN CONFLICT WITH THE CONTRACT DOCUMENTS OR ANY CODE REQUIREMENT SHALL BE CORRECTED BY THE CONTRACTOR AT HIS OWN EXPENSE, AND AT NO EXPENSE TO THE OWNER.
- ALL SYMBOLS AND ABBREVIATIONS USED ON THE DRAWINGS ARE CONSIDERED TO BE CONSTRUCTION STANDARDS. IF CLARIFICATION IS REQUIRED, THE CONTRACTOR SHALL NOTIFY ENGINEER PRIOR TO PROCEEDING WITH THE WORK.
- DO NOT SCALE DRAWINGS. ALL DIMENSIONS AND JOB SITE CONDITIONS SHALL BE VERIFIED BY THE CONTRACTOR AT THE JOB SITE PRIOR TO BID SUBMITTAL, START OF CONSTRUCTION AND/OR FABRICATION OF MATERIALS. IF DISCREPANCIES ARE ENCOUNTERED, THE ENGINEER SHALL BE NOTIFIED FOR CLARIFICATION.
- THE CONTRACTOR SHALL FURNISH ALL MATERIALS, LABOR, EQUIPMENT, TRANSPORTATION AND SERVICES NECESSARY FOR COMPLETION OF THE WORK AND PROVIDE A FULLY OPERATIONAL SYSTEM. ALL MATERIALS AND WORK SHALL COMPLY WITH APPLICABLE CODES AND GOVERNING REGULATIONS AND MEET THE APPROVAL OF THE CITY AND STATE FIRE MARSHALL.
- CONTRACTOR SHALL PROVIDE AND BE RESPONSIBLE FOR PROTECTION AND REPAIR OF ADJACENT EXISTING SURFACES AND AREAS WHICH MAY BE DAMAGED AS A RESULT OF DEMOLITION AND/OR NEW WORK.
- ALL EQUIPMENT THAT IS REMOVED AND NOT REUSED SHALL BE COORDINATED WITH, AND/OR RETURNED TO, THE BUILDING OWNER.
- 7. ALL EXISTING DUCT TAPS THAT ARE REMOVED AND NOT REUSED SHALL BE CAPPED AIRTIGHT AND SEALED WITH "MIRACLE" DUCT SEALER AND D-617 OR EQUAL.
- VERIFY FINAL LOCATION OF THERMOSTATS WITH ARCHITECT AND/OR TENANT CONSTRUCTION COORDINATOR PRIOR TO ANY INSTALLATION WORK.
- 9. CONTRACTOR SHALL PROVIDE RECORD/AS BUILT DOCUMENTS TO CONSTRUCTION COORDINATOR, ARCHITECT AND ENGINEER AT COMPLETION OF CONSTRUCTION.
- 10. MAINTAIN NET FREE AREA EQUAL TO DUCT SIZE WHERE FIRE DAMPERS OCCUR.
- 11. ROOM THERMOSTATS SHALL BE CAPABLE OF BEING SET TO MAINTAIN SPACE TEMPERATURE SET POINTS FOR 55° F TO 85° F AND SHALL BE CAPABLE OF OPERATING THE HEATING AND COOLING IN SEQUENCE. THERMOSTATS SHALL BE ADJUSTABLE TO PROVIDE A TEMPERATURE RANGE OF UP TO 5° F BETWEEN FULL HEATING AND FULL COOLING BEING SUPPLIED. TEMPERATURE CONTROL SYSTEM SHALL OPERATE IN
- 12. PROVIDE MINIMUM DUCT RADIUS ON ELBOWS AT 1-1/2 TIMES DUCT SIZE.

ACCORDANCE WITH THE BASE BUILDING SEQUENCE OF OPERATION

- 13. ALL CEILING DIFFUSERS ARE 4-WAY THROW UNLESS NOTED OTHERWISE. 13.1. DIFFUSERS SHALL BE ADJUSTED BY MECHANICAL CONTRACTOR AND/OR TEST & BALANCE CONTRACTOR FROM 4-WAY TO 3-WAY OR 2-WAY WHEN WITHIN 3'-0" OF ADJACENT WALL OR CORNER. SUBMIT PROPOSED ADJUSTMENTS IN WRITING PRIOR
- 14. CONTRACTOR SHALL STRICTLY COORDINATE ALL CEILING DIFFUSERS AND GRILLES WITH ARCHITECTURAL REFLECTED CEILING PLAN. IF ANY DISCREPANCIES ARE ENCOUNTERED THE ENGINEER SHALL BE NOTIFIED FOR CLARIFICATION. VERIFY WITH OWNERS REPRESENTATIVE IN FIELD PRIOR TO INSTALLATION.
- 15. RETURN AIR PLENUM SHALL NOT CONTAIN ANY COMBUSTIBLES.

TO ADJUSTING

- 16. MATERIALS EXPOSED WITHIN DUCT OR PLENUM SHALL COMPLY WITH SECTION 602.2 OF THE 2016 CMC. ALL MATERIALS EXPOSED WITHIN THE CEILING PLENUM SHALL HAVE A FLAME-SPREAD INDEX OF NOT MORE THAN 25 AND A SMOKE DEVELOPED RATING OF NOT MORE THAN 50.
- 17. PROVIDE SMOKE DETECTORS IN MAIN SUPPLY AIR DUCTS OF AIR MOVING SYSTEMS EXCEEDING 2,000 CFM AND COMBINATION OF SYSTEMS SERVING AREAS PERMANENTLY OPEN TO EACH OTHER WHOSE COMBINED SUPPLY AIR EXCEEDS 2,000 CFM PER SECTION 608.0 CMC
- 19. HEATING HOT WATER PIPING SHALL BE INSTALLED AS HIGH AS POSSIBLE.
- 20. THE CONTRACTOR SHALL COORDINATE ALL CEILING ACCESS PANELS FOR SERVICING MECHANICAL EQUIPMENT/DEVICES WITH THE ARCHITECT AND INTERIOR DESIGNER AS
- 1. PRIOR TO ROUGH-IN OF ELECTRICAL. PROVIDE COORDINATION SHOP DRAWINGS OF T-STAT LOCATIONS TO ARCH./ENG. FOR REVIEW.
- 22. DUCT SEALING:
- 22.1. DUCTWORK SHALL BE SEALED PRIOR TO DELIVERY TO JOB SITE. 22.2. DUCTWORK SHALL BE SEALED DURING DELIVERY.
- 22.3. DUCTWORK SHALL BE SEALED UPON INSTALLATION. 22.4. OPENINGS INTO EQUIPMENT AND DUCTWORK SHALL BE SEALED DURING CONSTRUCTION.
- 23. ALL CONTROL WIRING ROUTED IN CEILING PLENUM SHALL BE CLEARLY IDENTIFIED & SECURED TO DUCTWORK OR TIGHT TO STRUCTURE TO PREVENT DAMAGE DURING FUTURE TENTANT IMPROVEMENT PROJECTS.
- 24. THE CONTRACTOR SHALL VERIFY ALL DIFFUSER/GRILLE/REGISTER/BORDER AND FRAME TYPES WITH THE ARCHITECTURAL REFLECTED CEILING PLAN PRIOR TO ORDERING. COORDINATE ALL FINISHES WITH ARCHITECT.
- 25. ALL HVAC SYSTEMS INCLUDING HYDRONIC SYSTEMS SHALL BE BALANCED IN ACCORDANCE WITH AN APPROVED METHOD PER THE CMC SECTION 314.1, CALGREEN AND THE ENERGY EFFICIENCY STANDARDS.
- 26. THROUGH-PENETRATIONS AND MEMBRANE PENETRATIONS SHALL BE PROTECTED BY AN APPROVED PENETRATION FIRESTOP SYSTEM OR MEMBRANE PENETRATION FIRESTOP SYSTEM INSTALLED AS TESTED IN ACCORDANCE WITH ASTM E 814 OR UL 1479, WITH MINIMUM POSITIVE PRESSURE DIFFERENTIAL OF 0.01 INCH (2.49 PA) OF WATER OR AS OTHERWISE PERMITTED BY CBC, SECTION 714. LISTED THROUGH-PENETRATION FIRESTOP SYSTEMS AND MEMBRANE PENETRATIONS SHALL BE INSTALLED IN ACCORDANCE WITH THE INSTALLATION FOR DETAILS LISTED SYSTEMS. LISTED THROUGH-PENETRATION FIRESTOP SYSTEMS. MEMBRANE PENETRATION PROTECTION AND OTHER PERMITTED MEANS AND METHODS OF PENETRATION PROTECTION SHALL BE SUBMITTED FOR OSHPD FDD REVIEW AND APPROVAL PRIOR TO INSTALLATION.
- 27. PROVIDE BALANCING VOLUME DAMPERS IN EACH BRANCH DUCT AND IN EACH MAIN DUCT TO PROVIDE FOR COMPLETE AIR BALANCING. PROVIDE ADEQUATE ACCESS. OPPOSED BLADE DAMPERS (OBD'S) ARE NOT CONSIDERED BALANCING DAMPERS. COORDINATE ALL LOCATIONS WITH ARCHITECT'S REFLECTED CEILING PLAN WHERE REMOTE BALANCING DAMPERS ARE REQUIRED.
- 28. PROVIDE INTERNALLY LINED DUCTWORK FOR SUPPLY AND RETURN AIR PLENUMS ON ALL FAN COILS WITH MINIMUM ONE-INCH THICK ACOUSTICAL DUCT LINER.
- 29. INSTALL DIELECTRIC INSULATION WHERE COPPER PIPES CONNECT TO FERROUS PIPES, COMPONENTS AND EQUIPMENT.

Members Area Renovation

1500 Orange Avenue Coronado, CA 92118



González Architects Hospitality

Mechanical/Electrical/Plumbing Engineer tk1sc Collaborative 4755 Eastgate Mall, Suite 150 858.362.6800



15231 Laguna Canyon Road, Suite 100

Irvine, California 92618

949.751.5800 www.tk1sc.com Project Leader - Kenneth McClendon Mechanical Lead - Kenneth McClendor tk1sc Job #: 2019-0727



14 NE 1st Avenue, Suite 507 T+1 (305) 455 4216

∆ 01-05-22 Owner Revisions

MECHANICAL LEAD

09-17-2021 Drawn By Project No. Drawing No.

HV	AC LEGEND
SYMBOL	DESCRIPTION
	GENERAL
	LIMIT OF DEMOLITION
•	POINT OF CONNECTION
XY.ZZZ	KEYNOTE
M	FURNISHED & INSTALLED BY MECHANICAL
ME	FURNISHED BY MECHANICAL INSTALLED BY ELECTRICAL
EM	FURNISHED BY ELECTRICAL INSTALLED BY MECHANICAL
E	FURNISHED & INSTALLED BY ELECTRICAL
(RAR/EAR)	SUPPLY, RETURN, & EXHAUST REGISTER - NECK SIZE - AIR QUANTITY (C.F.M.)
(REAG)	RELIEF AIR GRILLE - NECK SIZE - AIR QUANTITY (CFM)
	LINEAR SUPPLY & RETURN -# OF SLOTS — SLOT WIDTH -CFM/FT -TOTAL LENGTH (FT)

	L1\/	AC LEGEND CONT.	1	Λ D [BREVIA	TIONS		BREVIATIONS CONT.
	П۷	AC LEGEND CONT.	4			· · · · - · · -	ADI	
_		PIPING	A/C	AIR CONDITIONING	EXH	EXHAUST	Т	THERMOSTAT OR THERMOMETER OR THROAT
_		PIPE TAG (E.G. 2"-CHWS)	ABV	ABOVE	FC	FLEXIBLE CONNECTION OR FAIL CLOSED	TCP	TEMPERATURE CONTROL PANEL
	\bigcirc	PIPE RISE	ACCEPT	ACCEPTANCE	FCU	FAN COIL UNIT	TDH	TOTAL DYNAMIC HEAD
		PIPE DROP PIPE BRANCH	ACU	AIR CONDITIONING UNIT	FD	FIRE DAMPER	TEMP	TEMPERATURE
		GATE VALVE	ADA	ACCESS DOOR	FF	FINISH FLOOR OR FINAL FILTER	THRU	THROUGH
	\longrightarrow	GLOBE VALVE	ADA ADD	AMERICANS WITH DISABILITIES ACT ADDITION	HWP	HEATING WATER PETURN	SQ FT	SQUARE FEET
	-	CHECK VALVE	AFF	ABOVE FINISH FLOOR	HWS	HEATING WATER RETURN HEATING WATER SUPPLY	SQ IN	SQUARE INCH
	─ ó─	BALL VALVE	AFF AHJ	AUTHORITY HAVING JURISDICTION	HX	HEAT EXCHANGER	ST	STRAINER OR SOUND TRAP OR STEAM TRAP
	—ф—	BUTTERFLY VALVE	AHU	AIR HANDLING UNIT	ID	INSIDE DIAMETER	STRUC	STANDARD STRUCTURAL
	<u> </u>	CIRCUIT SETTER	AP	ACCESS PANEL	IE IE	INVERT ELEVATION	TI	TENANT IMPROVEMENT
		REDUCER	APPROX	APPROXIMATE	IN	INCH	ТОР	TOP OF DUCT
-		STRAINER	ARCH	ARCHITECTURAL	IW	INDUSTRIAL WASTE	TS	TEMPERATURE SENSOR
	——————————————————————————————————————	UNION	ARI	AMERICAN REFRIGERATION INSTITUTE		LENGTH	TSP	TOTAL STATIC PRESSURE
$\overline{}$	<u> </u>	AIR VENT VALVE	AS	AIR SEPARATOR	LBS	POUNDS	TYP	TYPICAL
_	<u> </u>	PRESSURE GAUGE THERMOMETER	ASTM	AMERICAN SOCIETY FOR TESTING AND MATERIALS	LP	LOW PRESSURE	UC	UNDERCUT DOOR
	<u> </u>	CONTROL VALVE	AUTO	AUTOMATIC	LPC	LOW PRESSURE CONDENSATE	UG	UNDERGROUND
		PRESSURE REDUCING VALVE	AUX	AUXILIARY	LPS	LOW PRESSURE STEAM	UH	UNIT HEATER
		PRESSURE & TEMPERATURE RELIEF VALVE	AV	AIR VENT	М	MOTOR	UNO	UNLESS NOTED OTHERWISE
	X	PIPE ANCHOR	В	BOILER	MA	MIXED AIR	UTR	UP THRU ROOF
			BAS	BUILDING AUTOMATION SYSTEM	MAU	MAKEUP AIR	V	VENT
		DUCTWORK	BDD	BACKDRAFT DAMPER	MAX	MAXIMUM	VAV	VARIABLE AIR VOLUME
	<u> </u>	REMOVE EXIST. EQUIP., PIPES, OR DUCT SHOWN HATCHED	BFF	BELOW FINISH FLOOR	MC	MECHANICAL CONTRACTOR	VD	VOLUME DAMPER
		EXIST. DIFFUSER, RETURN AIR GRILLE OR EXHAUST GRILLE TO	BLDG	BUILDING	MCC	MOTOR CONTROL CENTER	VEL	VELOCITY
		BE REMOVED	BOD	BOTTOM OF DUCT	MECH	MECHANICAL	VFD	VARIABLE FREQUENCY DRIVE
		RELOCATED EXIST. DIFFUSER, RETURN AIR GRILLE OR	ВОР	BOTTOM OF PIPE	MIN	MINIMUM	W/	WITH
		EXHAUST GRILLE TO	BSMT	BASEMENT	MPC	MEDIUM PRESSURE CONDENSATE	W/O	WITHOUT
	KN KN KN KN KN KN	EXIST. DIFFUSER, RETURN AIR GRILLE OR EXHAUST GRILLE TO	BV	BALL VALVE	MPS	MEDIUM PRESSURE STEAM	WG	WATER GAUGE
		REMAIN OR BE RELOCATED	BYV	BUTTERFLY VALVE	MV	MANUAL AIR VENT	WMS	WIRE MESH SCREEN
		EXIST. MECHANICAL EQUIPMENT & DUCT	_	COMMON, CONDENSATE OR CONDUIT	(N)	NEW	WPD	WATER PRESSURE DROP
	<u> </u>	EXIST. DUCTWORK TO BE REMOVED & CAPPED	CA	CONTROL AIR, or COMBUSTION AIR	N/A	NOT APPLICABLE	WSHP	WATER SOURCE HEAT PUMP
		LINEAR DIFFUSER	CAC	CALIFORNIA ADMINISTRATIVE CODE	NC	NORMALLY CLOSED	WT	WEIGHT
		SUPPLY AIR	CAP	CAPACITY	NO	NORMALLY OPENED	XFMR	TRANSFORMER
			CAV	CONSTANT AIR VOLUME	NFPA	NATIONAL FIRE PROTECTION ASSOCIATION	FFE	FINISH FLOOR ELEVATION
		RETURN AIR	СВ	CHILLED BEAM	NIC	NOT IN CONTRACT	FLR	FLOOR
			СВС	CALIFORNIA BUILDING CODE	NTS	NOT TO SCALE	FPB	FAN POWERED BOX
		EXHAUST AIR	СС	COOLING COIL OR CONTROLS CONTRACTOR	OA	OUTSIDE AIR	FR	FIRE WRAP
	7 14x12 7		CD	CONSTRUCTION DOCUMENTS	OBD	OPPOSED BLADE DAMPER	FSD	FIRE/SMOKE DAMPER
	TTATZ	RECTANGULAR DUCT SIZE (WIDTH x DEPTH IN INCHES)	CEC	CALIFORNIA ELECTRICAL CODE	ОС	ON CENTER	FT	FOOT / FEET
	14x12 -	(WIDTH X DEFTH IN INCHES)	CFC	CALIFORNIA FIRE CODE	OD	OUTSIDE DIAMETER	G	GAS
	44" 1		CFM	CUBIC FEET PER MINUTE	OFCI	OWNER FURNISHED CONTRACTOR INSTALLED	GA	GAUGE, GAGE
	7 14"ø 7	ROUND DUCT SIZE	СН	CHILLER	OFOI	OWNER FURNISHED OWNER INSTALLED	GALV	GALVANIZED
	\	(WIDTH x DEPTH IN INCHES)	CHV	CHECK VALVE	Р	PUMP OR PRESSURE OR POLE	GLV	GLOBE VALVE
	17 9		CHWP	CHILLED WATER PUMP	PC	PUMPED CONDENSATE	GN	GENERAL NOTE
	7 R 7	DUCT RISE / DUCT DROP	CHWR	CHILLED WATER RETURN	PCR	PRESSURIZED CONDENSATE RETURN	GND	GROUND
			CHWS	CHILLED WATER SUPPLY	PD	PRESSURE DROP	GPM	GALLON PER MINUTE
	<u> </u>	DUCT WITH SOUND INSULATION	CL	CENTERLINE	PE	PNEUMATIC ELECTRIC	GV	GATE VALVE
	<u> </u>		CLG	CEILING	PF	PRE FILTER	HC	HEATING COIL
	7	STAINLESS STEEL DUCTWORK	СМС	CALIFORNIA MECHANICAL CODE	PG	PIPE GUIDE OR PRESSURE GAUGE	HP	HORSEPOWER
		FLEXIBLE DUCT	CONN	CONNECTION	PH	PHASE	HP HP	HIGH PRESSURE HEAT PUMP
	MMM .	FLEXIBLE DOCT	СР	CONTROL PANEL	PLBG	PLUMBING		
	7	RECTANGULAR DUCT UP	CPC	CALIFORNIA PLUMBING CODE	POC	POINT OF CONNECTION	HPC	HIGH PRESSURE CONDENSATE HIGH PRESSURE STEAM
			CV	CONSTANT VOLUME OR CONTROL VALVE	POD	POINT OF DISCONNECTION	HPS HRU	HIGH PRESSURE STEAM HEAT RECOVERY UNIT
	×	RECTANGULAR DUCT DOWN	CWP	CONDENSER WATER PUMP	PS	PRESSURE SENSOR	HVAC	HEAT RECOVERY UNIT HEATING, VENTILATION & AIR CONDITIONING
	7 7 7	DUCT TRANSITION (RECTANGULAR TO ROUND)	CWR	CONDENSER WATER RETURN	PSI	POUNDS PER SQUARE INCH	HW	HEATING WATER
	7	DOOT INMITORITION (NEOTANGOLAN TO NOUND)	cws	CONDENSER WATER SUPPLY	PSIG	POUNDS PER SQUARE INCH - GAUGE	1100	
	→ D.L./U.C.	DOOR LOUVER OR UNDERCUT	D	DROP OR DRAIN	QTY	QUANTITY		
	<u> </u>	AUTOMATIC DAMPER (WITH ACTUATOR)	DDC	DIRECT DIGITAL CONTROL	(R)	REMOVE		
	▶ —-—	BACKDRAFT DAMPER	DEMO	DEMOLISH / DEMOLITION	R	RISERS, RELOCATE OR RISE		
	Г	MANUAL VOLUME DAMPER	DEPT	DEPARTMENT	RA	RETURN AIR		
	(FSD)——	COMBINATION FIRE & SMOKE DAMPER	DET	DETAIL	REB	REBALANCE		
			DIA	DIAMETER	REF	RELIEF FAN		
	(FD)——	FIRE DAMPER	DIFF	DIFFERENCE	REFRIG	REFRIGERANT		
		1	DISCH	DISCHARGE	REL	RELOCATE		
		CONTROLS (PLAN)	DTR	DOWN DOWN THRU ROOF	REQ'D	REQUIRED		
		1	DIR	DOWN THRU ROOF DIAPHRAGM VALVE	REV	REVISE, REVISION OR REVOLUTIONS		
	<u></u>	CO2 SENSOR	DWG	DRAWING	RF	RETURN FAN REHEAT COIL		
		NITROGEN DIOXIDE SENSOR	DX	DIRECT EXPANSION	RHC	REFRIGERANT LIQUID	——	
	403	MILITOGETA DIOVIDE SEINOOK	(E)	EXISTING TO REMAIN	RM	ROOM		
	Θ	HUMIDITY SENSOR	EA	EXHAUST AIR OR EACH	RS	REFRIGERANT SUCTION		
	<u> </u>	OXYGEN SENSOR	EC	ELECTRICAL CONTRACTOR	RTU	ROOFTOP UNIT		
	Ūx	ROOM THERMOSTAT & ZONE NUMBER	ECON	ECONOMIZER ECONOMIZER	SA	SUPPLY AIR		
	<u> </u>	SWITCH (MANUAL WALL MOUNT OR DOOR INTERLOCK)	EF ECON	EXHAUST FAN	SAN	SANITARY		
	<u> </u>	SMOKE DETECTOR CARRON MONOYIDE SENSOR	EL	ELEVATION	SD	SMOKE DAMPER		
	<u> </u>	CARBON MONOXIDE SENSOR PRESSURE SENSOR (DUCT MOUNTED)	ELEC	ELECTRICAL	SEN	SENSIBLE		
	(P)	PRESSURE SENSOR (BOOM PRESSURE)	EQUIP	EQUIPMENT	SF	SUPPLY FAN OR SQUARE FEET		
	$\overline{\otimes}$	PURGE EXHAUST CONTROL SWITCH	ESP	EXTERNAL STATIC PRESSURE	SP	STATIC PRESSURE		
	HS HS	VISUAL STROBE AND AUDIBLE HORN	ET	EYPANSION TANK	OI OI	SPECIFICATION		

EXPANSION TANK

VISUAL STROBE AND AUDIBLE HORN

REFRIGERANT LEAK DETECTION SENSOR

SPEC SPECIFICATION

HOTEL DEL CORONADO.

Fitness Members Area Renovation

1500 Orange Avenue Coronado, CA 92118



González Architects Hospitality

Mechanical/Electrical/Plumbing Engineer
tk1sc Collaborative
4755 Eastgate Mall, Suite150
San Diego, CA 92121
858.362.6800

15231 Laguna Canyon Road, Suite 100 Irvine, California 92618 949.751.5800 www.tk1sc.com Project Leader - Kenneth McClendon Mechanical Lead - Kenneth McClendon tk1sc Job #: 2019-0727



1 01-05-22 Owner Revisions

MECHANICAL LEAD SHEET

											AIR	TEF	RMIN	AL U	INITS	- SI	NGLE	-DUC	Т	
						COOLING		HEATING			HEATIN	G HOT W	/ATER COIL	_			ELECT	RICAL CONN	IECTION	
^	TAG	#	MANUFACTURER	MODEL NUMBER	INLET SIZE (IN)	MAX AIR FLOW (CFM)	MIN AIR FLOW (CFM)	MAXAIR	REHEAT CAPACITY (BTU/HR)	EAT DB (°F)	LAT DB (°F)	ROWS	FLUID FLOW (GPM)	EWT (°F)	LWT (°F)	VALVE TYPE	VOLTAGE (V)	PHASE	HERTZ (HZ)	REMARKS
1		√ F6 √	→ PRICE →	SPV	1	1640	1640	1640	40 740~	√ 55 √	78	12	2.7	440	110 ~	2 WAX	120	✓	~~~	NDAYAY-BOXWITH BEHEAT-COIL, LINE DLEGUMWITH GLASTONGRIS, DUST INSULATION.
了	CAV	F7	TITUS	DESV	10	900	900	900	22360	55	78	2	1.5	140	110	2-WAY	120	1	60	EXISTING VAV BOX WITH REHEAT COIL. LINE PLENUM WITH ELASTOMERIC DUCT INSULATION.
	SAA	1 9✓	→ RIEE		747		1300	1300	rs2500^	∼ 55∕	78	1/2	2.2	<u></u>	740~	2-44/	1201	~~	√ 66~	NEW VAX BOX WITH RETHEAT GOID. LIKE PLENUK WITH ELASTONER TO BUST KISULATION.
\					•	($\overline{\mathcal{A}}$				~~		$\overline{\overline{}}$							

											FAI	NS										
TAG #	MANUFACTURER	MODEL NUMBER	SERVICE	TYPE	DRIVETYPE	AIR FLOW (CFM)	EXTERNAL STATIC PRESSURE (IN WG)	EFFICIENCY (%)	FAN SPEED (RPM)	MOTOR ENCLOSURE	MOTOR (BHP)	MOTOR (HP)	VOLTAGE (V)	PHASE	HERTZ (HZ)	FMERGENCY	VFD TAG	VIBRATION ISOLATION TAG	DETAIL REFERENCE	CONTROL DIAGRAM	OPERATING WEIGHT (LBS)	REMARKS
EF 7	GREENHECK	SQ-100-VG	MENS LOCKERS	INLINE CENTRIFUGAL	DIRECT	1100	0.36	37	1522	ODP	0.17	0.25	208	60	1	NO		VI-1	4/M5.02		70	PROVIDE WITH VARIGREEN CONTROLS FOR 0-10VDC CONTROL BY OTHERS
EF 8	GREENHECK	SQ-160-VG	WOMENS LOCKERS	INLINE CENTRIFUGAL	DIRECT	2800	0.55	42	1167	TENV	0.58	1	208	60	1	NO		V⊦1	4/M5.02		160	PROVIDE WITH VARIGREEN CONTROLS FOR 0-10VDC CONTROL BY OTHERS

				VIE	BRATIO	N ISOLA	ΓΙΟΝ	
TAG	#	MANUFACTURER	MODEL NUMBER	SERVICE	DEFLECTION (IN.)	BASE TYPE	DETAIL REFERENCE	REMARKS
VI	1	VIBREX	RMXA	F	1.0	SPRING HANGER	4/M5.02	

					DIFFU	SERS & GRILLES
UNIT NO.	MANUFACTURER & MODEL NO.	CFM	FACE SIZE	NECK SIZE	MAX NC	REMARKS
S1 -	TITUS PAS-AA	0-140	12"X12"	6"X6"	25	PROVIDE WITH ALUMINUM FACE AND HEAVY DUTY ENVIRO-THANE ENAMEL COATING FROM FACTORY.
\$2 -	TITUS PAS-AA	141-200	20"X20"	8"	25	PROVIDE WITH ALUMINUM FACE AND HEAVY DUTY ENVIRO-THANE ENAMEL COATING FROM FACTORY.
\$3 -	TITUS PAS-AA	201-500	20"X20"	14"	25	PROVIDE WITH ALUMINUM FACE AND HEAVY DUTY ENVIRO-THANE ENAMEL COATING FROM FACTORY.
E1 -	TITUS PAR-AA	0-210	12"X12"	10"X10"	25	PROVIDE WITH ALUMINUM FACE AND HEAVY DUTY ENVIRO-THANE ENAMEL COATING FROM FACTORY.
E2 -	TITUS PAR-AA	211-300	20"X20"	18"X18"	25	PROVIDE WITH ALUMINUM FACE AND HEAVY DUTY ENVIRO-THANE ENAMEL COATING FROM FACTORY.

Fitness Members Area Renovation

1500 Orange Avenue Coronado, CA 92118



González Architects Hospitality

Mechanical/Electrical/Plumbing Engineer
tk1sc Collaborative
4755 Eastgate Mall, Suite150
San Diego, CA 92121
858.362.6800

TKISC COLLABORATIVE 15231 Laguna Canyon Road, Suite 100 Irvine, California 92618

949.751.5800 www.tk1sc.com

Project Leader - Kenneth McClendon
Mechanical Lead - Kenneth McClendon
tk1sc Job #: 2019-0727



ation Seal A 14 NE 1st Avenue, Su Miami, FL T+1 (305) 45

 No
 Date
 Description

 09-17-21
 Permit Set


 1
 01-05-22
 Owner Revisions

Drawing Title

MECHANICAL SCHEDULES

Scale	As Noted
Date	09-17-2021
Drawn By	RS
Project No.	19022
Drawing No.	PC

M0.03



Fitness Members Area Renovation

1500 Orange Avenue Coronado, CA 92118



González Architects Hospitality

Mechanical/Electrical/Plumbing Engineer
tk1sc Collaborative
4755 Eastgate Mall, Suite150
San Diego, CA 92121
858.362.6800

tksc collaborative 15231 Laguna Canyon Road, Suite 100 Irvine, California 92618 949.751.5800 www.tk1sc.com

Project Leader - Kenneth McClendon Me**tileoficial Lead**d **K©hrietim M6Olea**don tk1sc Job #: 2019-0727






1 01-05-22 Owner Revisions

MECHANICAL DEMO OVERALL PLAN -MEMBERS LOCKER AND LOUNGE

Project No.

Drawing No.

MECHANICAL DEMO OVERALL PLAN - MEMBERS LOCKER AND LOUNGE Scale: 3/32" = 1' - 0"



1 MECHANICAL DEMO PLAN - MEMBERS LOCKER AND LOUNGE Scale: 3/16" = 1' - 0"

HOTEL DEL CORONADO.

Fitness Members Area Renovation

1500 Orange Avenue Coronado, CA 92118



González Architects Hospitality

Mechanical/Electrical/Plumbing Engineer
tk1sc Collaborative
4755 Eastgate Mall, Suite150
San Diego, CA 92121
858.362.6800

TKISC COLLABORATIVE

15231 Laguna Canyon Road, Suite 100 Irvine, California 92618

949.751.5800 www.tk1sc.com
Project Leader - Kenneth McClendon
Mechanical Lead - Kenneth McClendon
tk1sc Job #: 2019-0727





ration Seal Address 09 14 NE 1st Avenue, Suite 507 Miami, FL 33132 T+1 (305) 455 4216

No Date Description

09-17-21 Permit Set

01-05-22 Owner Revisions

MECHANICAL DEMO
PLAN - MEMBERS
LOCKER AND LOUNGE

 alle
 As Noted


 atte
 09-17-2021

 awn By
 RS

 oject No.
 19022

 awing No.
 PC

M1.01



Fitness Members Area Renovation

1500 Orange Avenue Coronado, CA 92118



González Architects Hospitality

Mechanical/Electrical/Plumbing Engineer
tk1sc Collaborative
4755 Eastgate Mall, Suite150
San Diego, CA 92121
858.362.6800

tksc collaborative 15231 Laguna Canyon Road, Suite 100 Irvine, California 92618 949.751.5800 www.tk1sc.com Project Leader - Kenneth McClendon Mechanical Lead - Kenneth McClendon

tk1sc Job #: 2019-0727





Address 14 NE 1st Avenue, Suite 507 Miami, FL 33132 T+1 (305) 455 4216


1 01-05-22 Owner Revisions

MECHANICAL OVERALL PLAN - MEMBERS LOCKER AND LOUNGE

Drawn By Project No.

Drawing No.

MECHANICAL OVERALL PLAN - MEMBERS LOCKER AND LOUNGE Scale: 3/32" = 1' - 0"



Fitness Members Area Renovation

1500 Orange Avenue Coronado, CA 92118



González Architects Hospitality

Mechanical/Electrical/Plumbing Engineer
tk1sc Collaborative
4755 Eastgate Mall, Suite150
San Diego, CA 92121
858.362.6800

15231 Laguna Canyon Road, Suite 100 Irvine, California 92618 949.751.5800 www.tk1sc.com

949.751.5800 www.tk1sc.com

Project Leader - Kenneth McClendon
Mechanical Lead - Kenneth McClendon
tk1sc Job #: 2019-0727



Registration Seal C-32509 Address 14 NE 1st Avenue, Suite 507 Miami, FL 33132 T+1 (305) 455 4216

No Date Description

09-17-21 Permit Set

1 01-05-22 Owner Revisions

Drawing Title

MECHANICAL ZONING

PLAN - MEMBERS LOCKER AND LOUNGE

Scale As Noted

Date 09-17-202


Drawn By RS

Project No. 19022

Drawing No. PC

M2.01Z

ERMIT SET: ISSUED FOR CONSTRUCTION



Fitness Members Area Renovation

1500 Orange Avenue Coronado, CA 92118



González Architects Hospitality

Mechanical/Electrical/Plumbing Engineer
tk1sc Collaborative
4755 Eastgate Mall, Suite150
San Diego, CA 92121
858.362.6800

15231 Laguna Canyon Road, Suite 100 Irvine, California 92618 949.751.5800 www.tk1sc.com

Project Leader - Kenneth McClendon

Mechanical Lead - Kenneth McClendor tk1sc Job #: 2019-0727



ration Seal Address 19 14 NE 1st Avenue, Suite 507 Miami, FL 33132 T+1 (305) 455 4216

No Date Description

09-17-21 Permit Set

01-05-22 Owner Revisions

MECHANICAL PLAN -MEMBERS LOCKER AND LOUNGE

Date 09-17-2021

Drawn By Rs

Project No. 19022

Drawing No. PC


1 MECHANICAL PLAN - MEMBERS LOCKER AND LOUNGE Scale: 3/16" = 1' - 0"

KEYED NOTES:

- (1) REFER TO ARCHITECTURAL PLANS FOR EXACT DIFFUSER LOCATION. (TYP.)
- DIFFUSER SHALL BE ALUMINUM CONSTRUCTION FOR CORROSION RESISTANCE. SEE DIFFUSER SCHEDULE. (TYP. ALL AIR DISTRIBUTION)
- MAINTAIN ACCESS TO EXISTING SMOKE FIRE DAMPER.
- EXISTING EXHAUST FAN, EF-1, AND EXISTING AIR HANDLER, AH-1, AND ALL ASSOCIATED AIR DISTRIBUTION, COOLING COILS AND HEATING COILS SHALL BE REBALANCED TO THE APPLICABLE FLOW RATES INDICATED ON SHEETS M0.03 AND M2.01 OF THE FITNESS RENOVATION PACKAGED. FITNESS RENOVATION PACKAGE IS A PREVIOUSLY PERMITTED SET
- (5) MAINTAIN EXISTING ACCESS TO MECHANICAL EQUIPMENT.
- 6 ADD/ ALTERNATE: REPLACE VAV BOX DDC CONTROLLER AND THERMOSTAT WITH NEW BUILDING STANDARD TYPE.
- 7) 42"X18" EGGCRATE GRILLE. FULL ALUMINUM CONSTRUCTION.
- 42"X18" EGGCRATE GRILLE. FULL ALUMINUM CONSTRUCTION.

 18"X18" EGGCRATE GRILLE. FULL ALUMINUM CONSTRUCTION.


 GRFC ACCESS PANEL WITH A TAPED EDGE BY OTHERS.



2. PROVIDE AT ALL PENETRATIONS OF DUCTS/PIPES THROUGH FULL HEIGHT WALLS

UNLESS NOTED OTHERWISE

ONSTRUCTION



IF "T" IS GREATER THAN 12'-0", OR THERE ARE ELBOWS UPSTREAM OF THE VAV BOX INLET, THEN PROVIDE TAP-OFF OF

SUPPLY AIR MAIN W/ DUCT DIAMETER EQUAL TO VAV BOX INLET SIZE PLUS 2", U.N.O.

BE EASILY ACCESSIBLE FROM A SINGLE POINT OF CEILING ACCESS.

4. THE CAV/VAV BOX ARRANGEMENT SHALL BE EASILY ACCESSIBLE FROM A SINGLE POINT OF CEILING ACCESS. THIS INCLUDES ACCESS TO THE DAMPER, DAMPER LINKAGE, DAMPER MOTOR, CONTROL

ENCLOSURE, DISCONNECT SWITCH & HEATING COIL ARRANGEMENT IN ROOMS WHERE THE SUPPLY & RETURN BOXES ARE LOCATED ADJACENT TO ONE ANOTHER, ACCESS TO ALL COMPONENTS OF BOTH BOXES SHALL

— ATTACH WITH SHEET METAL SCREWS & SEAL RECTANGULAR TO ROUND LOW - LOSS DUCT FITTING.

HOTEL DEL CORONADO.

Fitness Members Area Renovation

1500 Orange Avenue Coronado, CA 92118



González Architects Hospitality

Mechanical/Electrical/Plumbing Engineer tk1sc Collaborative 4755 Eastgate Mall, Suite150 San Diego, CA 92121 858.362.6800

COLLABORATIVE

15231 Laguna Canyon Road, Suite 100 Irvine, California 92618 949.751.5800 www.tk1sc.com

Project Leader - Kenneth McClendon Mechanical Lead - Kenneth McClendon tk1sc Job #: 2019-0727



14 NE 1st Avenue, Suite 507 T+1 (305) 455 4216


Issued/Revised No Date Description 1 01-05-22 Owner Revisions

Drawing Title

DETAILS


PC
19022
RS
09-17-2021
As Noted
_






HEATING HOT WATER PIPING

NONE






- IN ACCORDANCE WITH SECTION 13.5.6.2.2(5) OF ASCE 7-05 AS AMENDED BY 2010 CBC SECTION 1615A.1.16 (1615.10.13*) AND ASTM E580 SECTION 5.3 AND 5.4.
- 2. MECHANICAL TERMINALS SHALL BE SUPPORTED DIRECTLY ON RUNNERS CLASSIFIED AS ASTM HEAVY DUTY, BUT THEY MUST ALSO HAVE A MINIMUM OF TWO (2) #12 GAGE SLACK SAFETY WIRES ATTACHED TO THE FIXTURE AT DIAGONAL CORNERS AND ANCHORED TO THE STRUCTURE ABOVE.
- 3. MECHANICAL TERMINALS WEIGHING 56 LBS. OR MORE MUST BE INDEPENDENTLY SUPPORTED BY NOT LESS THAN FOUR (4) TAUT #12 GAGE WIRES ATTACHED TO THE HOUSING AND TO THE STRUCTURE ABOVE. THE FOUR (4) TAUT #12 GAGE WIRES, INCLUDING THEIR ATTACHMENT TO THE STRUCTURE ABOVE, MUST BE CAPABLE OF SUPPORTING FOUR (4) TIME THE WEIGHT OF THE UNIT.
- 4. FLEXIBLE DUCT TO BE INSTALLED AND SUPPORTED PER SMACNA SECTION 3.5 AND 3.7. FLEXIBLE DUCT CONNECTIONS SHALL BE CASCO SILENT FLEX II OR EQUAL ACOUSTICAL FLEX DUCT.
- FLEXIBLE DUCTWORK SHALL NOT HAVE A BEND RADIUS TIGHTER THAN 1.5 TIMES THE DUCT DIAMETER. RETURN AIR REGISTERS AND RELIEF AIR REGISTERS ARE SIMILAR.
- 8. EXHAUST AIR REGISTERS SIMILAR WITH RIGID DUCT IN LIEU OF FLEX.
- 9. DIFFUSERS AND REGISTERS TO BE INSTALLED PER SMACNA. 10. PROVIDE REMOTE ACTUATED VOLUME DAMPERS AT HARD-LID CEILING INSTALLATION.

DUCT SUPPORT DETAIL

NONE

CEILING DIFFUSER

NONE



Fitness Members Area Renovation

1500 Orange Avenue Coronado, CA 92118



González Architects Hospitality

Mechanical/Electrical/Plumbing Engineer
tk1sc Collaborative
4755 Eastgate Mall, Suite150
San Diego, CA 92121
858.362.6800

tksc collaborative

15231 Laguna Canyon Road, Suite 100 Irvine, California 92618 949.751.5800 www.tk1sc.com Project Leader - Kenneth McClendon

Mechanical Lead - Kenneth McClendon tk1sc Job #: 2019-0727



istration Seal 2509	Add 14 NE 1st Avenue, Suite Miami, FL 33 T+1 (305) 455 4

No Date Description


09-17-21 Permit Set

1 01-05-22 Owner Revisions

Drawing Title

DETAILS

Scale As Noted Date 09-17-2021 Drawn By RS Project No. 19022 Drawing No. PC		M5.02
Date 09-17-2021 Drawn By RS	Drawing No.	PC
Date 09-17-2021	Project No.	19022
	Drawn By	RS
Scale As Noted	Date	09-17-2021
	Scale	As Noted



ZONE UNOCCUPIED OVERRIDE [TITLE 24 SECTION 120.2(e)1]:
A TIMED LOCAL OVERRIDE CONTROL SHALL ALLOW AN OCCUPANT TO OVERRIDE THE SCHEDULE AND PLACE THE

A.O.-VALVE COMMAND

UNIT INTO AN OCCUPIED MODE FOR A 60 MINUTE PERIOD OF TIME. AT THE EXPIRATION OF THIS TIME, CONTROL OF THE UNIT SHALL AUTOMATICALLY RETURN TO THE SCHEDULE.

── H.W.S

AB H.W.R.

3-W VALVE OPTION

CONSTANT VOLUME TERMINAL UNIT - AIR FLOW AND TEMPERATURE CONTROL: THE CONTROLLER SHALL MEASURE THE AIRFLOW AND MODULATE THE ZONE DAMPER TO MAINTAIN A CONSTANT

AIRFLOW SETPOINT. WHEN ZONE TEMPERATURE IS LESS THAN ITS HEATING SETPOINT, THE CONTROLLER SHALL ENABLE HEATING TO MAINTAIN THE ZONE TEMPERATURE AT ITS HEATING SETPOINT.

REHEATING - HIGH DISCHARGE AIR TEMPERATURE LIMIT: THE CONTROLLER SHALL MEASURE THE SUPPLY AIR TEMPERATURE AND LIMIT THE SUPPLY AIR TEMPERATURE TO A MAXIMUM PER THE CAV SCHEDULE. • THE REHEAT VALVE SHALL MODULATE TO SATISFY THE SUPPLY AIR TEMPERATURE SETPOINT UNTIL THE MAXIMUM CAV BOX SUPPLY AIR TEMPERATURE IS REACHED.

SUPPLY AIR TEMPERATURE MONITORING: THE CONTROLLER SHALL MONITOR THE SUPPLY AIR TEMPERATURE.

ALARMS SHALL BE PROVIDED AS FOLLOWS: • HIGH SUPPLY AIR TEMP: THE SUPPLY AIR TEMPERATURE IS GREATER THAN 105'F FOR 10 MINUTES. THE ALARM SHALL AUTOMATICALLY CLEAR WHEN THE SUPPLY AIR TEMPERATURE RETURNS BELOW THE ALARM THRESHOLD FOR 5 MINUTES.

 LOW SUPPLY AIR TEMP: THE SUPPLY AIR TEMPERATURE IS LESS THAN 45°F FOR 10 MINUTES. THE ALARM SHALL AUTOMATICALLY CLEAR WHEN THE SUPPLY AIR TEMPERATURE RETURNS ABOVE THE ALARM THRESHOLD FOR 5 MINUTES.

- IF THE COOLING LOOP SIGNAL IS GREATER THAN 95%, SEND 1 COOLING SUPPLY AIR TEMPERATURE RESET
- IF THE ZONE TEMPERATURE EXCEEDS THE ZONE COOLING SETPOINT BY 2°F FOR 2 MINUTES, SEND 2 COOLING
- AIR TEMPERATURE RESET REQUESTS.

STANDBY MODE - OCCUPANCY SENSING ZONE CONTROLS (WHERE NOTED ON FLOOR PLANS) [TITLE 24 SECTION DURING OCCUPIED HOURS, THE CONTROLLER SHALL MONITOR THE ZONE OCCUPANCY.

AN ADAPTIVE ZONE LEVEL OPTIMAL START ALGORITHM SHALL BE USED TO MINIMIZE THE ENERGY REQUIRED AND WARM-UP OR COOL-DOWN TIME DURING THE UNOCCUPIED PERIOD, NECESSARY TO ACHIEVE ZONE OCCUPIED

TEMPERATURE SETPOINTS BY THE START OF SCHEDULED OCCUPIED PERIOD. THE LEARNING ADAPTIVE ALGORITHM

SHALL COMPARE THE ZONE TEMPERATURE TO ITS SETPOINT AT BEGINNING OF SCHEDULED OCCUPIED PERIOD AND SHALL AUTOMATICALLY ADAPT THE HEATING OR COOLING RESPONSE TIME FOR THE NEXT UNOCCUPIED PERIOD.

HIGH ZONE TEMPERATURE: THE ZONE TEMPERATURE IS GREATER THAN THE COOLING SETPOINT BY 5°F FOR

• LOW ZONE TEMPERATURE: THE ZONE TEMPERATURE IS LESS THAN THE HEATING SETPOINT BY 5°F FOR 10

MINUTES. THE ALARM SHALL AUTOMATICALLY CLEAR WHEN THE ZONE TEMPERATURE RETURNS ABOVE THE

10 MINUTES. THE ALARM SHALL AUTOMATICALLY CLEAR WHEN THE ZONE TEMPERATURE RETURNS BELOW THE

WHEN ALL ROOM(S) SERVED BY THE ZONE ARE UNOCCUPIED FOR 5 MINUTES, THE UNIT SHALL BE PLACED IN

UNLESS OTHERWISE SPECIFIED, ALL SETPOINTS, TIME PARAMETERS, AND SETPOINT RESET PARAMETERS ARE

THE UNIT SHALL RUN ACCORDING TO A USER DEFINABLE TIME SCHEDULE IN THE FOLLOWING MODES:

ADJUSTABLE. THE FOLLOWING SETPOINTS ARE RECOMMENDED VALUES. VALUES SHALL BE FIELD ADJUSTED DURING

THE STARTUP AND TUNING PERIOD TO MEET THE REQUIREMENTS OF ACTUAL FIELD CONDITIONS THROUGHOUT THE

- THE UNIT SHALL MAINTAIN THE STANDBY MODE COOLING AND HEATING SETPOINTS. WHEN THE ZONE TEMPERATURE IS BETWEEN THE STANDBY COOLING AND HEATING SETPOINTS, THE DAMPER
- WHEN OCCUPANCY IS DETECTED IN ANY OF THE ROOM(S) FOR 60 SECONDS, THE ZONE SHALL RETURN TO OCCUPIED MODE.

CAV BOX COOLING AND HEATING:

RUN CONDITIONS - SCHEDULED:

A 75°F COOLING SETPOINT

A 70°F HEATING SETPOINT

 A 78°F COOLING SETPOINT A 68°F HEATING SETPOINT

AN 85°F COOLING SETPOINT

A 55°F HEATING SETPOINT

OCCUPIED MODE: THE UNIT SHALL MAINTAIN

STANDBY MODE: THE UNIT SHALL MAINTAIN:

ALARMS SHALL BE PROVIDED AS FOLLOWS:

ALARM THRESHOLD FOR 5 MINUTES.

ALARM THRESHOLD FOR 5 MINUTES.

ZONE LEVEL OPTIMAL START [TITLE 24 SECTION 120.2(k)]:

A DEADBAND OF 5°F BETWEEN COOLING AND HEATING.

UNOCCUPIED MODE (NIGHT SETBACK): THE UNIT SHALL MAINTAIN

TIME OF DAY SCHEDULE:
OCCUPIED MODE SHALL BE INITIATED UPON A START REQUEST FROM A CAV BOX.

ZONE SETPOINT ADJUST:
THE OCCUPANT SHALL BE ABLE TO ADJUST THE ZONE TEMPERATURE HEATING AND COOLING SETPOINTS AT THE ZONE SENSOR. THE RANGE OF ADJUSTMENT SHALL BE ± -2 .

FAN IN HAND ALARM CONDITION: FAN IS COMMANDED OFF, BUT THE STATUS IS ON FOR MORE THAN 1 MINUTE. RETURN-TO-NORMAL CONDITION: THE ALARM SHALL AUTOMATICALLY CLEAR WHEN THE FAN STATUS MATCHES THE COMMAND FOR MORE THAN 1 MINUTE.

SCALE

NONE

• EXHAUST FAN VFD FAULT ALARM CONDITION: VFD FAULT IS ACTIVE FOR MORE THAN 1 MINUTE. RETURN TO NORMAL CONDITION: THE ALARM SHALL AUTOMATICALLY CLEAR WHEN THE VFD FAULT IS NOT ACTIVE FOR MORE THAN 1 MINUTE.

SYMBOL AFMS AIR FLOW MEASURING STATION COOLING COIL HEATING COIL CR CURRENT SENSING RELAY OR TRANSMITTER CO2 SENSOR — DUCT MOUNTED CO2 TRANSMITTER - WALL DIFFERENTIAL PRESSURE SWITCH OR TRANSMITTER - FILTER DIFFERENTIAL PRESSURE SWITCH OR TRANSMITTER -DUCT DIFFERENTIAL PRESSURE TRANSMITTER - BUILDING HUMIDITY TRANSMITTER - WALL HUMIDITY SWITCH OCCUPANCY SENSOR - WALL E FURNISHED AND INSTALLED BY ELECTRICAL SMOKE DETECTOR TEMPERATURE SENSOR - WALL TEMPERATURE SENSOR - DUCT TEMPERATURE SENSOR -AVERAGING TEMPERATURE SENSOR - OUTDOOR TEMPERATURE SENSOR - PIPE BUTTERFLY VALVE WITH ACTUATOR 2-WAY VALVE WITH ACTUATOR 3-WAY MIXING VALVE WITH ACTUATOR 3-WAY DIVERTING VALVE WITH ACTUATOR A.I. ANALOG INPUT B.I. BINARY INPUT ANALOG OUTPUT B.O. BINARY OUTPUT BUILDING NETWORK CONTROLLER VAV CONTROLLER ADVANCED APPLICATION CONTROLLER APPLICATION SPECIFIC CONTROLLER BACNET MANUFACTURER'S BACNET INTERFACE

DESCRIPTION

HOTELDEL ORONADO.

Fitness Members Area Renovation

1500 Orange Avenue Coronado, CA 92118



González Architects Hospitality

Mechanical/Electrical/Plumbing Engineer tk1sc Collaborative 4755 Eastgate Mall, Suite 150 San Diego, CA 92121 858.362.6800



15231 Laguna Canyon Road, Suite 100 Irvine, California 92618 949.751.5800 www.tk1sc.com Project Leader - Kenneth McClendon Mechanical Lead - Kenneth McClendon tk1sc Job #: 2019-0727



14 NE 1st Avenue, Suite 507 T+1 (305) 455 4216

No Date Description 09-17-21 Permit Set 1 01-05-22 Owner Revisions

Drawing Title

WIRING & CONTROLS

09-17-2021 Drawn By Project No. Drawing No.

- REQUESTS SHALL BE SENT ACCORDING TO THE FOLLOWING: • IF THE COOLING LOOP SIGNAL IS LESS THAN 85%, SEND 0 COOLING SUPPLY AIR TEMPERATURE RESET
- REQUEST.
- SUPPLY AIR TEMPERATURE RESET REQUESTS. IF THE ZONE TEMPERATURE EXCEEDS THE ZONE SETPOINT BY 3°F FOR 2 MINUTES, SEND 3 COOLING SUPPLY

EXHAUST FANS - BUILDING EXHAUST UNLESS OTHERWISE NOTED, ALL SETPOINTS ARE ADJUSTABLE.

THE CONTROLLER SHALL MONITOR THE FAN STATUS.

ALARMS SHALL BE PROVIDED AS FOLLOWS:

FAN STATUS:

FAN FAILURE

A.I.-AIRFLOW

I.-ZONE OVERRIDE

A.I. – ZONE SETPOINT

B.O/B.O.-FLOATING M

A.O.-VALVE COMMAND

RUN CONDITIONS: INTERLOCKED. FANS SHALL RUN WHEN EXISTING EF-1 RUNS.

THE FAN SHALL RUN TO MAINTAIN THE CFM INDICATED ON THE M0.03 EQUIPMENT

THE FAN SHALL HAVE A USER DEFINABLE MINIMUM RUNTIME OF 60 MINUTES.

EXHAUST AIRFLOW CONTROL (CONSTANT VOLUME): THE CONTROLLER SHALL MEASURE THE

ALARM CONDITION: FAN IS COMMANDED ON, BUT THE STATUS IS OFF FOR MORE THAN 1

A.I.-SUPPLY AIR TEMP.

AB H.W.R.

S B.I.-OCCUPANCY SENSOR BACnet POINT

RETURN-TO-NORMAL CONDITION: THE ALARM SHALL AUTOMATICALLY CLEAR WHEN

THE FAN STATUS MATCHES THE COMMAND FOR MORE THAN 1 MINUTE.

EXHAUST FAN

SCALE

NONE

1.01 GENERAL CONDITIONS

A. General Description:

- 1. Air conditioning for indicated area complete with supply ducts, return air ducts, air distribution equipment and controls.
- 2. Air conditioning units complete with required supply fans, cooling coils, filters, ductwork, diffusers, grilles, dampers, controls and other items herein specified.
- 3. Ventilation of miscellaneous rooms with exhaust fans, ducting and
- 4. Removal of existing ductwork and piping as indicated on the drawings.

1.02 RELATED WORK INCLUDED IN THIS SECTION

- A. Furnish electrical devices necessary for mechanical work, except disconnects unless indicated otherwise.
- B. Line and low voltage wiring for mechanical controls including final
- C. Conduit for line and low voltage wiring for mechanical controls.
- D. Responsibility for obtaining clarification of discrepancies between
- mechanical and electrical work prior to proceeding with the work. E. Responsibility for proper operation of automatic pneumatic/electric controls and equipment and of electric power driven equipment furnished under this section.
- F. Miscellaneous steel for ducts and pipes hangers and supports including structural calculations prepared by a California licensed Structural Engineer.

1.03 RELATED WORK SPECIFIED IN OTHER SECTIONS

- A. Concrete work including miscellaneous metal in connection with pits, trenches and catch basins with foundations or concrete pads under rooftop package units, boiler units, pump and other mechanical equipment. Templates for spacing and sizes of concrete pads and anchor bolts under this section.
- B. Electrical work as follows will be provided Electrical contract scope:
- 1. Conduit for line wiring for equipment and devices as indicated or specified except conduit for line and low voltage wiring for mechanical controls as specified under Division 26.
- 2. Line wiring for equipment and devices as indicated or specified herein except line and low voltage wiring for mechanical controls as specified under Division 26.
- 3. Providing disconnect switches.
- 4. Installing electrical devices such as starters and disconnects, and when indicated, furnishing all such devices.
- C. Building Management and Control System Temperature Controls.

1.04 QUALITY ASSURANCE

- A. Codes and Standards: In addition to the requirements of all governing codes, ordinances and agencies, conform to the requirements of the following codes and standards:
- 1. Applicable City regulations and ordinances
- 2. California Building Code, 2019 Edition
- California Mechanical Code, 2019 Edition 4. The California Code of Regulations (CCR) Title 24, 2019.
- 5. Health and Safety Code, State of California 6. National Board of Fire Underwriters Publications:
- a. Pamphlet # 70 National Electrical Code b. Pamphlet # 90A Air Conditioning Systems

1.05 SUBMITTALS

- A. Shop Drawings: Before any of the materials of this Section are delivered at the jobsite, submit complete shop drawings. Show all details of all ductwork, piping and equipment pads. The shop drawings shall represent a coordinated set of drawings with other disciplines.
- B. Product Data:
- 1. Submit copies of all manufacturers' product data simultaneously with all shop drawing submittals.
- 2. Product data to include all air conditioning equipment, hangers, fans, ductwork construction, piping, and other standard items as required to complement shop drawings for a submittal indicating all products to be used on this work.
- 3. Manufacturers and suppliers of equipment shall provide all data necessary for compliance with the State of California Energy Efficiency Code: Compliance certification for all equipment shall be included in equipment submittals.
- C. Record Drawings: Maintain throughout the progress of the work project record drawings and submit to the Architect at completion of work.
- D. Operating Manuals and Maintenance Manuals:
- 1. Submit copies of all operating instructions and maintenance
- 2. Fully instruct Owner operating personnel and demonstrate performance, operation and maintenance of equipment. Amount of time allocated for said instruction and demonstrations of equipment and systems shall be part of these obligations. Submit a letter to Architect signed by Owner representative who will operate system stating that he is fully instructed by contractor about operation and maintenance of equipment and system.
- 3. Submit one additional set of approved instructions and one additional set of approved 11 inch x 17 inch control diagrams suitably framed behind glass for mounting as directed.

1.06 PRODUCT HANDLING

ONSTRUCTION

- A. Protection: Take all precautions necessary to protect the materials of this section before, during, and after installation.
- B. Replacements: In the event of damage, immediately repair all damaged and defective work to the approval of the Architect at no additional cost to Owner.

1.07 JOB CONDITIONS

A. Examination of the Site: Examine the site and include all conditions in bid proposal under which work is to be performed.

1.08 MISCELLANEOUS

- A. Locations and Accessibility: Contractor shall fully inform himself regarding peculiarities and limitations of spaces available for installation of work under this section. Valves, motors, controls and other devices requiring service, maintenance and adjustment shall be placed in fully accessible positions and locations. Provide access doors where required in ductwork or construction whether specially detailed or not, and render all such devices accessible.
- B. Drawings indicate desired location and arrangement of ductwork, piping, equipment and other items, and are to be followed as closely as possible. All offsets and interferences may not be indicated due to the scale of the Drawings. Contractor shall assume responsibility for coordinating work with all other trades. Work specified and not clearly \ defined by the drawings shall be installed and arranged in a manner satisfactory to Architect. In the event changes in indicated locations and arrangements are deemed necessary by Architect, they shall be made by Contractor without additional charges provided the change is ordered before work is installed and no extra materials are required.

PART 2-PRODUCTS

2.00 ACCESS PANELS

- A. PERFORMANCE REQUIREMENTS
- 1. FIRE-RATED ACCESS DOORS AND FRAMES: ASSEMBLIES COMPLYING WITH NFPA 80 THAT ARE LISTED AND LABELED BY A QUALIFIED TESTING AGENCY, FOR FIRE-PROTECTION RATINGS INDICATED ACCORDING TO NFPA 252 OR UL 10 B.
- B. FLUSH ACCESS DOORS WITH CONCEALED FLANGES
- 1. DESCRIPTION: FACE OF DOOR FLUSH WITH FRAME; WITH CONCEALED FLANGE FOR GYPSUM BOARD INSTALLATION AND CONCEALED HINGE. 2. LOCATIONS: CEILING.
- 3. UNCOATED STEEL SHEET FOR DOOR: NOMINAL 0.060 INCH, 16 GAGE, FACTORY PRIMED.
- 4. FRAME MATERIAL: SAME MATERIAL AND THICKNESS AS
- 5. LATCH AND LOCK: CAM LATCH, SCREWDRIVER OPERATED.

C. FIRE-RATED ACCESS DOORS AND FRAMES

- 1. DESCRIPTION: DOOR FACE FLUSH WITH FRAME, WITH A CORE OF MINERAL-FIBER INSULATION ENCLOSED IN SHEET METAL, WITH CONCEALED FLANGE FOR GYPSUM BOARD INSTALLATION. SELF-CLOSING DOOR. AND CONCEALED HINGE.
- 2. LOCATIONS: CEILING.
- 3. FIRE-RESISTANCE RATING: NOT LESS THAN THAT OF ADJACENT CONSTRUCTION. 4. UNCOATED STEEL SHEET FOR DOOR: NOMINAL 0.036 INCH.
- 20 GAGE, FACTORY PRIMED. 5. FRAME MATERIAL: SAME MATERIAL, NOMINAL 0.060 INCH, 16 GAGE, AND SAME FINISH AS DOOR.
- 6. LATCH AND LOCK: SELF-CLOSING, SELF-LATCHING DOOR HARDWARE, OPERATED BY KEY, WITH INTERIOR RELEASE.

2.01 PIPE HANGERS

- A. Hangers shall be complete with threaded steel rods and vibration isolators, sound and electrolysis isolators as required and hereinafter specified. Concrete inserts shall be furnished and installed under this
- B. 2-1/2 inches and smaller: Grinnell 104 or approved equal.
- C. 3 inches and larger: Grinnell 260. D. Concrete inserts: Grinnell 280.

2.02 VIBRATION ISOLATION

- A. Provide vibration isolation equipment for all mechanical equipment and piping as specified herein and indicated on the drawings. The vibration isolation system shall be installed in a manner to prevent the transmission of vibration to the structure. No rigid connections between rotating or oscillating equipment or piping and the building will be permitted.
- B. General Requirements:
- 1. Vibration isolation manufacturer shall furnish written instructions covering the installation and adjustment of all isolators. The manufacturer shall replace any isolation that has been improperly
- 2. Mechanical subcontractor shall coordinate his work with the other trades. Contractor following him, such as plastering or electrical, shall be notified and instructed to avoid any contact with his
- installation that would reduce the effectiveness of the system. 3. Inspections: Vibration isolation manufacturer shall make an inspection of the vibration installation, and inform the Contractor in writing of any necessary corrections and/or adjustments.
- 4. Bases: Where called for in the specifications and on the drawings, all structural steel bases, including concrete pouring form bases, shall be designed and fabricated by the vibration isolation manufacturer. The concrete for the pouring form bases shall be by
- 5. Vibration isolation shall be manufactured by a single manufacturer. All isolation shall be in strict accordance with the following specifications and manufactured by M.W. Sausse and Co., Inc. The isolation manufacturer shall include in the submittal the following information:
- Type of isolator.
- b. Deflection.
- c. Free or unloaded height. d. All physical characteristics of springs used.
- e. Size of structural members.
- f. Efficiency calculations.
- g. Any other pertinent information to make the submittal

complete.

- C. Technical Requirements:
- 1. Isolators shall be designed or treated for resistance to corrosion. Structural steel bases shall be cleaned of welding slag and painted with primer and finish coat. All nuts, bolts and washers shall be zinc-electroplated.
- 2. All equipment shall be equipped with seismic restraints in accordance with the requirements of all governing agencies. These restraints shall be designed and supplied by the vibration isolation manufacturer. Suspended equipment and piping shall be restrained by steel cable. This cable and the method of installation shall be the responsibility of the mechanical contractor. The cable restraints shall be installed in such a manner as to not short circuit the vibration isolation. The Contractor shall submit details for approval.

2.03 INSULATION

- A. All insulation shall comply with California Code of Regulations, Title 24. B. Install pipe insulation after piping is installed, tested and approved, and
- is in clean dry condition. Firmly butt insulation joints. C. Hydronic Supply and Return: Insulate piping with flexible elastomeric insulation with factory applied jacket, Armacell AP ARMAFLEX, 1-1/2" thick. Insulate fittings, flanges and valves mitered section of insulation and adhere longitudinal laps and butt strips of jacket with pressure sensitive tape system.
- D. Unions: Insulate in same manner as fittings, flanges and valve bodies. Conspicuously mark locations on pipe coverings.
- E. Shields: For pipes 4 inches and larger, at each hanger protect insulation with 12 inches long 18 gauge galvanized metal shield over heavy density calcium silicate insulation insert. For pipes 3 inches and smaller, at each hanger protect insulation with 4 inch long 18 gauge galvanized metal shield.
- Thermal Duct Insulation: Insulate all concealed cold supply air, return air and plenums unless otherwise specified, with Johns Manville Microlite fiberglass duct insulation, wrapped entirely around duct with joints lapped at least 2 inches and secured with 16 gauge galvanized wire on 12 inch centers. Insulation value shall comply with Title 24 requirements. Insulation shall cover all surfaces including standing
- H. Mechanical fasteners shall be flush with the liner surface and shall start within 2 inches of the leading edge of each section and within 3 inches of the leading edge of all cross joints within the duct section. All exposed edges and the leading edge of all cross joints of the liner shall be heavily coated with an approved fire resistant adhesive. The duct liner shall be cut to assure snug closing corner joints, the black surface of the liner shall face the air stream, transverse joints shall be neatly butted, and heavily coated with an approved fire resistant adhesive.
- I. Contractor s Option: Concealed main supply air ducts and plenums may be lined in lieu of external wrapping as hereinbefore specified.
- J. Lined Duct: Where indicated, line ducts with flexible elastomeric duct insulation 1" in thickness.

2.04 VALVES

Valves shall be of same manufacturer or equivalent by comparator chart of approved manufacturer. Provide adapters for valves in copper tubing where necessary. Provide chain operated valves for valves located 7 feet above finished floor in equipment rooms and equipment areas.

- A. Gate Valves: 150 lb. SWB, Nibco F-617-0
- B. Globe Valves:
- 1. 2 inches and smaller: 150 lb. SWP. Nibco T-235Y 2. 2-1/2 inches and larger: 125 lb. SWP, iron body, Nibco F-718-B
- C. Check Valves:

1. Horizontal Swing:

- a. 2 inches and smaller: 125 lb. SWP, screwed, Nibco T-413
- b. 2-1/2 inches and larger: 125 lb. SWP, iron body, flanged, Nibco F-918 B.
- 2. Silent type (at pump discharge): All sizes: 125 lb. SWP, iron body (all bronze in copper pipe system), Miller 162.

D. Balancing Valves:

- 1. 1-1/4 inches through 2-1/2 inches: 125 lb. SWP, Bell & Gossett circuit setter, bronze, screwed.
- 2. 2-1/2 inches and larger: Rockwell 175 lb. WWP lubricated semi-steel plug valves with plugs and bolted yokes, operating wrench, with adjustable locking step indicator and arc when balancing cock is used as a shutoff valve.
- E. Butterfly valves for condenser and hot water systems shall be provided in lieu of gate valves. Crane No. 42F quartermaster, cast iron body, lug wafer type with EPT seats and gear operator with position indicator. 200 lb. WWP pressure tight shut-off at differential pressures up to 200 psi. Provide extended stem for insulated lines.
- F. Ball Valves: 150 lb. SWP, bronze body, Nibco T-585-20.

2.05 STRAINERS

- A. Y-type with semi-steel body and stainless steel basket with 1/8 inch perforations and lined with 20 mesh stainless steel screen. Strainer shall be of same size as pipeline in which installed. Provide hose gate valve with each strainer blowoff.
- 1. 2-1/2 inches and smaller: Armstrong AISC series, 125 lb., screwed ends with screwed gasket cap.
- 2. 3 inches and larger: Armstrong AIFL series, 125 lb., flanged ends and bolted gasketed cap.

2.06 PIPING ACCESSORIES

A. Pressure Gauges: Ashcroft Duragauge 1379-A, complete with 4-1/4 inch diameter dial and gauge cock. One pressure gauge cock and gauge shall be installed on suction and discharge side of each pump and elsewhere indicated to accept a master pressure gauge.

- B. Thermometers: Weiss 7VS 3-1/2 inch Vari-Angle adjustable angle red mercury industrial thermometers with 7 inch chrome-plated bronze case, 3-1/2 inch stem with swivel nut, 3/4 inch NPT brass separable socket and etched scale with gradations as indicated or required.
- C. Air Vent Valves:
- 1. Water: 75 psi working pressure. Hoffman No. 79 2. Water: 150 psi working pressure. Hoffman No. 78
- D. Tank Fittings: Bell & Gossett series ATF of size corresponding to compression tank diameters.
- E. Flexible Pipe Connections: Braided stainless steel for condenser water piping and braided bronze for hot water systems.

2.07 HYDRONIC PIPING

- A. Chilled, Hot and Condenser Water Piping:
- 1. 2 Inches and Smaller: Type L hard-drawn copper tubing, wrought copper fittings with soldered joints.
- 2. 2-1/2 Inches and above: Schedule 40 black steel pipe with standard welded fittings.

B. Pipe Insulation:

1. All insulation shall comply with the State of California Energy Conservation Standards. 2. See section 2.03

2.08 UNIONS AND GASKETS

- A. 2 inches and under for steel pipe: Screwed malleable iron, ground joint, 300 lb. WOG Class with brass to iron seat, black.
- B. 2-1/2 inches and larger for steel pipe: Cast iron flanged gasket type, conforming to ANSI B16.1, black to suit service, or 150 lb. forged steel slip-on flanges.
- C. Unions for copper tubing: Anaconda 1633 or 1733. D. Dielectric unions: EPCO, complete with isolators and gaskets of same
- size as pipe, galvanized or black to suit service. E. Dielectric flanges: F.H. Maloney Co. flanges for cathodic insulation.

2.09 DUCTS AND SHEET METAL WORK

F. Gaskets: 1/16 inch Garlock 17022.

Provide ducts, plenums, access doors, fresh air intakes and exhausts as indicated and required. All ductwork shall be constructed, erected and tested in accordance with the most restrictive of local regulations, procedures detailed in the ASHRAE Handbook of Fundamentals or the applicable standards adopted by the Sheet Metal and Air Conditioning Contractors National Association. Provide prefabricated spiral lockseam ducts and fittings and rectangular ducts of galvanized steel. Primary cold supply air shall be medium pressure, 4 inch S.P. Distribution ductwork downstream of VAV boxes shall be low pressure, 1 inch S.P. Outside air and exhaust air ductwork shall be low pressure. 2 inch S.P.

- A. Final connections to ceiling diffuser boxes and linear diffusers shall be made with flexible glass fiber duct. Thermaflex M-KE. Connections of flexible duct to round ducts shall be made with ½ inch wide positive
- C. Flat duct surfaces shall be crimped diagonally regardless of size.

B. All connections to main cold supply ducts shall be made with low loss

- Longitudinal joints in all duct sizes may be flat-lock joints. Transverse joints and intermediate bracing shall be constructed of galvanized sheet metal or galvanized structural angles in accordance with requirements of the ASHRAE guide and public authorities having jurisdiction.
- D. Lock joints shall be hammered to make them airtight. Inside of duct shall present a smooth surface to flow of air. E. Changes in size of ducts shall increase gradually with a slope of not more than 12 inches in 5 feet where possible, but not more than 12
- inches in 3 feet in any event. F. Turns shall be made with a throat radius of not less than the duct width. G. Horizontal ductwork shall be strongly supported with galvanized hangers in accordance with the requirements of the ASHRAE guide
- and public authorities having jurisdiction. H. Provide double thickness turning vanes at all sharp right angle turns. I. Plenums shall be made of 18 gauge galvanized sheet steel reinforced horizontally on a maximum of 48 inch centers by 1-1/2 x 1-1/4 x 1/8

inch galvanized angles and reinforced vertically by 1-1/2 inch standing

- J. Plenum access doors 24 x 54 inch minimum size shall be galvanized sheet steel doors and frames properly reinforced to prevent breathing. Door shall be of same gauge as the duct or casing and shall have 1 inch insulation with galvanized sheet steel on both sides. Each door shall be hung on 5% tee hinges with one or more catches which are operable from both sides and similar to Ventfabrics, Inc. 260 Ventlock Hatch. Doors shall be hung to open against pressure and shall be fitted
- with felt to ensure airtightness. K. Flexible connections for air ducts shall be 16 oz. airtight Ventglass noncombustible fabric with fire retardant neoprene coating on outside Attach to ductwork by lock seam. Install not more than 6 inches long. Provide where required or indicated.
- L. Seal joints on main cold supply air ducts at each floor with UL classified sealant. Sealant shall be specifically designed to seal high pressure ductwork.

2.10 TURNING VANES

- A. Both dimensions less than 48 inches: Single vane or approved double thickness airfoil vanes.
- B. Either dimension greater than 48 inches: Double thickness airfoil vanes of approved pattern.
- C. Rectangular smooth radius elbows: Provide multiple splitter vanes.

2.11 DAMPERS

- A. Provide balancing volume dampers in each branch duct and in each main duct of constant volume systems to provide for complete air balancing. Fit each manual volume damper with bearings and an adjusting device having a locking mechanism. Provide access panels if concealed or inaccessible through ceiling or wall.
- B. Balancing dampers where neither dimension of duct exceeds 17 inches may be a job fabricated butterfly type consisting of a blade constructed of 18 gauge galvanized steel securely riveted or welded at its center

- axis to a square operating rod.
 - C. Balancing dampers where either dimension exceeds 18 inches shall be Air Balance
 - AC-116, opposed blade type. D. Fire dampers: Fusible link out of airstream type manufactured in

accordance with requirements of State Fire Marshal and public

- authorities having jurisdiction, with permanent labeling identification. Provide suitable access for servicing dampers. E. Combination Smoke and Fire Dampers:
- 1. General Description: Ruskin FSD-36 or equal by Greenheck, Leakage class 2, for wall, floor, grille, or out of wall application as indicated on the plans. Labeled according to UL 555S. Combination fire and smoke dampers shall be labeled according to
- UL 555 for 1-1/2 hour rating. 2. Fusible Links: Resettable, 165 deg F rated
- 3. Frame and Blades: 0.064-inch thick galvanized sheet steel. 4. Mounting Sleeve: Factory-installed, galvanized sheet steel; length
- to suit wall or floor application. 5. Damper Motors: Provide actuator by manufacturer. Electrical connection shall be 115 V, single phase, 60 Hz.
- F. Install fire and smoke dampers according to manufacturer's
- UL-approved written instructions. G. Backdraft Dampers: Ruskin CBD2 and CBD6 with extruded aluminum frames, aluminum blades, and vinyl edge seals and adjustable counterweights.

2.12 INLINE CENTRIFUGAL FANS

- A. Greenheck Model SQ. Fan shall be duct mounted, direct driven
- centrifugal square inline B. Fan shall be manufactured at an ISO 9001 certified facility. Fan shall be listed by Underwriters Laboratories (UL 705). Fan shall bear the AMCA certified ratings seal for sound and air performance.
- C. The fan shall be of bolted construction utilizing corrosion resistant fasteners. Housing shall be minimum 18 gauge galvanized steel with integral duct collars. Bolted access doors shall be provided on three
- D. Wheel shall be centrifugal backward inclined, constructed of 100% aluminum, including a precision machined cast aluminum hub. Wheel shall be balanced in accordance with AMCA Standard 204-96, Balance Quality and Vibration Levels for Fans.

E. Motor shall be heavy duty type with permanently lubricated sealed ball

sides, sealed with closed cell neoprene gasketing.

2.13 SINGLE DUCT VARIABLE AIR VOLUME BOXES (DDC)

bearings and furnished at the specified voltage, phase, and enclosure. F. Bearings shall be permanently lubricated, sealed ball bearings and selected for a minimum L50 life in excess of 200,000 hours at maximum

catalogued operating speed. G. The fan shall be provided with Varigreen type motor that accepts 0-10VDC signal for motor speed adjustment.

- A. Terminal units shall be PRICE Model SDV, pressure independent, single inlet type. Units shall be provided with factory installed electronic actuator, as furnished under Section 15900, flow controller and required relays to change set point in response to thermostat control. Regulators shall be factory preset for minimum and maximum air quantities designated. Units shall be capable of varying air quantity from the maximum set point within the normal operating range to minimum set point indicated. At maximum set point the air volume shall not vary more than +/- 5% when subjected to inlet variations from 1 to 6 inches of water. On a call for less than maximum cooling, the unit shall reduce the primary air volume to satisfy the requirements. For exterior zones, the reheat coil shall be activated in sequence after the minimum
- setting is reached. B. Terminal units shall be selected as indicated without exceeding pressure drop and noise criteria curve of NC 30. Provide sound insulation downstream as indicated and required to attain above noise

2.14 DIFFUSERS, REGISTERS AND GRILLES

- A. Air distribution equipment shall be of sizes and capacities indicated, furnished in factory finished enamel of color selected. Submit paint
- samples for approval. B. Square Ceiling Diffusers: Titus model PAS, steel construction with baked on heavy duty envirothane enamel coating with aluminum perforated face. Mounting shall be adapted to ceiling suspension system. 12 x 12 inch and 20 x 20 inch ceiling module shall be used for
- hard ceiling installation and in all restrooms. D. Return and Relief Air Grilles: Titus model PDR, steel construction with baked on heavy duty envirothane enamel coating with aluminum perforated face to match ceiling diffusers.
- M. Provide branch balancing damper with remote damper operator by Pottorff or Young Regulator in inaccessible locations where no access panels are indicated on the drawings.

2.15 HVAC INSTRUMENTATION AND CONTROLS

- A. Contractor shall familiarize himself with the existing controls system at the job site prior to proposal of work to assure that scope is adequately understood.
- B. Direct digital controls:
- 1. New and remodel VAV boxes New and remodel boxes shall be provided with controllers which are compatible with existing installed DDC systems where present. Contractor shall include all points to match existing configuration of boxes. Submit manufacturer and points list for approval. Thermostats shall match existing. Submit sample of thermostat to architect for approval.
- 2. New fans and unitary equipment New and remodeled equipment shall be tied into existing DDC controls systems in a manner to match the existing. Include all reprogramming of the existing DDC controls system to operate and sequence new equipment. Submit manufacturer, points list, and sequences proposed. Thermostats shall match existing. Submit sample of thermostat to architect for

HOTEL DELL ORONADO.

Fitness Members Area Renovation

1500 Orange Avenue Coronado, CA 92118



Hospitality

Mechanical/Electrical/Plumbing Engineer tk1sc Collaborative 858.362.6800

> COLLABORATIVE 15231 Laguna Canyon Road, Suite 100

Irvine, California 92618

949.751.5800 www.tk1sc.com

Project Leader - Kenneth McClendon

Mechanical Lead - Kenneth McClendon

tk1sc Job #: 2019-0727



14 NE 1st Avenue, Suite 507

Miami, FL 33132 T+1 (305) 455 4216

No Date Description 09-17-21 Permit Set 1\ 01-05-22 Owner Revisions

Drawing Title

SPECIFICATIONS

As Noted Date 09-17-2021 Drawn By Project No.

SPECIFICATIONS

Item: Manufacturer:

1. Pipe Hangers & Supports: Fee & Mason, Elcen

2 Vibration Isolation: Mason Industries

3. Insulation: Owens-Corning, Certainteed, Knauf 4. Valves: Nibco. Crane

5. Strainers: Crane, Walworth, Strong, Keckley, Mueller

6. Pressure Gauges: Marsh. Marshalltown. Trerice

7. Thermometers: Palmer, Trerice

8. Gas-Fired Make-up Air Units: Modine

9. Computer Room AC Units: Data-Aire

10. Rooftop Packaged Unit: Trane

11. Split System AC Unit: Trane

12. Water Source Heat Pump: Climate Master 13. Four-pipe Fan Coil Units: Enviro-Tec

14. Dampers: Pottorff, Greenheck

15. Fans: Greenheck, Twin City 16. VAV Boxes: Titus, Kreuger

17. Diffusers, Registers, Grilles: Price, Krueger

PART 3-EXECUTION

3.01 STATEMENT

A. All Heating, ventilation and air conditioning shall be installed in accordance with the requirements of all governing authorities.

3.02 LOCATIONS AND ACCESSIBILITY

A. Drawings indicate desired location and arrangement of piping, ductwork, equipment and other items, and are to be followed as closely as possible. All offsets and interferences may not be indicated due to

the scale of the Drawings. Coordinate work with all other trades. B. Valves, motors, controls and other devices requiring service, maintenance and adjustment shall be placed in fully accessible positions and locations. Provide access doors where required in ductwork and construction and render all such devices accessible.

3.03 EQUIPMENT IDENTIFICATION

A. All major equipment shall bear firmly attached metal nameplates which state name of manufacturer, model number and electrical data. An additional permanent label shall be affixed to each equipment which will clearly indicate by number which operating and maintenance manual explains maintenance requirements in detail.

B. Valve Identification:

1. Valve charts: Typewritten charts not less than 8x10 inches shall be made showing assigned numbers controlled in each system by each valve in mechanical equipment rooms only. Charts shall be mounted behind aluminum framed glass in chiller room.

2. Valve tags: Provide tag consisting of 2 inch diameter, 20 gauge, stainless steel or copper disk for each main line shut-off valve or cock. Fasten tags in place with continuous steel ring or chain around stem of valves and around pipe for cock. Disks shall be stamped with a number corresponding to identification (or location) number shown on valve chart and with service designation with 1/4 inch high letters.

C. Pipe Identification: Mark each individual pipe for quick and easy identification with Idento Bands, aluminum with enamel finish, 1-1/2 inches wide, installed as recommended by manufacturer after completion of piping and finish painting. Unless otherwise specified, coding shall conform to Scheme for the Identification of Piping Systems (ANSI A13.1-1956). Color scheme shall be approved. Base color for markers shall be as follows:

Compressed air: Orange Condenser water: Green Space heating hot water: Orange Make-up water: Green Refrigerant piping: Yellow

3.04 INITIAL LUBRICATION, ADJUSTING AND FILLING SYSTEMS

A. Before operating any mechanical systems, equipment bearings shall be lubricated and bolts, pulleys, and other moving parts checked for alignment and tolerances in accordance with manufacturer s operating instructions. Piping and liquid systems shall be flushed out and filled with operating fluids. After tests, valves and other parts of work shall be adjusted for quiet operation. Strainers shall be cleaned out by removing and washing basket or screen. Compressors shall have lubricating oil changed. Vibrations and noise shall be suppressed.

3.05 CLEANING OF EQUIPMENT, MATERIALS AND PREMISES

A. Clean equipment and materials thoroughly. Leave surfaces to be painted smooth, clean, and ready for painters. Clean entire premise of unused materials, rubbish, debris, grease spots and dirt left by subcontractors. Remove, clean and replace pipeline strainers after systems have been in operation for a period of 30 calendar days.

3.06 HANGERS AND SUPPORTS

A. Hold horizontal pipe runs firmly in place using approved steel and iron hangers, supports, and/or pipe rests, unless otherwise indicated. Suspend hanger rods from concrete inserts or from approved brackets, clamps or clips. Hang pipes individually or in groups if supporting structure is adequate to support weight of piping and fluid. Except for buried piping, hang or support pipe runs so they may expand or contract freely without strain to pipe or equipment.

B. Horizontal Steel Piping: Provide hangers or supports every 10 feet except every 8 feet for piping under 1 inch in diameter, unless otherwise specified.

C. Horizontal Copper Tubing: For 2 inch diameter and over, provide hangers, every 10 feet, for 1-1/2 inch diameter and smaller, every 6

D. Vertical Piping: Support at every floor with wrought iron pipe clamps. E. Branches: Provide separate hangers or supports for branch lines 6 feet or more in length.

3.07 EQUIPMENT AND MATERIALS

A. Install per manufacturer's recommendations.

3.08 ACCESSIBILITY

A. Install work readily accessible for normal operation, reading of instruments, adjustment, service, inspection and repair. Provide access panels where indicated and required.

3.09 EXPANSION AND CONTRACTION

A. Install piping subject to expansion and contraction with expansion loops made up of bends or fittings, expansion joints, swing joints, or other approved methods or devices. Branch lines from main subject to expansion and contraction shall have a swing joint at point of connection with the main. Risers which pass through one or more floors shall have swing joints at their base. Anchor lines subject to expansion and contraction by approved methods to restrict movement.

3.10 SYSTEM BALANCING

A. Section Includes: Testing, adjusting and balancing of mechanical equipment and systems.

B. Provide and be responsible for protection and repair of adjacent surfaces and areas which may become damaged as a result of Work of this Section. Protect Work hereunder until completion and final acceptance. Repair or replace damaged or defective Work to original specified conditions, at no extra cost to the Owner.

C. All performance testing and balancing of the mechanical systems

1. Supply air systems.

2. Return air, fresh air and exhaust air systems. 3. Hydronic systems.

4. Report and report forms.

D. Submittals: Submit a complete testing and balancing procedure indicating all test equipment that will be used, testing procedures, test data sheets, systems schematics and points of testing.

1. Test and Balance Data: Submit test and balance data on completion of work under this Section.

2 Certification: Certify in writing that system has been adjusted and balanced and design conditions have been attained.

E. Contractor shall provide to the Architect. HVAC Contractor and Electrical Contractor requirements for drive changes, installation of additional dampers, vanes, grille baffles or other items as may be required to balance the system to the Owner's satisfaction.

F. Verification of Conditions: Prior to testing and balancing, balancing contractor shall inspect equipment and materials to assure that all balancing operations can be performed. Balance subcontractor shall arrange with HVAC Contractor and Electrical Contractor for satisfactory correction of all defects in workmanship and/or material that could affect the work specified herein.

G. System Operation: Contractor shall coordinate with HVAC specifications and controls specifications and contractors to have all parts of systems in full operation and shall continue the operation of same during each working day of testing and balancing.

H. System testing and balancing shall be performed by an independent agency certified by the Associated Air Balance Council (AABC) or

I. All test instruments shall be accurately calibrated and maintained in good working order. Test instruments shall have certification by the manufacturer or by an approved test laboratory within one year of the

J. Air Distribution Testing and Balancing:

1. Test and adjust blower RPM to design requirements.

2. Test and record motor full load amperes.

3. Make pitot tube transverse of main supply, return, exhaust and

outside air ducts and obtain design CFM. 4. Test and record system static pressures, suction and discharge.

5. Test and adjust system for design exhaust air CFM.

6. Test and adjust system for design outside air CFM.

7. If more than one outside air design condition exists (demand control ventilation), balance report shall include separate tests for minimum condition and maximum condition.

8. Test and record entering air temperature (D.B. heating and cooling).

9. Test and record entering air temperature (W.B. cooling). 10. Test and record leaving air temperatures (D.B. heating and

11. Test and record leaving air temperature (W.B. cooling).

12. Adjust all main supply and return air ducts to proper design CFM. 13. Test and adjust each VAV box to within plus-minus 5% of design.

14. Test and adjust each diffuser, grille and register to within plus-minus 5% of the amount shown on the drawings. 15. Each grille, diffuser and register shall be identified as to location

and area. 16. Size, type and manufacturer of diffusers, grilles, registers and all tested equipment shall be identified and listed. Manufacturer s ratings on all equipment shall be used to make required calculations.

17. Readings and tests of diffusers, grilles and registers shall include the required FPM velocity and test velocity, required CFM and test result CFM after adjustments. 18. In cooperation with the control manufacturer's representative, the

setting adjustment of automatically operated controls to operate as specified, indicated and/or noted. 19. All diffusers, registers and grilles and all equipment shall be adjusted to maintain the design conditions.

K. Duct Leakage Testing:

1. Test apparatus shall be a high pressure portable blower with an orifice flow measuring device. Each orifice assembly shall be accurately calibrated with its own calibration curve.

2. Contractor to close off and seal all openings in the duct section to be tested. 3. Each section duct mains shall be tested at a pressure corresponding to its pressure rated, as tabulated below. Total

allowable leakage at the testing pressure shall not exceed 2.5% of the total design CFM for the section being tested.

Pressure Test Rating Pressure 1 in. 1.5 in.

2 in. 2.5 in. 4 in. 4.5 in. 6 in. 6.5 in.

4. Duct system for smoke control shall be tested in accordance with Section 905 of the California Building Code by the required special inspector or special inspection agency.

L. Space pressure testing

1. For separate air systems serving separate rooms, balance contractor shall perform space pressure testing.. 2. Pressure measurements shall be recorded for each system at system boundaries and outside doors...

Pressure testing shall occur with doors closed.

M. Hydronic System Balancing: Test, balance and adjust all water systems. Adjust water flows to boilers, pumps, coils, etc., to amounts shown on Drawings. Record following points where applicable to the respective system and any other items necessary to establish that each equipment item is operating properly and at designed capacities and conditions.

1. Outside air temperatures D.B. and W.B.

Boilers:

Water inlet and outlet temperatures. Water inlet and outlet pressures. Water inlet and outlet flows.

3. Pumps:

Pump discharge pressure. Pump suction pressure. Pump differential head. Pump cut-off head.

N. Coordinate Tests with the manufacturer of each equipment.

O. Witness: Notify Architect in writing two weeks prior to testing and balancing of all major equipment in order to arrange that Architect s representative will witness the tests.

P. Reporting

Reports shall include all outlets, balanced to tolerances indicated above. Indications of "not accessible" or "not operating" are not acceptable. Balance contractor shall resolve any access issues with mechanical subcontractor before submitting report.

For any new pump or fan (e.g. exhaust fan, supply fan), include pump curve or fan curve in the report. Drive changes, if required to achieve design air quantities, are

the responsibility of contractor. Q. Mechanical and balancing contractors shall be responsible for all Title 24 Acceptance testing requirements as indicated on the compliance documentation. Copies of all Acceptance tests shall be included in the

air balance report and submitted to the engineer and the owner for

3.11 CONNECTION

A. Connections between two dissimilar metal pipes shall be made with dielectric unions.

3.12 TESTS

A. Furnish necessary labor and equipment for testing.

B. Hydrostatic Tests: Make by completely filling piping system with water and eliminating accumulations of air so that leakage, no matter how small, will be apparent on testing gauge immediately. Maintain pressure until pipe under test has been examined, but in no case less than 24 hours. Test systems at following pressure:

SYSTEM TEST PRESSURE Chilled Water 125 psig Condenser Water 125 psig Hot Water 125 psig

3.13 INSTALLATION

A. Cooling towers, boiler, pumps, air handling units, exhaust fans and other equipment shall be installed on concrete bases and bolted to vibration isolators and then anchored to structures.

3.14 COCKS

A. Upon balancing of system, all balancing cocks shall have body plug permanently set to indicate balance position of plug.

3.15 AIR DISTRIBUTION EQUIPMENT LOCATIONS

A. Air distribution equipment locations shall be coordinated with architectural drawings.

3.16 TURNING VANES

A. Turning vanes shall be installed in all right angle sharp turns in ducts.

3.17 DUCT LINING

A. Where indicated, specified duct dimensions are net clear dimensions, i.e., clear dimensions, after insulation has been installed.

3.18 REPAIR OF EXISTING SURFACES

A. Contractor shall provide and be responsible for protection and repair of adjacent existing surfaces and areas that may have been damaged as a result of demolition and new work.

3.19 CAPPING OF DUCTS

A. All existing ducts that are removed and not reused shall be capped airtight and sealed with "miracle" duct sealer and D-617 or equal.

3.20 CEILING DIFFUSER COORDINATION

A. Contractor shall strictly coordinate all ceiling diffusers and grilles with architectural reflected ceiling plan. If any discrepancies are encountered, the engineer shall be notified for clarification.

3.21 THERMOSTAT LOCATION

A. Contractor shall coordinate final location of all thermostats with architect and tenant construction coordinator prior to any rough-in installation work. Coordinated shop drawings showing thermostats, sensors, switches, and all other wall devices should be provided to the design team for review.

B. Provide insulated backing on all thermostats located on exterior walls so fluctuations in wall temperature do not provide false readings. Verify that thermostats will not be installed in direct sunlight. C. Provide white thermostat covers for all locations within scope of work.

3.22 AS-BUILT DRAWINGS

A. Contractor shall provide record as-built drawings to tenant construction coordinator and architect at the completion of tenant construction.

3.23 SMOKE DAMPERS IN DUCTWORK

A. Maintain net free area equal to duct size at all smoke and fire dampers. B. Smoke and fire dampers shall be provided with adequate access doors by this contractor.

3.24 THERMOSTAT REQUIREMENTS

A. Room thermostats shall be capable of being set to maintain space temperature set points for 55 degrees to 85 degrees and shall be capable of operating the heating and cooling in sequence. Thermostats shall be adjustable to provide a temperature range of 5 degrees between full heating and full cooling being supplied. Temperature control system shall operate in accordance with the base building sequence of operation.

3.25 DUCT ELBOWS

3.26 DIFFUSER THROW PATTERN

A. Provide minimum duct radius on elbows at one and one half times duct

A. All ceiling diffusers shown on the plans shall be provided as four way

horizontal position unless otherwise noted. 3.27 DUCTWORK REQUIREMENTS OF UMC

A. All ductwork shall conform to chapter 6 of the Uniform Mechanical

throw unless otherwise noted. Pattern blades shall be set in a

3.28 DUCT AND EQUIPMENT REQUIREMENTS OF TITLE 24

A. All supply air ducts and fire dampers shall be installed per Title 24

B. All mechanical equipment shall be certified by the manufacturer for compliance with Title 24 energy requirements.

3.29 RETURN AIR PLENUM REQUIREMENTS

A. Return air plenum shall not contain any combustible material.

3.30 ACCESS REQUIREMENTS

A. Provide access and clearance requirements per 2016 Mechanical code and manufacture installation whichever is more restrictive.

3.31 DUCTWORK PROTECTION DURING CONSTRUCTION

A. At the time of rough installation or during storage on the construction site and until final startup of the heating and cooling equipment, all ducts and other related air distribution component openings shall be covered with tape and plastic to reduce the amount of dust and debris which may collect in the system.

3.32 TEMPORARY VENTILATION DURING CONSTRUCTION

A. The permanent HVAC system shall only be used during construction if necessary to condition the building within the required temperature range for material and equipment installation. If the HVAC system is used during construction, use return air filters with MERV-8 Filtration. Replace all filters immediately prior to occupancy.

3.33 CONTROLS INSTALLATION

A. WIRING

a. Low voltage (Class 2) wiring in concealed accessible spaces may

be plenum rated and is not required to be enclosed in conduit. b. NEC Class 1 (Line Voltage) wiring shall be UL listed in approved raceway as specified by NEC.

c. Low-Voltage wiring shall meet NEC Class 2 requirements. Subfuse

Low-Voltage power circuits as required to meet Class 2 current d. Conduit: All conduit shall comply with the minimum requirements of the local authority having jurisdiction.

e. Install wiring in conduit where subject to mechanical damage and at levels below 10ft in mechanical, electrical, or service room.

f. Install wiring in conduit for wall sensors and extend the conduit 6" above t[he ceiling. Install a bushing on the end of the

i. Install wiring in conduit above inaccessible ceilings. ii. Install class 1 and class 3 wiring in separate conduits. Boxes and panels containing high voltage wiring and equipment shall not be used for Low-Voltage wiring 3except for the purpose of interfacing the two through relays and transformers.

iii. Conceal conduit except within mechanical. Electrical, or service rooms, maintain minimum clearance of 6" between raceway and high-temperature equipment such as team pipes or flues.

iv. Flexible metal conduit and liquid tight flexible metal conduit less than ½ inch electrical trade size. B. BAS contractor shall provide stepdown transformers.

3.34 CONTROLS INSTALLATION

A. Project record documents. Submit three copies of record (as-built) documents upon completion of installation for approval prior to final completion. Submittal shall consist of:

B. Project record drawings of as-built versions of submittal shop drawings and product data shall be provided in electronic. As-built floor plans indicating the routing of MSTP communication wiring shall be included.

END OF SECTION

HOTELDELLORONADO.

Fitness Members Area Renovation

1500 Orange Avenue Coronado, CA 92118



González Architects Hospitality

Mechanical/Electrical/Plumbing Engineer tk1sc Collaborative 4755 Eastgate Mall, Suite 150 San Diego, CA 92121 858.362.6800

> COLLABORATIVE 15231 Laguna Canyon Road, Suite 100

> > Irvine, California 92618

949.751.5800 www.tk1sc.com

Project Leader - Kenneth McClendon

Mechanical Lead - Kenneth McClendon

tk1sc Job #: 2019-0727



14 NE 1st Avenue, Suite 507 Miami, FL 33132 T+1 (305) 455 4216 No Date Description 09-17-21 Permit Set 1\ 01-05-22 Owner Revisions

SPECIFICATIONS

Drawing Title

As Noted 09-17-2021 Drawn By Project No.

SPECIFICATIONS

ONSTRU

STATE OF CALIFORNIA		STATE OF CALIFORNIA
STATE OF CALIFORNIA Mechanical Systems	STATE OF CALIFORNIA Mechanical Systems	Mechanical Systems
NRCC-MCH-E (Created 09/2020) CERTIFICATE OF COMPLIANCE CERTIFICATE OF COMPLIANCE NRCC-MCH-E	NRCC-MCH-E (Created 09/2020) CERTIFICATE OF COMPLIANCE CERTIFICATE OF COMPLIANCE NRCC-MCH-E	NRCC-MCH-E (Created 09/2020) CERTIFICATE OF COMPLIANCE CRITIFICATE OF COMPLIANCE NRCC-MCH-E
This document is used to demonstrate compliance for mechanical systems that are within the scope of the permit application and are demonstrating compliance using the prescriptive path outlined in §140.4, or §141.0(b)2 for alterations.	Project Name:Hotel Del Coronado Fitness Members ARea RenovationReport Page:Page 2 of 10Project Address:1500 Orange AvenueDate Prepared:2021-07-29	Project Name: Hotel Del Coronado Fitness Members ARea Renovation Report Page: Page 3 of 10 Project Address: 1500 Orange Avenue Date Prepared: 2021-07-29
Project Name: Hotel Del Coronado Fitness Members ARea Renovation Report Page: Page 1 of 10 Project Address: 1500 Orange Avenue Date Prepared: 2021-07-29	D. EXCEPTIONAL CONDITIONS	01 02 03 04 05 06 07 08
A. GENERAL INFORMATION	This table is auto-filled with uneditable comments because of selections made or data entered in tables throughout the form.	Fan Name or Item Tag Fan Function Qty Supply Airflow HP Unit ² Design HP Unit ² De
01 Project Location (city) Coronado 04 Total Conditioned Floor Area 3,560 02 Climate Zone 7 05 Total Unconditioned Floor Area 0	Table H indicates a Fan Power System Index that exceeds the maximum allowed per §140.4(c). Please revise to demonstrate compliance.	Item Tag
03 Occupancy Types Within Project: 06 # of Stories (Habitable Above Grade) 1 Office (B) Retail (M) Non-refrigerated Warehouse (S)	E. ADDITIONAL REMARKS This table includes remarks made by the permit applicant to the Authority Having Jurisdiction.	EF-8 Exhaust 1 2,800 Nameplate HP 1
Hotel/ Motel Guest Rooms (R-1) School (E) Healthcare Facility (I) High-Rise Residential (R-2/R-3) Relocatable Class Bldg (E) Other (Write In): Locker Room	The case in the case of the particular to the case of	Calculated Adjustment (in H ₂ O)
FOOTNOTES: Climate zone can be determined on the California Energy Commission's website at http://www.energy.ca.gov/maps/renewable/building_climate_zones.html	F. HVAC SYSTEM SUMMARY (DRY & WET SYSTEMS)	Total System Design Supply Airflow (CFM): 2,800 Total System Design (B)HP: 1 Maximum System Fan Power (B)HP:
B. PROJECT SCOPE	This Section Does Not Apply	
Table Instructions: Include any mechanical systems that are within the scope of the permit application and are demonstrating compliance using the prescriptive path outlined in §140.4, or §141.0(b)2 for alterations.	G. PUMPS	¹ FOOTNOTE: Computer room economizers must meet requirements of <u>§140.9(a)</u> and will be documented on the NRCC-PRC-E document. ² The unit used for HP must be consistent for all fans within a system.
My project consists of (check all that apply) 01 02 03	This Section Does Not Apply	I. SYSTEM CONTROLS
Air System(s) Wet System Components Dry System Components	H. FAN SYSTEMS & AIR ECONOMIZERS Table Instructions: Complete the following Table for fan systems to demonstrate compliance with prescriptive requirements found in §140.4(c), §140.4(e) and §140.4(m). First	This Section Does Not Apply
Heating Air System Water Economizer Air Economizer Cooling Air System Pumps Electric Resistance Heat	document the system details, then add fans within that system to document compliance with fan power requirements. Fan systems serving only process loads are exempt from these requirements and do not need to be included in Table H.	J. VENTILATION AND INDOOR AIR QUALITY
Mechanical Controls Hydronic System Piping Fan Systems Mechanical Controls (existing to remain, altered or new) Mechanical Controls (existing to remain, altered or new)	System Name: FE-7 Fconomizer! NA: < 54 kBtu/h cooling Economizer System Fan Constant Volume	This Section Does Not Apply
new) Chillers Ventilation	O1	K. TERMINAL BOX CONTROLS
☐ Boilers Zonal Systems/ Terminal Boxes	Fan Name or Fan Function Qty Supply Airflow HP Unit ² Design Fan Power Pressure Drop Adjustment - <u>Table 140.4-B</u>	Table Instructions: Complete the following Table to demonstrate compliance with prescriptive zone control requirements in \$\frac{\$140.4(d)}{0}\$. 01 02 03 04 05 06 07 08 09 10 11 12
C. COMPLIANCE RESULTS Table Instructions: If any cell on this table says "DOES NOT COMPLY" or "COMPLIES with Exceptional Conditions" refer to Table D. for guidance.	Item Tag HP Device Design Airflow through Device (CFM)	Design Deadband Compliance Reheated, Recooled, Mixed Air Compliance
01 02 03 04 05 06 07 08 09 System System	EF-7 Exhaust 1 1,100 Nameplate HP 0.25	Zone/System/ VAV Box Zone/ Control Strategy page 5140 4(4) Peak Primary Air
Summary Pumps AND Economizers AND \$110.2. AND Ventilation AND Controls AND \$110.2. AND Towers	Calculated Adjustment (in H ₂ O)	Name or Zonal Control Strategy per 9.140.4(d) Primary In Recooled Mixed Outside Air Peak Deadband Primary Suffer Suf
\$140.4(k) \$140.4(k) \$140.4(c) \$140.4(c) \$140.4(d) \$140.4		CFM CFM CFM CFM CFM CFM Airflow CFM Airflow CFM
(See Table F) (See Table G) (See Table H) (See Table I) (See Table J) (See Table K) (See Table L) (See Table M) AND AND Yes AND Yes AND Yes AND Yes AND Yes AND COMPLIES	Total System Design Supply Airflow (CFM): 1,100 Total System Design (B)HP: 0.25 Maximum System Fan Power (B)HP: System Name: EF-8 Economizer:¹ NA: ≤ 54 kBtu/h cooling Economizer NA: ≤ 54 kBtu/h cooling Economizer Constant Volume	F6 NA: Pressurization control Yes
Mandatory Measures Compliance (See Table Q for Details) COMPLIES	Table Continued	F9 NA: Pressurization control Yes Table Continued
A Building Energy Efficiency Standards - 2019 Nonresidential Compliance: http://www.energy.ca.gov/title24/2019standards/ September 2020	CA Building Energy Efficiency Standards - 2019 Nonresidential Compliance: http://www.energy.ca.gov/title24/2019standards September 2020	CA Building Energy Efficiency Standards - 2019 Nonresidential Compliance: http://www.energy.ca.gov/title24/2019standards September 2020
rate of california Mechanical Systems	STATE OF CALIFORNIA Mechanical Systems	STATE OF CALIFORNIA Mechanical Systems
RCC-MCH-E (Created 09/2020) CALIFORNIA ENERGY COMMISSION CERTIFICATE OF COMPLIANCE NRCC-MCH-E	NRCC-MCH-E (Created 09/2020) CALIFORNIA ENERGY COMMISSION CERTIFICATE OF COMPLIANCE NRCC-MCH-E	NRCC-MCH-E (Created 09/2020) CALIFORNIA ENERGY COMMISSION CERTIFICATE OF COMPLIANCE NRCC-MCH-E
roject Name: Hotel Del Coronado Fitness Members ARea Renovation Report Page: Page 4 of 10 page 14 of	Project Name: Hotel Del Coronado Fitness Members ARea Renovation Report Page: Page 5 of 10 Project Address: 1500 Orange Avenue Date Prepared: 2021-07-29	Project Name: Hotel Del Coronado Fitness Members ARea Renovation Report Page: Page 6 of 10 Project Address: 1500 Orange Avenue Date Prepared: 2021-07-29
Of the repared Date Prepared: Z021-07-29 01 02 03 04 05 06 07 08 09 10 11 12	M. COOLING TOWERS	O. DECLARATION OF REQUIRED CERTIFICATES OF ACCEPTANCE
Design Deadband Compliance Reheated, Recooled, Mixed Air Compliance	This Section Does Not Apply	Table Instructions: Selections have been made based on information provided in previous tables of this document. If any selection needs to be changed, please explain why in Table E. Additional Remarks. These documents must be provided to the building inspector during construction and can be found online at https://www.energy.ca.gov/
Zone/System/ NAV Poy Reheated 20% (30% if 1st Stage 2nd Stage 2nd Stage 2nd Stage 2nd Stage 2nd Stage 2nd Stage 3nd Stage 3n	N. DECLARATION OF REQUIRED CERTIFICATES OF INSTALLATION	title24/2019standards/2019_compliance_documents/Nonresidential_Documents/NRCA/
Name or VAY BOX Name or VAY Name or VAY BOX N	Table Instructions: Selections have been made based on information provided in previous tables of this document. If any selection needs to be changed, please explain why in Table E. Additional Remarks. These documents must be provided to the building inspector during construction and can be found online at https://www.energy.ca.gov/	YES NO Form/Title Systems To Be Field Verified Pass Fail
CFM CFM CFM Airflow CFM Airflow CFM Airflow CFM Heating	title24/2019standards/2019_compliance_documents/Nonresidential_Documents/NRCI/ Field Inspector	NRCA-MCH-02-A Outdoor Air must be submitted for all newly installed HVAC units.
F7 NA: Pressurization control CFM DB Nate: Max Flow? Yes	YES NO Form/Title Systems To Be Field Verified Pass Fail	Note: MCH02-A can be performed in conjunction with MCH-07-A Supply Fan VFD Acceptance (if applicable) since testing activities overlap.
165	NRCI-MCH-01-E - Must be submitted for all buildings.	NRCA-MCH-03-A Constant Volume Single Zone HVAC NOTE: This form does not automatically move to "Yes" If Constant Volume Single Zone
. DISTRIBUTION (DUCTWORK AND PIPING)		NOTE: This form does not automatically move to "Yes". If Constant Volume Single Zone HVAC Systems are included in the scope, permit applicant should move this form to "Yes"
Table Instructions: Complete the following tables to show compliance with mandatory pipe insulation requirements found in \$120.3 and prescriptive requirements found in \$140.4(1) for duct leakage testing.		"Yes". ○ NRCA-MCH-04-A Air Distribution Duct Leakage
Duct Leakage Sealing Duct leakage testing triggered for		international state and a second
ne answers to the questions below AHU-1 Duct. leakage testing ringgered for No Poly to the following duct system(s): 11 No The scope of the project includes only duct systems serving healthcare facilities.		INTO THE LOCATION OF THE LOCAT
No Duct system provides conditioned air to an occupiable space for a constant volume, single zone, space-conditioning system.		NRCA-MCH-06-A Demand Control Ventilation Systems Acceptance must be submitted for all systems required to employ demand controlled ventilation (refer to §120.1(c)3)
13 No The space conditioning system serves less than 5,000 ft ² of conditioned floor area. 14 No The <u>combined</u> surface area of the ducts in the following locations is more than 25% of the total surface area of the entire duct system:		can vary outside ventilation flow rates based on maintaining interior carbon dioxide (CO2) concentration setpoints.
Outdoors In a cross directly under a reaf that has a H factor greater than the H factor of the spiling or if the reaf does not meet the		NRCA-MCH-07-A Supply Fan Variable Flow Controls
requirements of §140.3(a)1B or if the roof has fixed vents or openings to the outside/ unconditioned spaces		○ NRCA-MCH-08-A Valve Leakage Test
In an unconditioned crawlspace In other unconditioned spaces		
No The scope of the project includes extending an existing duct system, which is constructed, insulated or sealed with asbestos. The scope of the project includes an existing duct system that is documented to have been previously sealed as confirmed through field verification and		○ NRCA-MCH-09-A Supply Water Temperature Reset Controls □ □
Yes diagnostic testing in accordance with procedures in the <u>Reference Nonresidential Appendix NA2.</u> Duct system shall be sealed in accordance with the California Mechanical Code.		○ NRCA-MCH-10-A Hydronic System Variable Flow Controls
, and the second court of		NRCA-MCH-11-A Automatic Demand Shed Controls
CA Building Energy Efficiency Standards - 2019 Nonresidential Compliance: http://www.energy.ca.gov/title24/2019standards September 2020	CA Building Energy Efficiency Standards - 2019 Nonresidential Compliance: http://www.energy.ca.gov/title24/2019standards September 2020	CA Building Energy Efficiency Standards - 2019 Nonresidential Compliance: http://www.energy.ca.gov/title24/2019standards September 2020
		STATE OF CALIFORNIA
	STATE OF CALIFORNIA	
Mechanical Systems IRCC-MCH-E (Created 09/2020) CALIFORNIA ENERGY COMMISSION	Mechanical Systems NRCC-MCH-E (Created 09/2020) CALIFORNIA ENERGY COMMISSION	Mechanical Systems NRCC-MCH-E (Created 09/2020) CALIFORNIA ENERGY COMMISSION
Alechanical Systems RCC-MCH-E (Created 09/2020) CALIFORNIA ENERGY COMMISSION CERTIFICATE OF COMPLIANCE NRCC-MCH-E Project Name: Hotel Del Coronado Fitness Members ARea Renovation Report Page: Page 7 of 10	Mechanical Systems NRCC-MCH-E (Created 09/2020) CERTIFICATE OF COMPLIANCE Project Name: Hotel Del Coronado Fitness Members ARea Renovation Report Page: Page 8 of 10	Mechanical Systems NRCC-MCH-E (Created 09/2020) CERTIFICATE OF COMPLIANCE Project Name: Hotel Del Coronado Fitness Members ARea Renovation Report Page: Page 9 of 10
Wechanical Systems IRCC-MCH-E (Created 09/2020) CERTIFICATE OF COMPLIANCE Project Name: Hotel Del Coronado Fitness Members ARea Renovation Report Page: Page 7 of 10 Project Address: 1500 Orange Avenue Date Prepared: 2021-07-29	Mechanical Systems NRCC-MCH-E (Created 09/2020) CERTIFICATE OF COMPLIANCE Project Name: Hotel Del Coronado Fitness Members ARea Renovation Report Page: Page 8 of 10 Project Address: 1500 Orange Avenue Date Prepared: 2021-07-29	Mechanical Systems NRCC-MCH-E (Created 09/2020) CERTIFICATE OF COMPLIANCE Project Name: Hotel Del Coronado Fitness Members ARea Renovation Project Address: 1500 Orange Avenue CALIFORNIA ENERGY COMMISSION NRCC-MCH-E Project Name: Page 9 of 10 Date Prepared: 2021-07-29
Acade Composition Control of the Composition Control of the Control of Contro	Mechanical Systems NRCC-MCH-E (Created 09/2020) CERTIFICATE OF COMPLIANCE Project Name: Hotel Del Coronado Fitness Members ARea Renovation Report Page: Page 8 of 10 Project Address: 1500 Orange Avenue Date Prepared: 2021-07-29 P. DECLARATION OF REQUIRED CERTIFICATES OF VERIFICATION Table Instructions: Selections have been made based on information provided in previous tables of this document. If any selection needs to be changed, please explain why in	Mechanical Systems NRCC-MCH-E (Created 09/2020) CERTIFICATE OF COMPLIANCE Project Name: Hotel Del Coronado Fitness Members ARea Renovation Project Address: 1500 Orange Avenue Q. MANDATORY MEASURES DOCUMENTATION LOCATION Table Instructions: Indicate where mandatory measures are documented in the plan set or construction documentation. For any mandatory measures that do not apply, mark
Mechanical Systems RCC-MCH-E (Created 09/2020) CALIFORNIA ENERGY COMMISSION EXERTIFICATE OF COMPLIANCE Oroject Name: Hotel Del Coronado Fitness Members ARea Renovation Project Address: 1500 Orange Avenue Report Page: Page 7 of 10 Date Prepared: 2021-07-29	Mechanical Systems NRCC-MCH-E (Created 09/2020) CERTIFICATE OF COMPLIANCE Project Name: Hotel Del Coronado Fitness Members ARea Renovation Project Address: 1500 Orange Avenue P. DECLARATION OF REQUIRED CERTIFICATES OF VERIFICATION Table Instructions: Selections have been made based on information provided in previous tables of this document. If any selection needs to be changed, please explain why in Table E. Additional Remarks. These documents must be completed by a HERS Rater and provided to the building inspector during construction. The final documents must be created by a HERS Providers registry, but drafts can be found online at https://www.energy.ca.gov/title24/2019standards/2019 compliance documents/	Mechanical Systems NRCC-MCH-E (Created 09/2020) CERTIFICATE OF COMPLIANCE Project Name: Hotel Del Coronado Fitness Members ARea Renovation Project Address: 1500 Orange Avenue Q. MANDATORY MEASURES DOCUMENTATION LOCATION Table Instructions: Indicate where mandatory measures are documented in the plan set or construction documentation. For any mandatory measures that do not apply, mark the plan sheet or construction document location as "N/A", any active cells that are left blank will result in non-compliance in Table C.
RCC-MCH-E (created 09/2020) RCC-MCH-E (created 09/2020) RECRIFICATE OF COMPLIANCE FOREITH Hotel Del Coronado Fitness Members ARea Renovation Report Page: NRCC-MCH-E roject Address: 1500 Orange Avenue NRCA-MCH-12-A FDD for Packaged Direct Expansion Units NRCA-MCH-13-A Automatic FDD for Air Handling Units and Zone Terminal Units Acceptance NRCA-MCH-14-A Distributed Energy Storage DX AC Systems Acceptance	Mechanical Systems NRCC-MCH-E (Created 09/2020) CERTIFICATE OF COMPLIANCE Project Name: Hotel Del Coronado Fitness Members ARea Renovation Report Page: Page 8 of 10 Project Address: 1500 Orange Avenue Date Prepared: 2021-07-29 P. DECLARATION OF REQUIRED CERTIFICATES OF VERIFICATION Table Instructions: Selections have been made based on information provided in previous tables of this document. If any selection needs to be changed, please explain why in Table E. Additional Remarks. These documents must be completed by a HERS Rater and provided to the building inspector during construction. The final documents must be created by a HERS Providers registry, but drafts can be found online at https://www.energy.ca.gov/title24/2019standards/2019_compliance_documents/ Nonresidential_Documents/NRCV/ Field Inspector	Mechanical Systems NRCC-MCH-E (Created 09/2020) CERTIFICATE OF COMPLIANCE Project Name: Hotel Del Coronado Fitness Members ARea Renovation Project Address: 1500 Orange Avenue Q. MANDATORY MEASURES DOCUMENTATION LOCATION Table Instructions: Indicate where mandatory measures are documented in the plan set or construction documentation. For any mandatory measures that do not apply, mark the plan sheet or construction document location as "N/A", any active cells that are left blank will result in non-compliance in Table C. O1 Plan sheet or construction document location O2 Plan sheet or construction document location
Acade Comparison Compa	Mechanical Systems NRCC-MCH-E (Created 09/2020) CERTIFICATE OF COMPLIANCE Project Name: Hotel Del Coronado Fitness Members ARea Renovation Project Address: 1500 Orange Avenue P. DECLARATION OF REQUIRED CERTIFICATES OF VERIFICATION Table Instructions: Selections have been made based on information provided in previous tables of this document. If any selection needs to be changed, please explain why in Table E. Additional Remarks. These documents must be completed by a HERS Rater and provided to the building inspector during construction. The final documents must be created by a HERS Providers registry, but drafts can be found online at https://www.energy.ca.gov/title24/2019standards/2019_compliance_documents/Nance/ Field Inspector Pass Fail	Mechanical Systems NRCC-MCH-E (Created 09/2020) CERTIFICATE OF COMPLIANCE Project Name: Hotel Del Coronado Fitness Members ARea Renovation Project Address: 1500 Orange Avenue Q. MANDATORY MEASURES DOCUMENTATION LOCATION Table Instructions: Indicate where mandatory measures are documented in the plan set or construction documentation. For any mandatory measures that do not apply, mark the plan sheet or construction document location as "N/A", any active cells that are left blank will result in non-compliance in Table C.
Mechanical Systems RCC-MCH-E (Created 09/2020) CERTIFICATE OF COMPLIANCE CERTIFICATE OF COMPLIANCE NRCC-MCH-E (roject Name: Hotel Del Coronado Fitness Members ARea Renovation Report Page: Page 7 of 10 Project Address: 1500 Orange Avenue NRCC-MCH-E (roject Name: Hotel Del Coronado Fitness Members ARea Renovation Report Page: Page 7 of 10 Project Address: 1500 Orange Avenue NRCC-MCH-E (roject Name: Hotel Del Coronado Fitness Members ARea Renovation Report Page: Page 7 of 10 Page Prepared: 2021-07-29 NRCC-MCH-12-A FDD for Packaged Direct Expansion Units NRCC-MCH-12-A FDD for Packaged Direct Expansion Units NRCC-MCH-13-A Automatic FDD for Air Handling Units and Zone Terminal Units Acceptance NRCC-MCH-13-A Automatic FDD for Air Handling Units and Zone Terminal Units Acceptance NRCC-MCH-13-A Automatic FDD for Air Handling Units and Zone Terminal Units Acceptance NRCC-MCH-13-A Distributed Energy Storage DX AC Systems Acceptance NOTE: This form does not automatically move to "Yes". If Distributed Energy Storage DX	Mechanical Systems NRCC-MCH-E (Created 09/2020) CERTIFICATE OF COMPLIANCE Project Name: Hotel Del Coronado Fitness Members ARea Renovation Project Address: 1500 Orange Avenue P. DECLARATION OF REQUIRED CERTIFICATES OF VERIFICATION Table Instructions: Selections have been made based on information provided in previous tables of this document. If any selection needs to be changed, please explain why in Table E. Additional Remarks. These documents must be completed by a HERS Rater and provided to the building inspector during construction. The final documents must be created by a HERS Providers registry, but drafts can be found online at https://www.energy.ca.gov/title24/2019standards/2019_compliance_documents/Narcv/ Field Inspector	Mechanical Systems NRCC-MCH-E (Created 09/2020) CERTIFICATE OF COMPLIANCE Project Name: Hotel Del Coronado Fitness Members ARea Renovation Project Address: 1500 Orange Avenue Date Prepared: Q. MANDATORY MEASURES DOCUMENTATION LOCATION Table Instructions: Indicate where mandatory measures are documented in the plan set or construction documentation. For any mandatory measures that do not apply, mark the plan sheet or construction document location as "N/A", any active cells that are left blank will result in non-compliance in Table C. O1 Plan sheet or construction document location Compliance with Mandatory Measures documented through
RCC-MCH-E (Created 09)-2020) EXERTIFICATE OF COMPLIANCE TO Ject Name: Hotel Del Coronado Fitness Members ARea Renovation Report Page: Page 7 of 10 To Ject Address: 1500 Orange Avenue Date Prepared: 2021-07-29 NRCA-MCH-12-A FDD for Packaged Direct Expansion Units NRCA-MCH-13-A Automatic FDD for Air Handling Units and Zone Terminal Units Acceptance NRCA-MCH-14-A Distributed Energy Storage DX AC Systems Acceptance NRCA-MCH-15-A Thermal Energy Storage DX Storage DX AC Systems are included in the scope, permit applicant should move this form to "Yes". NRCA-MCH-15-A Thermal Energy Storage (TES) System Acceptance NOTE: This form does not automatically move to "Yes". If Chilled Water Storage, Ice-on-Coil Internal Melt, Ice-on-Coil External Melt, Ice-On-Coil External Melt, Ice Harvester, Brine, Ice-Slurry, Eutectic	Mechanical Systems NRCC-MCH-E (Created 09/2020) CERTIFICATE OF COMPLIANCE Project Name: Hotel Del Coronado Fitness Members ARea Renovation Report Page: Page 8 of 10 Project Address: 1500 Orange Avenue Date Prepared: 2021-07-29 P. DECLARATION OF REQUIRED CERTIFICATES OF VERIFICATION Table Instructions: Selections have been made based on information provided in previous tables of this document. If any selection needs to be changed, please explain why in Table E. Additional Remarks. These documents must be completed by a HERS Rater and provided to the building inspector during construction. The final documents must be created by a HERS Providers registry, but drafts can be found online at https://www.energy.ca.gov/title24/2019standards/2019_compliance_documents/ Nonresidential_Documents/NRCV/ YES NO Form/Title Field Inspector Pass Fail NRCV-MCH-04-H Duct Leakage Test NOTE: Must be completed by a HERS Rater NRCV-MCH-24 Enclosure Air Leakage Worksheet	Mechanical Systems NRCC-MCH-E (Created 09/2020) CERTIFICATE OF COMPLIANCE Project Name: Hotel Del Coronado Fitness Members ARea Renovation Project Address: 1500 Orange Avenue Date Prepared: Q. MANDATORY MEASURES DOCUMENTATION LOCATION Table Instructions: Indicate where mandatory measures are documented in the plan set or construction documentation. For any mandatory measures that do not apply, mark the plan sheet or construction document location as "N/A", any active cells that are left blank will result in non-compliance in Table C. O1 Plan sheet or construction document location Compliance with Mandatory Measures documented through
Mechanical Systems IRCC-MCH-E (Created 99/2020) CERTIFICATE OF COMPLIANCE Project Name: Hotel Del Coronado Fitness Members ARea Renovation Report Page: Page 7 of 10 Project Address: 1500 Orange Avenue On NRCA-MCH-12-A FDD for Packaged Direct Expansion Units NRCA-MCH-13-A Automatic FDD for Air Handling Units and Zone Terminal Units Acceptance NRCA-MCH-13-A Distributed Energy Storage DX AC Systems Acceptance NRCA-MCH-14-A Distributed Energy Storage DX AC Systems Acceptance NRCA-MCH-15-A Thermal Energy Storage (TES) System Acceptance work are included in the scope, permit applicant should move this form to "Yes". NRCA-MCH-15-A Thermal Energy Storage (TES) System Acceptance NOTE: This form does not automatically move to "Yes". If Chilled Water Storage, Ice-on-Coil Internal Melt, Ice-on-Coil External Melt, Ice-on-Coil External Melt, Ice-on-Coil External Melt, Ice-Slurry, Eutectic Salt, Clathrate Hydrate Slurry (CHS), Cryogenic or Encapulated (Ice Ball) Systems are included in the scope, permit applicant should move this form to "Yes".	Mechanical Systems NRCC-MCH-E (Created 09/2020) CERTIFICATE OF COMPLIANCE Project Name: Hotel Del Coronado Fitness Members ARea Renovation Project Address: 1500 Orange Avenue P. DECLARATION OF REQUIRED CERTIFICATES OF VERIFICATION Table Instructions: Selections have been made based on information provided in previous tables of this document. If any selection needs to be changed, please explain why in Table E. Additional Remarks. These documents must be completed by a HERS Rater and provided to the building inspector during construction. The final documents must be created by a HERS Providers registry, but drafts can be found online at https://www.energy.ca.gov/title24/2019standards/2019_compliance_documents/NRCV/ Pass Fail NRCV-MCH-04-H Duct Leakage Test NOTE: Must be completed by a HERS Rater NRCV-MCH-24 Enclosure Air Leakage Worksheet NOTE: Must be completed by a HERS Rater	Mechanical Systems NRCC-MCH-E (Created 09/2020) CERTIFICATE OF COMPLIANCE Project Name: Hotel Del Coronado Fitness Members ARea Renovation Project Address: 1500 Orange Avenue Date Prepared: Q. MANDATORY MEASURES DOCUMENTATION LOCATION Table Instructions: Indicate where mandatory measures are documented in the plan set or construction documentation. For any mandatory measures that do not apply, mark the plan sheet or construction document location as "N/A", any active cells that are left blank will result in non-compliance in Table C. O1 Plan sheet or construction document location Compliance with Mandatory Measures documented through
Acc-McH-E (created 99/2020) EXCLIFORNIA ENERGY COMMISSION EXCLIPION E (compliance) EXCLIFORNIA ENERGY COMMISSION EXCLIPION ENERG	Mechanical Systems NRCC-MCH-E (Created 09/2020) CERTIFICATE OF COMPLIANCE Project Name: Hotel Del Coronado Fitness Members ARea Renovation Report Page: Page 8 of 10 Project Address: 1500 Orange Avenue Date Prepared: 2021-07-29 P. DECLARATION OF REQUIRED CERTIFICATES OF VERIFICATION Table Instructions: Selections have been made based on information provided in previous tables of this document. If any selection needs to be changed, please explain why in Table E. Additional Remarks. These documents must be completed by a HERS Rater and provided to the building inspector during construction. The final documents must be created by a HERS Providers registry, but drafts can be found online at https://www.energy.ca.gov/title24/2019standards/2019_compliance_documents/ Nonresidential Documents/NRCV/ YES NO Form/Title Pass Fail NRCV-MCH-04-H Duct Leakage Test NOTE: Must be completed by a HERS Rater NRCV-MCH-24 Enclosure Air Leakage Worksheet NOTE: Must be completed by a HERS Rater NRCV-MCH-27 High-rise Residential NOTE: Must be completed by a HERS Rater	Mechanical Systems NRCC-MCH-E (Created 09/2020) CERTIFICATE OF COMPLIANCE Project Name: Hotel Del Coronado Fitness Members ARea Renovation Project Address: 1500 Orange Avenue Date Prepared: Q. MANDATORY MEASURES DOCUMENTATION LOCATION Table Instructions: Indicate where mandatory measures are documented in the plan set or construction documentation. For any mandatory measures that do not apply, mark the plan sheet or construction document location as "N/A", any active cells that are left blank will result in non-compliance in Table C. O1 Plan sheet or construction document location Compliance with Mandatory Measures documented through
CC-MCH-E (Created 09/2020) CALIFORNIA ENERGY COMMISSION CC-MCH-E (Created 09/2020) CALIFORNIA ENERGY COMMISSION CALIFORNIA ENERGY COMMISSION CC-MCH-E (Created 09/2020) CALIFORNIA ENERGY COMMISSION CALI	Mechanical Systems NRCC-MCH-E (Created 09/2020) CERTIFICATE OF COMPLIANCE Project Name: Hotel Del Coronado Fitness Members ARea Renovation Report Page: Page 8 of 10 Project Address: 1500 Orange Avenue Date Prepared: 2021-07-29 P. DECLARATION OF REQUIRED CERTIFICATES OF VERIFICATION Table Instructions: Selections have been made based on information provided in previous tables of this document. If any selection needs to be changed, please explain why in Table E. Additional Remarks. These documents must be completed by a HERS Rater and provided to the building inspector during construction. The final documents must be created by a HERS Providers registry, but drafts can be found online at https://www.energy.ca.gov/title24/2019standards/2019_compliance_documents/NRCV/ YES NO ROCY-MCH-04-H Duct Leakage Test NOTE: Must be completed by a HERS Rater O NRCV-MCH-24 Enclosure Air Leakage Worksheet NOTE: Must be completed by a HERS Rater	Mechanical Systems NRCC-MCH-E (Created 09/2020) CERTIFICATE OF COMPLIANCE Project Name: Hotel Del Coronado Fitness Members ARea Renovation Project Address: 1500 Orange Avenue Oate Prepared: Q. MANDATORY MEASURES DOCUMENTATION LOCATION Table Instructions: Indicate where mandatory measures are documented in the plan set or construction documentation. For any mandatory measures that do not apply, mark the plan sheet or construction document location as "N/A", any active cells that are left blank will result in non-compliance in Table C. O1 Plan sheet or construction document location Compliance with Mandatory Measures documented through
Acc-Mark E (created 09/2020) Accumentation of the Energy Commission of Entress Members ARea Renovation Report Page: Page 7 of 10 roject Address: 1500 Orange Avenue Date Prepared: 2021-07-29 Acceptance NRCA-MCH-12-A FDD for Packaged Direct Expansion Units Date Prepared: 2021-07-29 NRCA-MCH-13-A Automatic FDD for Air Handling Units and Zone Terminal Units Acceptance NRCA-MCH-14-A Distributed Energy Storage DX AC Systems Acceptance NRCA-MCH-14-A Distributed Energy Storage DX AC Systems are included in the scope, permit applicant should move this form to "Yes". NRCA-MCH-15-A Thermal Energy Storage (TES) System Acceptance NOTE: This form does not automatically move to "Yes". If Chilled Water Storage, Ice-on-Coil Internal Melt, Ice-on-Coil External Melt, Ice Harvester, Brine, Ice-Slurry, Eutectic Salt, Clathrate Hydrate Slurry (CHS), Cryogenic or Encapulated (Ice Ball) Systems are included in the scope, permit applicant should move this form to "Yes". NRCA-MCH-16-A Supply Air Temperature Reset Controls	Mechanical Systems NRCC-MCH-E (Created 09/2020) CERTIFICATE OF COMPLIANCE Project Name: Hotel Del Coronado Fitness Members ARea Renovation Report Page: Page 8 of 10 Project Address: 1500 Orange Avenue Date Prepared: 2021-07-29 P. DECLARATION OF REQUIRED CERTIFICATES OF VERIFICATION Table Instructions: Selections have been made based on information provided in previous tables of this document. If any selection needs to be changed, please explain why in Table E. Additional Remarks. These documents must be completed by a HERS Rater and provided to the building inspector during construction. The final documents must be created by a HERS Providers registry, but drafts can be found online at https://www.energy.ca.gov/title24/2019standards/2019_compliance_documents/ Nonresidential Documents/NRCV/ YES NO Form/Title Pass Fail NRCV-MCH-04-H Duct Leakage Test NOTE: Must be completed by a HERS Rater NRCV-MCH-24 Enclosure Air Leakage Worksheet NOTE: Must be completed by a HERS Rater NRCV-MCH-27 High-rise Residential NOTE: Must be completed by a HERS Rater	Mechanical Systems NRCC-MCH-E (Created 09/2020) CERTIFICATE OF COMPLIANCE Project Name: Hotel Del Coronado Fitness Members ARea Renovation Project Address: 1500 Orange Avenue Oate Prepared: Q. MANDATORY MEASURES DOCUMENTATION LOCATION Table Instructions: Indicate where mandatory measures are documented in the plan set or construction documentation. For any mandatory measures that do not apply, mark the plan sheet or construction document location as "N/A", any active cells that are left blank will result in non-compliance in Table C. O1 Plan sheet or construction document location Compliance with Mandatory Measures documented through
CALIFORNIA ENERGY COMMISSION CALIFORNIA ENERGY CALIFORNIA ENERGY COMMISSION CALIFORNIA	Mechanical Systems NRCC-MCH-E (Created 09/2020) CERTIFICATE OF COMPLIANCE Project Name: Hotel Del Coronado Fitness Members ARea Renovation Report Page: Page 8 of 10 Project Address: 1500 Orange Avenue Date Prepared: 2021-07-29 P. DECLARATION OF REQUIRED CERTIFICATES OF VERIFICATION Table Instructions: Selections have been made based on information provided in previous tables of this document. If any selection needs to be changed, please explain why in Table E. Additional Remarks. These documents must be completed by a HERS Rater and provided to the building inspector during construction. The final documents must be created by a HERS Providers registry, but drafts can be found online at https://www.energy.ca.gov/title24/2019standards/2019_compliance_documents/ Nonresidential Documents/NRCV/ YES NO Form/Title Pass Fail NRCV-MCH-04-H Duct Leakage Test NOTE: Must be completed by a HERS Rater NRCV-MCH-24 Enclosure Air Leakage Worksheet NOTE: Must be completed by a HERS Rater NRCV-MCH-27 High-rise Residential NOTE: Must be completed by a HERS Rater	Mechanical Systems NRCC-MCH-E (Created 09/2020) CERTIFICATE OF COMPLIANCE Project Name: Hotel Del Coronado Fitness Members ARea Renovation Project Address: 1500 Orange Avenue Date Prepared: Q. MANDATORY MEASURES DOCUMENTATION LOCATION Table Instructions: Indicate where mandatory measures are documented in the plan set or construction documentation. For any mandatory measures that do not apply, mark the plan sheet or construction document location as "N/A", any active cells that are left blank will result in non-compliance in Table C. O1 Plan sheet or construction document location Compliance with Mandatory Measures documented through
ACC-MCH-E (Created 09)2020) CALUFORNIA ENERGY COMMISSION CACUPORNIA ENERGY CACUPORNIA ENERGY COMMISSION CACUPORNIA E	Mechanical Systems NRCC-MCH-E (Created 09/2020) CERTIFICATE OF COMPLIANCE Project Name: Hotel Del Coronado Fitness Members ARea Renovation Report Page: Page 8 of 10 Project Address: 1500 Orange Avenue Date Prepared: 2021-07-29 P. DECLARATION OF REQUIRED CERTIFICATES OF VERIFICATION Table Instructions: Selections have been made based on information provided in previous tables of this document. If any selection needs to be changed, please explain why in Table E. Additional Remarks. These documents must be completed by a HERS Rater and provided to the building inspector during construction. The final documents must be created by a HERS Providers registry, but drafts can be found online at https://www.energy.ca.gov/title24/2019standards/2019_compliance_documents/ Nonresidential Documents/NRCV/ YES NO Form/Title Pass Fail NRCV-MCH-04-H Duct Leakage Test NOTE: Must be completed by a HERS Rater NRCV-MCH-24 Enclosure Air Leakage Worksheet NOTE: Must be completed by a HERS Rater NRCV-MCH-27 High-rise Residential NOTE: Must be completed by a HERS Rater	Mechanical Systems NRCC-MCH-E (Created 09/2020) CERTIFICATE OF COMPLIANCE Project Name: Hotel Del Coronado Fitness Members ARea Renovation Project Address: 1500 Orange Avenue Date Prepared: Q. MANDATORY MEASURES DOCUMENTATION LOCATION Table Instructions: Indicate where mandatory measures are documented in the plan set or construction documentation. For any mandatory measures that do not apply, mark the plan sheet or construction document location as "N/A", any active cells that are left blank will result in non-compliance in Table C. O1 Plan sheet or construction document location Compliance with Mandatory Measures documented through
RCC.MCH-E (Crested 09/2005) CALIFORNIA ENERGY COMMISSION	Mechanical Systems NRCC-MCH-E (Created 09/2020) CERTIFICATE OF COMPLIANCE Project Name: Hotel Del Coronado Fitness Members ARea Renovation Report Page: Page 8 of 10 Project Address: 1500 Orange Avenue Date Prepared: 2021-07-29 P. DECLARATION OF REQUIRED CERTIFICATES OF VERIFICATION Table Instructions: Selections have been made based on information provided in previous tables of this document. If any selection needs to be changed, please explain why in Table E. Additional Remarks. These documents must be completed by a HERS Rater and provided to the building inspector during construction. The final documents must be created by a HERS Providers registry, but drafts can be found online at https://www.energy.ca.gov/title24/2019standards/2019_compliance_documents/ Nonresidential Documents/NRCV/ YES NO Form/Title Pass Fail NRCV-MCH-04-H Duct Leakage Test NOTE: Must be completed by a HERS Rater NRCV-MCH-24 Enclosure Air Leakage Worksheet NOTE: Must be completed by a HERS Rater NRCV-MCH-27 High-rise Residential NOTE: Must be completed by a HERS Rater	Mechanical Systems NRCC-MCH-E (Created 09/2020) CERTIFICATE OF COMPLIANCE Project Name: Hotel Del Coronado Fitness Members ARea Renovation Project Address: 1500 Orange Avenue Date Prepared: Q. MANDATORY MEASURES DOCUMENTATION LOCATION Table Instructions: Indicate where mandatory measures are documented in the plan set or construction documentation. For any mandatory measures that do not apply, mark the plan sheet or construction document location as "N/A", any active cells that are left blank will result in non-compliance in Table C. O1 Plan sheet or construction document location Compliance with Mandatory Measures documented through
CALIFORNIA ENERGY COMMISSION CALIFORNIA ENERGY CALIFORNIA ENERGY COMMISSION CALIFORNIA	Mechanical Systems NRCC-MCH-E (Created 09/2020) CERTIFICATE OF COMPLIANCE Project Name: Hotel Del Coronado Fitness Members ARea Renovation Report Page: Page 8 of 10 Project Address: 1500 Orange Avenue Date Prepared: 2021-07-29 P. DECLARATION OF REQUIRED CERTIFICATES OF VERIFICATION Table Instructions: Selections have been made based on information provided in previous tables of this document. If any selection needs to be changed, please explain why in Table E. Additional Remarks. These documents must be completed by a HERS Rater and provided to the building inspector during construction. The final documents must be created by a HERS Providers registry, but drafts can be found online at https://www.energy.ca.gov/title24/2019standards/2019_compliance_documents/ Nonresidential Documents/NRCV/ YES NO Form/Title Pass Fail NRCV-MCH-04-H Duct Leakage Test NOTE: Must be completed by a HERS Rater NRCV-MCH-24 Enclosure Air Leakage Worksheet NOTE: Must be completed by a HERS Rater NRCV-MCH-27 High-rise Residential NOTE: Must be completed by a HERS Rater	Mechanical Systems NRCC-MCH-E (Created 09/2020) CERTIFICATE OF COMPLIANCE Project Name: Hotel Del Coronado Fitness Members ARea Renovation Project Address: 1500 Orange Avenue Date Prepared: Q. MANDATORY MEASURES DOCUMENTATION LOCATION Table Instructions: Indicate where mandatory measures are documented in the plan set or construction documentation. For any mandatory measures that do not apply, mark the plan sheet or construction document location as "N/A", any active cells that are left blank will result in non-compliance in Table C. O1 Plan sheet or construction document location Compliance with Mandatory Measures documented through
Caufornia Energy Commission Cauf	Mechanical Systems NRCC-MCH-E (Created 09/2020) CERTIFICATE OF COMPLIANCE Project Name: Hotel Del Coronado Fitness Members ARea Renovation Report Page: Page 8 of 10 Project Address: 1500 Orange Avenue Date Prepared: 2021-07-29 P. DECLARATION OF REQUIRED CERTIFICATES OF VERIFICATION Table Instructions: Selections have been made based on information provided in previous tables of this document. If any selection needs to be changed, please explain why in Table E. Additional Remarks. These documents must be completed by a HERS Rater and provided to the building inspector during construction. The final documents must be created by a HERS Providers registry, but drafts can be found online at https://www.energy.ca.gov/title24/2019standards/2019_compliance_documents/ Nonresidential Documents/NRCV/ YES NO Form/Title Pass Fail NRCV-MCH-04-H Duct Leakage Test NOTE: Must be completed by a HERS Rater NRCV-MCH-24 Enclosure Air Leakage Worksheet NOTE: Must be completed by a HERS Rater NRCV-MCH-27 High-rise Residential NOTE: Must be completed by a HERS Rater	Mechanical Systems NRCC-MCH-E (Created 09/2020) CERTIFICATE OF COMPLIANCE Project Name: Hotel Del Coronado Fitness Members ARea Renovation Project Address: 1500 Orange Avenue Oate Prepared: Q. MANDATORY MEASURES DOCUMENTATION LOCATION Table Instructions: Indicate where mandatory measures are documented in the plan set or construction documentation. For any mandatory measures that do not apply, mark the plan sheet or construction document location as "N/A", any active cells that are left blank will result in non-compliance in Table C. O1 Plan sheet or construction document location Compliance with Mandatory Measures documented through
California Energy Commission California Energy Storage California Energy Energy California Energy Storage California Energy Storage California Energy Energy Energy California Energy Energy Energy Energy California Energy Energy Energy Energy Energy Energy California Energy En	Mechanical Systems NRCC-MCH-E (Created 09/2020) CERTIFICATE OF COMPLIANCE Project Name: Hotel Del Coronado Fitness Members ARea Renovation Report Page: Page 8 of 10 Project Address: 1500 Orange Avenue Date Prepared: 2021-07-29 P. DECLARATION OF REQUIRED CERTIFICATES OF VERIFICATION Table Instructions: Selections have been made based on information provided in previous tables of this document. If any selection needs to be changed, please explain why in Table E. Additional Remarks. These documents must be completed by a HERS Rater and provided to the building inspector during construction. The final documents must be created by a HERS Providers registry, but drafts can be found online at https://www.energy.ca.gov/title24/2019standards/2019_compliance_documents/ Nonresidential Documents/NRCV/ YES NO Form/Title Pass Fail NRCV-MCH-04-H Duct Leakage Test NOTE: Must be completed by a HERS Rater NRCV-MCH-24 Enclosure Air Leakage Worksheet NOTE: Must be completed by a HERS Rater NRCV-MCH-27 High-rise Residential NOTE: Must be completed by a HERS Rater	Mechanical Systems NRCC-MCH-E (Created 09/2020) CERTIFICATE OF COMPLIANCE Project Name: Hotel Del Coronado Fitness Members ARea Renovation Project Address: 1500 Orange Avenue Date Prepared: Q. MANDATORY MEASURES DOCUMENTATION LOCATION Table Instructions: Indicate where mandatory measures are documented in the plan set or construction documentation. For any mandatory measures that do not apply, mark the plan sheet or construction document location as "N/A", any active cells that are left blank will result in non-compliance in Table C. O1 Plan sheet or construction document location Compliance with Mandatory Measures documented through
California Energy Commission California Energy Storage California Energy Energy California Energy Storage California Energy Storage California Energy Energy Energy California Energy Energy Energy Energy California Energy Energy Energy Energy Energy Energy California Energy En	Mechanical Systems NRCC-MCH-E (Created 09/2020) CERTIFICATE OF COMPLIANCE Project Name: Hotel Del Coronado Fitness Members ARea Renovation Report Page: Page 8 of 10 Project Address: 1500 Orange Avenue Date Prepared: 2021-07-29 P. DECLARATION OF REQUIRED CERTIFICATES OF VERIFICATION Table Instructions: Selections have been made based on information provided in previous tables of this document. If any selection needs to be changed, please explain why in Table E. Additional Remarks. These documents must be completed by a HERS Rater and provided to the building inspector during construction. The final documents must be created by a HERS Providers registry, but drafts can be found online at https://www.energy.ca.gov/title24/2019standards/2019_compliance_documents/ Nonresidential Documents/NRCV/ YES NO Form/Title Pass Fail NRCV-MCH-04-H Duct Leakage Test NOTE: Must be completed by a HERS Rater NRCV-MCH-24 Enclosure Air Leakage Worksheet NOTE: Must be completed by a HERS Rater NRCV-MCH-27 High-rise Residential NOTE: Must be completed by a HERS Rater	Mechanical Systems NRCC-MCH-E (Created 09/2020) CERTIFICATE OF COMPLIANCE Project Name: Hotel Del Coronado Fitness Members ARea Renovation Project Address: 1500 Orange Avenue Date Prepared: Q. MANDATORY MEASURES DOCUMENTATION LOCATION Table Instructions: Indicate where mandatory measures are documented in the plan set or construction documentation. For any mandatory measures that do not apply, mark the plan sheet or construction document location as "N/A", any active cells that are left blank will result in non-compliance in Table C. O1 Plan sheet or construction document location Compliance with Mandatory Measures documented through
California Energy Commission California Energy Energy Energy Energy California Energy Commission California Energy Energy Energy California Energy Ener	Mechanical Systems NRCC-MCH-E (Created 09/2020) CERTIFICATE OF COMPLIANCE Project Name: Hotel Del Coronado Fitness Members ARea Renovation Report Page: Page 8 of 10 Project Address: 1500 Orange Avenue Date Prepared: 2021-07-29 P. DECLARATION OF REQUIRED CERTIFICATES OF VERIFICATION Table Instructions: Selections have been made based on information provided in previous tables of this document. If any selection needs to be changed, please explain why in Table E. Additional Remarks. These documents must be completed by a HERS Rater and provided to the building inspector during construction. The final documents must be created by a HERS Providers registry, but drafts can be found online at https://www.energy.ca.gov/title24/2019standards/2019_compliance_documents/ Nonresidential Documents/NRCV/ YES NO Form/Title Pass Fail NRCV-MCH-04-H Duct Leakage Test NOTE: Must be completed by a HERS Rater NRCV-MCH-24 Enclosure Air Leakage Worksheet NOTE: Must be completed by a HERS Rater NRCV-MCH-27 High-rise Residential NOTE: Must be completed by a HERS Rater	Mechanical Systems NRCC-MCH-E (Created 09/2020) CERTIFICATE OF COMPLIANCE Project Name: Hotel Del Coronado Fitness Members ARea Renovation Project Address: 1500 Orange Avenue Date Prepared: Q. MANDATORY MEASURES DOCUMENTATION LOCATION Table Instructions: Indicate where mandatory measures are documented in the plan set or construction documentation. For any mandatory measures that do not apply, mark the plan sheet or construction document location as "N/A", any active cells that are left blank will result in non-compliance in Table C. O1 Plan sheet or construction document location Compliance with Mandatory Measures documented through
California Energy Commission California Energy Storage California Energy Energy California Energy Storage California Energy Storage California Energy Energy Energy California Energy Energy Energy Energy California Energy Energy Energy Energy Energy Energy California Energy En	Mechanical Systems NRCC-MCH-E (Created 09/2020) CERTIFICATE OF COMPLIANCE Project Name: Hotel Del Coronado Fitness Members ARea Renovation Report Page: Page 8 of 10 Project Address: 1500 Orange Avenue Date Prepared: 2021-07-29 P. DECLARATION OF REQUIRED CERTIFICATES OF VERIFICATION Table Instructions: Selections have been made based on information provided in previous tables of this document. If any selection needs to be changed, please explain why in Table E. Additional Remarks. These documents must be completed by a HERS Rater and provided to the building inspector during construction. The final documents must be created by a HERS Providers registry, but drafts can be found online at https://www.energy.ca.gov/title24/2019standards/2019_compliance_documents/ Nonresidential Documents/NRCV/ YES NO Form/Title Pass Fail NRCV-MCH-04-H Duct Leakage Test NOTE: Must be completed by a HERS Rater NRCV-MCH-24 Enclosure Air Leakage Worksheet NOTE: Must be completed by a HERS Rater NRCV-MCH-27 High-rise Residential NOTE: Must be completed by a HERS Rater	Mechanical Systems NRCC-MCH-E (Created 09/2020) CERTIFICATE OF COMPLIANCE Project Name: Hotel Del Coronado Fitness Members ARea Renovation Project Address: 1500 Orange Avenue Oate Prepared: Q. MANDATORY MEASURES DOCUMENTATION LOCATION Table Instructions: Indicate where mandatory measures are documented in the plan set or construction documentation. For any mandatory measures that do not apply, mark the plan sheet or construction document location as "N/A", any active cells that are left blank will result in non-compliance in Table C. O1 Plan sheet or construction document location Compliance with Mandatory Measures documented through
MacCharle (Normal By 2000) ERTIFICATE OF COMPLIANCE RECMEH (Formation 197,000) RECMEH (Serval Motel Del Coronado Fitness Members ARea Renovation Report Page: Page 7 of 10 Project Address: 1500 Grange Avenue Date Prepared: 2021-07-29 RRCA-MCH-12-A FDD for Packaged Direct Expansion Units Date Prepared: 2021-07-29 RRCA-MCH-13-A Automatic FDD for Air Handling Units and Zone Terminal Units Record Page: Record Page 1 Page 7 of 10 Project Address: 1500 Grange Avenue Date Prepared: 2021-07-29 RRCA-MCH-13-A Automatic FDD for Air Handling Units and Zone Terminal Units Record Page 1 Page 7 of 10 Page 8 of 10	Mechanical Systems NRC-MCHE (Frended pi32030) (EERTIFICATE OF COMPUNACE Project Kame: Hotel be Cronado Fitness Members ARea Renovation Project Address: 1500 Orange Avenue Date Prepared: 2021-07-29	Mechanical Systems NRC-MCHE (Forated 87)2000 [CERTIFICATE OF COMPLIANCE Project Address: \$500 Orange Avenue Onter Propiect Maries Mote De Common Filmess Members ARea Renovation Report Page: Prage 9 of 10
Mechanical Systems SECM-HE (Fronta 197):200 SERTIFICATE OF COMPLANCE PROJECT Name: Notice Del Coronado Fitness Members ARea Renovation Report Page: Page 7 of 10 Project Name: Notice Del Coronado Fitness Members ARea Renovation Report Page: Page 7 of 10 Project Address: 1500 Orange Avenue Oate Prepared: 2021-07-29 NRCA-MCH-12-A FDD for Packaged Direct Expansion Units Oate Prepared: 2021-07-29 NRCA-MCH-13-A Automatic FDD for Air Handling Units and Zone Terminal Units Oate Prepared: Oate Prepa	Mechanical Systems NRCC-MCH-E (Created 09/2020) CERTIFICATE OF COMPLIANCE Project Name: Hotel Del Coronado Fitness Members ARea Renovation Report Page: Page 8 of 10 Project Address: 1500 Orange Avenue Date Prepared: 2021-07-29 P. DECLARATION OF REQUIRED CERTIFICATES OF VERIFICATION Table Instructions: Selections have been made based on information provided in previous tables of this document. If any selection needs to be changed, please explain why in Table E. Additional Remarks. These documents must be completed by a HERS Rater and provided to the building inspector during construction. The final documents must be created by a HERS Providers registry, but drafts can be found online at https://www.energy.ca.gov/title24/2019standards/2019_compliance_documents/ Nonresidential Documents/NRCV/ YES NO Form/Title Pass Fail NRCV-MCH-04-H Duct Leakage Test NOTE: Must be completed by a HERS Rater NRCV-MCH-24 Enclosure Air Leakage Worksheet NOTE: Must be completed by a HERS Rater NRCV-MCH-27 High-rise Residential NOTE: Must be completed by a HERS Rater	Mechanical Systems NRCC-MCH-E (Created 09/2020) CERTIFICATE OF COMPLIANCE Project Name: Hotel Del Coronado Fitness Members ARea Renovation Project Address: 1500 Orange Avenue Date Prepared: Q. MANDATORY MEASURES DOCUMENTATION LOCATION Table Instructions: Indicate where mandatory measures are documented in the plan set or construction documentation. For any mandatory measures that do not apply, mark the plan sheet or construction document location as "N/A", any active cells that are left blank will result in non-compliance in Table C. O1 Plan sheet or construction document location Compliance with Mandatory Measures documented through
Mechanical Systems (CACH-I (Frende 197/230) CERTIFICATE OF COMPLIANCE NRCC-MCHE Project Name: Hotel Del Corroado Fitness Members ARea Renovation Report Page: Page 7 of 10 Project Name: Hotel Del Corroado Fitness Members ARea Renovation Report Page: Page 7 of 10 Project Address: 1500 Orange Avenue O	Mechanical Systems NRC-MCHE (Frended pi32030) (EERTIFICATE OF COMPUNACE Project Kame: Hotel be Cronado Fitness Members ARea Renovation Project Address: 1500 Orange Avenue Date Prepared: 2021-07-29	Mechanical Systems NRCC-MCH-E PROJECT FOR COMPLANCE Project Address: \$500 crange Avenue Ox. MANDATORY MEASURES DOCUMENTATION LOCATION Table Instructions: Indicate where mandatory measures are documented in the plan set or construction documentation. For any mandatory measures that do not apply, mark the plan sheet or construction document location as "N/A", any active cells that are left blank will result in non-compliance in Table C. Compliance with Mandatory Measures documented through Yes M7.02 Compliance with Mandatory Measures Note Block: W/A" and the plan sheet or construction document location NRC-MCH-E Project Address: \$500 crange Avenue Date Prepared: 2021-07-29
MICHARILA SYSTEMS INCOMPLIANCE INCOMPLIANC	Mechanical Systems NRC-MCHE (Frended pi32030) (EERTIFICATE OF COMPUNACE Project Kame: Hotel be Cronado Fitness Members ARea Renovation Project Address: 1500 Orange Avenue Date Prepared: 2021-07-29	Mechanical Systems NRCC-MCH-E PROJECT FOR COMPLANCE Project Address: \$500 crange Avenue Ox. MANDATORY MEASURES DOCUMENTATION LOCATION Table Instructions: Indicate where mandatory measures are documented in the plan set or construction documentation. For any mandatory measures that do not apply, mark the plan sheet or construction document location as "N/A", any active cells that are left blank will result in non-compliance in Table C. Compliance with Mandatory Measures documented through Yes M7.02 Compliance with Mandatory Measures Note Block: W/A" and the plan sheet or construction document location NRC-MCH-E Project Address: \$500 crange Avenue Date Prepared: 2021-07-29
MICAMORICA Systems CALIFORMAD FINESC COMMISSION CERTIFICATE OF COMPLIANCE NICCAMORIC STORY COMPLIANCE NICCAMORIC STORY COMPLIANCE NICCAMORICA STORY COMPLIANCE NI	Mechanical Systems NRC-MCHE (Frended pi32030) (EERTIFICATE OF COMPUNACE Project Kame: Hotel be Cronado Fitness Members ARea Renovation Project Address: 1500 Orange Avenue Date Prepared: 2021-07-29	Mechanical Systems NRCC-MCH-E PROJECT FOR COMPLANCE Project Address: \$500 crange Avenue Ox. MANDATORY MEASURES DOCUMENTATION LOCATION Table Instructions: Indicate where mandatory measures are documented in the plan set or construction documentation. For any mandatory measures that do not apply, mark the plan sheet or construction document location as "N/A", any active cells that are left blank will result in non-compliance in Table C. Compliance with Mandatory Measures documented through Yes M7.02 Compliance with Mandatory Measures Note Block: W/A" and the plan sheet or construction document location NRC-MCH-E Project Address: \$500 crange Avenue Date Prepared: 2021-07-29
MICCAMCH-12-A REPRIATOR OF COMPLIANCE TOPICE NAME: GOOD REPRIATOR OF COMPLIANCE TOPICE NAME: A CONFIDENCE OF CONFIDENCE OF THE PROPERTY OF THE	Mechanical Systems NRC-MCHE (Frended pi32030) (EERTIFICATE OF COMPUNACE Project Kame: Hotel be Cronado Fitness Members ARea Renovation Project Address: 1500 Orange Avenue Date Prepared: 2021-07-29	Mechanical Systems NRCC-MCH-E PROJECT FOR COMPLANCE Project Address: \$500 crange Avenue Ox. MANDATORY MEASURES DOCUMENTATION LOCATION Table Instructions: Indicate where mandatory measures are documented in the plan set or construction documentation. For any mandatory measures that do not apply, mark the plan sheet or construction document location as "N/A", any active cells that are left blank will result in non-compliance in Table C. Compliance with Mandatory Measures documented through Yes M7.02 Compliance with Mandatory Measures Note Block: W/A" and the plan sheet or construction document location NRC-MCH-E Project Address: \$500 crange Avenue Date Prepared: 2021-07-29
Michael Systems Michael Mich	Mechanical Systems NRC-MCHE (Frended pi32030) (EERTIFICATE OF COMPUNACE Project Kame: Hotel be Cronado Fitness Members ARea Renovation Project Address: 1500 Orange Avenue Date Prepared: 2021-07-29	Mechanical Systems NRCC-MCH-E PROPRIED TO COMPLIANCE NRCC-MCH-E Project Address: \$500 crange Avenue Out MANDATORY MEASURES DOCUMENTATION LOCATION Table Instructions: Indicate where mandatory measures are documented in the plan set or construction documentation. For any mandatory measures that do not apply, mark the plan sheet or construction document location as "N/A", any active cells that are left blank will result in non-compliance in Table C. Compliance with Mandatory Measures documented through Yes M7.02 Compliance with Mandatory Measures Note Block: W7.02
MICHAEL Systems INCEMPLIANCE OF COMPLIANCE INCEMPLIANCE	Mechanical Systems NRC-MCHE (Frended pi32030) (EERTIFICATE OF COMPUNACE Project Kame: Hotel be Cronado Fitness Members ARea Renovation Project Address: 1500 Orange Avenue Date Prepared: 2021-07-29	Mechanical Systems NRCC-MCH-E PROJECT FOR COMPLANCE Project Address: \$500 crange Avenue Ox. MANDATORY MEASURES DOCUMENTATION LOCATION Table Instructions: Indicate where mandatory measures are documented in the plan set or construction documentation. For any mandatory measures that do not apply, mark the plan sheet or construction document location as "N/A", any active cells that are left blank will result in non-compliance in Table C. Compliance with Mandatory Measures documented through Yes M7.02 Compliance with Mandatory Measures Note Block: W/A" and the plan sheet or construction document location NRC-MCH-E Project Address: \$500 crange Avenue Date Prepared: 2021-07-29
MICHARICA Systems (SERTIFICATE OF COMPLIANCE (SERTIFICATE (SERTIFICAT	Mechanical Systems NRC-MCHE (Frended pi32030) (EERTIFICATE OF COMPUNACE Project Kame: Hotel be Cronado Fitness Members ARea Renovation Project Address: 1500 Orange Avenue Date Prepared: 2021-07-29	Mechanical Systems NRCC-MCH-E PROJECT FOR COMPLANCE Project Address: \$500 crange Avenue Ox. MANDATORY MEASURES DOCUMENTATION LOCATION Table Instructions: Indicate where mandatory measures are documented in the plan set or construction documentation. For any mandatory measures that do not apply, mark the plan sheet or construction document location as "N/A", any active cells that are left blank will result in non-compliance in Table C. Compliance with Mandatory Measures documented through Yes M7.02 Compliance with Mandatory Measures Note Block: W/A" and the plan sheet or construction document location NRC-MCH-E Project Address: \$500 crange Avenue Date Prepared: 2021-07-29
MCCHARLICA Systems CERTIFICATE OF COMPLIANCE CERTIFICATE OF COMPLIANCE CERTIFICATE OF COMPLIANCE NRCC-MCHE	Mechanical Systems NRC-MCHE (Frended pi32030) (EERTIFICATE OF COMPUNACE Project Kame: Hotel be Cronado Fitness Members ARea Renovation Project Address: 1500 Orange Avenue Date Prepared: 2021-07-29	Mechanical Systems NRCC-MCH-E PROJECT FOR COMPLANCE Project Address: \$500 crange Avenue Ox. MANDATORY MEASURES DOCUMENTATION LOCATION Table Instructions: Indicate where mandatory measures are documented in the plan set or construction documentation. For any mandatory measures that do not apply, mark the plan sheet or construction document location as "N/A", any active cells that are left blank will result in non-compliance in Table C. Compliance with Mandatory Measures documented through Yes M7.02 Compliance with Mandatory Measures Note Block: W/A" and the plan sheet or construction document location NRC-MCH-E Project Address: \$500 crange Avenue Date Prepared: 2021-07-29
Mechanical Systems CERTIFICATION OF COMPLIANCE NINCC-MCH-12 AFTOD for Packaged Direct Expansion Units Once Prepared. Once Once Prepared. Once Once Prepared. Once Once Once Prepared. Once Once Once Once Once Once Once Once	Mechanical Systems NRC-MCHE (Frended pi32030) (EERTIFICATE OF COMPUNACE Project Kame: Hotel be Cronado Fitness Members ARea Renovation Project Address: 1500 Orange Avenue Date Prepared: 2021-07-29	Mechanical Systems NRCC-MCH-E PROJECT FOR COMPLANCE Project Address: \$500 crange Avenue Ox. MANDATORY MEASURES DOCUMENTATION LOCATION Table Instructions: Indicate where mandatory measures are documented in the plan set or construction documentation. For any mandatory measures that do not apply, mark the plan sheet or construction document location as "N/A", any active cells that are left blank will result in non-compliance in Table C. Compliance with Mandatory Measures documented through Yes M7.02 Compliance with Mandatory Measures Note Block: W/A" and the plan sheet or construction document location NRC-MCH-E Project Address: \$500 crange Avenue Date Prepared: 2021-07-29
Mechanical Systems CERTIFICAT DE COMPLIANCE CERTIFICATION DE COMPLIANCE CERTIFICATION DE COMPLIANCE CERTIFICATION DE COMPLIANCE CERTIFICATION DE COMPLIANCE Project Name: Incided Description of Packaged Direct Expansion Units Oil # NRCA-MCH-12-A FDD for Packaged Direct Expansion Units Oil # NRCA-MCH-12-A FDD for Packaged Direct Expansion Units Oil # NRCA-MCH-12-A FDD for Packaged Direct Expansion Units Oil # NRCA-MCH-14-A Distributed Sensy Storage DX AC Systems Acceptance Oil # NRCA-MCH-14-A Distributed Sensy Storage DX AC Systems Acceptance Oil # NRCA-MCH-14-A Distributed Sensy Storage DX AC Systems Acceptance Oil # NRCA-MCH-14-A Distributed Sensy Storage DX AC Systems Acceptance Oil # NRCA-MCH-14-A Distributed Sensy Storage DX AC Systems Acceptance Oil # NRCA-MCH-14-A Distributed Sensy Storage DX AC Systems Acceptance Oil # NRCA-MCH-15-A Thermal Energy Storage (TES) Systems Acceptance Oil # NRCA-MCH-15-A Thermal Energy Storage (TES) Systems Acceptance Oil # NRCA-MCH-15-A Thermal Energy Storage DX AC Systems Acceptance Oil # NRCA-MCH-15-A Condenser Water Temperature Reset Controls	Mechanical Systems NRC-MCHE (Frended pi32030) (EERTIFICATE OF COMPUNACE Project Kame: Hotel be Cronado Fitness Members ARea Renovation Project Address: 1500 Orange Avenue Date Prepared: 2021-07-29	Mechanical Systems NRCC-MCH-E PROJECT FOR COMPLANCE Project Address: \$500 crange Avenue Ox. MANDATORY MEASURES DOCUMENTATION LOCATION Table Instructions: Indicate where mandatory measures are documented in the plan set or construction documentation. For any mandatory measures that do not apply, mark the plan sheet or construction document location as "N/A", any active cells that are left blank will result in non-compliance in Table C. Compliance with Mandatory Measures documented through Yes M7.02 Compliance with Mandatory Measures Note Block: W/A" and the plan sheet or construction document location NRC-MCH-E Project Address: \$500 crange Avenue Date Prepared: 2021-07-29
Mechanical Systems INCENDENCIANE (Present APRICE) REPORT OF COMPLIANCE REPORT OF COMPLIANCE REPORT OF COMPLIANCE REPORT THE COMPLIAN	Mechanical Systems NRC-MCHE (Frended pi32030) (EERTIFICATE OF COMPUNACE Project Kame: Hotel be Cronado Fitness Members ARea Renovation Project Address: 1500 Orange Avenue Date Prepared: 2021-07-29	Mechanical Systems NRC-MCH-E NRC-MCH-E Project Address: 1500 Crange Avenue Onto Project Address: 1500 Orange Avenue Onto Project Avenue Onto Project Avenue Onto Project Avenue Onto Project A
INCEMENTAL Florence JOSEPHANNE FORCE MARKET FLORENCE (PORTHANNE) FORCE MARKET STATES AND CONTRIBUTION OF PERSONAL PROPERTY AND CONTRIBUTION OF P	Mechanical Systems NRC-MCHE (Frended pi32030) (EERTIFICATE OF COMPUNACE Project Kame: Hotel be Cronado Fitness Members ARea Renovation Project Address: 1500 Orange Avenue Date Prepared: 2021-07-29	Mechanical Systems NRC-MCHE (Forated 87)2000 [CERTIFICATE OF COMPLIANCE Project Address: \$500 Orange Avenue Onter Propiect Maries Mote De Common Filmess Members ARea Renovation Report Page: Prage 9 of 10
MICHANICA SYSTEMS CERTIFICATE OF COMPLIANCE FORCE AND CONTROLLED OF COMPLIANCE FORCE THANKS IN CONTROLLED OF CONTROLLED OF CONTROLS FINES Members After Renovation FORCE THANKS IN CONTROLLED OF CONTROLS FINES Members After Renovation FORCE THANKS IN CONTROLLED OF CONTROLS FINES Members After Renovation FORCE THANKS IN CONTROLLED OF CONTROLS FINES MEmbers After Renovation FORCE THANKS IN CONTROLLED OF CONTROLS FINES MEmbers After Renovation FORCE THANKS IN CONTROLLED OF CONTROLS FINES MEMBERS AND CONTROLS FINES	Mechanical Systems NRC-MCHE (Frended pi32030) (EERTIFICATE OF COMPUNACE Project Kame: Hotel be Cronado Fitness Members ARea Renovation Project Address: 1500 Orange Avenue Date Prepared: 2021-07-29	Mechanical Systems NRC-MCH-E NRC-MCH-E Project Address: 1500 Crange Avenue Onto Project Address: 1500 Orange Avenue Onto Project Avenue Onto Project Avenue Onto Project Avenue Onto Project A
Mechanical Systems CRETHEAT OF COMPLANCE CRETHEAT OF CRE	Mechanical Systems NRC-MCHE (Frended pi32030) (EERTIFICATE OF COMPUNACE Project Kame: Hotel be Cronado Fitness Members ARea Renovation Project Address: 1500 Orange Avenue Date Prepared: 2021-07-29	Mechanical Systems NRC-MCHE (Forated 87)2000 [CERTIFICATE OF COMPLIANCE Project Address: \$500 Orange Avenue Onter Propiect Maries Mote De Common Filmess Members ARea Renovation Report Page: Prage 9 of 10
MICHANICA Systems CERTIFICATE (DE COMPLANCE MICHANICA STATE STATE A CONTINUE AREA PROPERTY STATE OF THE PROP	Mechanical Systems NRC-MCHE (Frended pi32030) (EERTIFICATE OF COMPUNACE Project Kame: Hotel be Cronado Fitness Members ARea Renovation Project Address: 1500 Orange Avenue Date Prepared: 2021-07-29	Mechanical Systems NRC-MCH-E (Pinate 40)(2000) [CERTIFICATE OF COMPLIANCE NRC-MCH-E Project Marms: Hotel De Loronado Fitness Members ARea Renovation Project Address: \$500 orange Avenue Oate Prepared: 2021.07.29
Control (power all price (CAMPUND) CAMPUND) CAMPU	Mechanical Systems NRC-MCHE (Frended pi32030) (EERTIFICATE OF COMPUNACE Project Kame: Hotel be Cronado Fitness Members ARea Renovation Project Address: 1500 Orange Avenue Date Prepared: 2021-07-29	Mechanical Systems NRC-MCHE (Finated 97)2070) (ERTIFICATE OF COMPLIANCE NRCC-MCHE Project Marme: Hotel De Connado Fitness Members ARea Renovation Report Page: Page 9 of 10 Project Address: 3500 Orange Avenue Oate Prepared: Q. MANDATORY MEASURES DOCUMENTATION LOCATION Table Instructions: Indicate where mondatory measures are documented in the plan set or construction documentation. For any mandatory measures that do not apply, mark the plan sheet or construction document location as "N/A", any active cells that are left blank will result in non-compliance in Table C. O1 Plan sheet or construction document location Compliance with Mandatory Measures Socumented through Yes M7.02
Rechanical Systems Countries was a service of the complete of the countries of the countri	Mechanical Systems NRC-MCHE (Frended pi32030) (EERTIFICATE OF COMPUNACE Project Kame: Hotel be Cronado Fitness Members ARea Renovation Project Address: 1500 Orange Avenue Date Prepared: 2021-07-29	Mechanical Systems NRIC-MORE (Renated 97)2070) (ERRIFICATE OF COMPLIANCE Project Marme: Hotel Del Coronado Fitness Members ARea Renovation Project Address: 3500 orange Avenue Q. MANDATORY MEASURES DOCUMENTATION LOCATION Table Instructions: Indicate where mondatory measures are documented in the plan set or construction documentation. For any mandatory measures that do not apply, mark the plan sheet or construction document location as "N/A", any active cells that are left blank will result in non-compliance in Table C. O1 Plan sheet or construction document location Compliance with Mandatory Measures documented through Yes M7.02
Country Temporary Tempor	Mechanical Systems NRC-MCHE (Frended pi32030) (EERTIFICATE OF COMPUNACE Project Kame: Hotel be Cronado Fitness Members ARea Renovation Project Address: 1500 Orange Avenue Date Prepared: 2021-07-29	Mechanical Systems NRC-MORE (Renate 97)2070) (ERRIFICATE OF COMPLIANCE Project Marme: Hotel De Loronado Fitness Members ARea Renovation Project Address: 1500 Orange Avenue Oate Prepared: Q. MANDATORY MEASURES DOCUMENTATION LOCATION Table Instructions: Indicate where mondatory measures are documented in the plan set or construction documentation. For any mandatory measures that do not apply, mark the plan sheet or construction document location as "N/A", any active cells that are left blank will result in non-compliance in Table C. O1 Plan sheet or construction document location Compliance with Mandatory Measures documented through Yes M7.02
Con File Count of Prison of 1970 Control (1970) Count of 1970 Count of 1	Mechanical Systems NRC-MCHE (Frended pi32030) (EERTIFICATE OF COMPUNACE Project Kame: Hotel be Cronado Fitness Members ARea Renovation Project Address: 1500 Orange Avenue Date Prepared: 2021-07-29	Mechanical Systems NRIC-MORE (Renated 97)2070) (ERRIFICATE OF COMPLIANCE Project Marme: Hotel Del Coronado Fitness Members ARea Renovation Project Address: 3500 orange Avenue Q. MANDATORY MEASURES DOCUMENTATION LOCATION Table Instructions: Indicate where mondatory measures are documented in the plan set or construction documentation. For any mandatory measures that do not apply, mark the plan sheet or construction document location as "N/A", any active cells that are left blank will result in non-compliance in Table C. O1 Plan sheet or construction document location Compliance with Mandatory Measures documented through Yes M7.02
COLORISMS	Mechanical Systems NRC-MCHE (Frended pi32030) (EERTIFICATE OF COMPUNACE Project Kame: Hotel be Cronado Fitness Members ARea Renovation Project Address: 1500 Orange Avenue Date Prepared: 2021-07-29	Mechanical Systems NRC-MCHE (Finated 97)2020) (ERTIFICATE OF COMPLIANCE NRC-MCHE Project Marme: Hotel De Loronado Fitness Members ARea Renovation Report Page: Page 9 of 10 Project Address: 1500 Orange Avenue Oate Prepared: Oate Prep
Country Temporary Tempor	Mechanical Systems NRC-MCHE (Frended pi32030) (EERTIFICATE OF COMPUNACE Project Kame: Hotel be Cronado Fitness Members ARea Renovation Project Address: 1500 Orange Avenue Date Prepared: 2021-07-29	Mechanical Systems NRCC-MCH-E PROJECT FOR COMPLANCE Project Address: \$500 crange Avenue Ox. MANDATORY MEASURES DOCUMENTATION LOCATION Table Instructions: Indicate where mandatory measures are documented in the plan set or construction documentation. For any mandatory measures that do not apply, mark the plan sheet or construction document location as "N/A", any active cells that are left blank will result in non-compliance in Table C. Compliance with Mandatory Measures documented through Yes M7.02 Compliance with Mandatory Measures Note Block: W/A" and the plan sheet or construction document location NRC-MCH-E Project Address: \$500 crange Avenue Date Prepared: 2021-07-29
Wechanical Systems COLITIONS CHIEF CONTROLL CON	Mechanical Systems NRC-MCHE (Frended pi32030) (EERTIFICATE OF COMPUNACE Project Kame: Hotel be Cronado Fitness Members ARea Renovation Project Address: 1500 Orange Avenue Date Prepared: 2021-07-29	Mechanical Systems NRCC-MCH-E PROJECT FOR COMPLANCE Project Address: \$500 crange Avenue Ox. MANDATORY MEASURES DOCUMENTATION LOCATION Table Instructions: Indicate where mandatory measures are documented in the plan set or construction documentation. For any mandatory measures that do not apply, mark the plan sheet or construction document location as "N/A", any active cells that are left blank will result in non-compliance in Table C. Compliance with Mandatory Measures documented through Yes M7.02 Compliance with Mandatory Measures Note Block: W/A" and the plan sheet or construction document location NRC-MCH-E Project Address: \$500 crange Avenue Date Prepared: 2021-07-29

TITLE-24 MANDATORY MEASURES

EQUIPMENT AND SYSTEMS EFFICIENCY

- 1. ANY APPLIANCE FOR WHICH THERE IS A CALIFORNIA STANDARD ESTABLISHED IN THE APPLIANCE EFFICIENCY STANDARDS MAY BE INSTALLED ONLY IF THE MANUFACTURER HAS CERTIFIED TO THE COMMISSION, AS SPECIFIED IN THOSE REGULATIONS, T HAT THE APPLIANCE COMPLIES WITH THE APPLICABLE STANDARD FOR THAT APPLIANCE.
- 2. PIPING AND DUCTING SYSTEMS SHALL BE INSULATED IN ACCORDANCE WITH THE SECTIONS 120.3, 120.4, 120.7 OF TITLE 24 ENERGY EFFICIENCY STANDARDS, CHAPTER 6 OF THE 2019 CMC, AND ALL CODES HAVING JURISDICTION.
- 3. ALL HVAC SYSTEMS SHALL MEET THE EFFICIENCY AND CONTROL REQUIREMENTS PER SECTION 110.2 AND 120.2 E.E.S.
- 4. ALL HVAC EQUIPMENT AND APPLIANCES SHALL MEET THE REQUIREMENTS PER SECTION

110.1-110.3, 110.5, 120.1-120.4 TITLE-24 ENERGY STANDARDS.

- 5. EACH SPACE CONDITIONING SYSTEM SHALL BE INSTALLED WITH AN AUTOMATIC TIME SWITCH WITH AN ACCESSIBLE MANUAL OVERRIDE THAT ALLOW OPERATION OF THE SYSTEM DURING OFF-HOURS FOR UP TO 4 HOURS. THE TIME SWITCH SHALL BE CAPABLE OF PROGRAMMING DIFFERENT SCHEDULES FOR WEEKDAYS AND WEEKENDS, INCORPORATE AN AUTOMATIC HOLIDAY "SHUT-OFF" FEATURE THAT TURNS OFF ALL LOADS FOR AT LEAST 24 HOURS, THEN RESUMES THE NORMALLY SCHEDULED OPERATION, AND HAS PROGRAM BACKUP CAPABILITIES THAT PREVENT THE LOSS OF THE DEVICE'S PROGRAM AND TIME SETTING FOR AT LEAST 10 HOURS IF POWER IS
- 6. EACH SPACE CONDITIONING SYSTEM SHALL BE INSTALLED WITH CONTROLS THAT TEMPORARILY RESTART AND TEMPORARILY OPERATE THE SYSTEM AS REQUIRED TO MAINTAIN A SETBACK HEATING AND COOLING THERMOSTAT SETPOINT.
- 7. EACH SPACE CONDITIONING ZONE SHALL BE CONTROLLED BY AN INDIVIDUAL THERMOSTATIC CONTROL THAT RESPONDS TO TEMPERATURE WITHIN THE ZONE. WHERE USED TO CONTROL HEATING, THE CONTROL SHALL BE ADJUSTABLE DOWN TO 55°F OR LOWER. FOR COOLING, THE CONTROL SHALL BE ADJUSTABLE UP TO 85°F OR HIGHER. WHERE USED TO CONTROL BOTH HEATING AND COOLING, THE CONTROL SHALL BE CAPABLE OF PROVIDING A DEAD BAND OR AT LEAST 5°F WITHIN WHICH THE SUPPLY OR HEATING AND COOLING IS SHUT OFF OF REDUCED TO A MINIMUM.
- 8. THERMOSTATS SHALL HAVE NUMERIC SETPOINTS IN °F.
- 9. THERMOSTATS SHALL HAVE ADJUSTABLE SETPOINT STOPS ACCESSIBLE ONLY TO AUTHORIZED PERSONNEL.
- 10. HEAT PUMPS SHALL BE INSTALLED WITH CONTROLS TO PREVENT ELECTRIC RESISTANCE SUPPLEMENTARY HEATER OPERATION WHEN THE HEATING LOAD CAN BE MET BY THE HEAT PUMP ALONE. ELECTRIC RESISTANCE SUPPLEMENTARY HEATING OPERATION IS PERMITTED DURING TRANSIENT PERIODS, SUCH AS START-UPS AND FOLLOWING ROOM THERMOSTAT SETPOINT ADVANCE, WHEN CONTROLS ARE PROVIDED WHICH USE PREFERENTIAL RATE CONTROL, INTELLIGENT RECOVERY, STAGING, RAMPING, OR SIMILAR CONTROL MECHANISMS DESIGNED TO PRECLUDE THE UNNECESSARY OPERATION OF SUPPLEMENTARY HEATING DURING THE RECOVERY PERIOD. SUPPLEMENTARY HEATER OPERATION IS ALSO PERMITTED DURING DEFROST.
- 11. GRAVITY OR AUTOMATIC DAMPERS INTERLOCKED AND CLOSED ON FAN SHUTDOWN SHALL BE PROVIDED ON THE OUTSIDE AIR INTAKES AND DISCHARGES OF ALL SPACE CONDITIONING AND EXHAUST SYSTEMS.
- 12. ALL GRAVITY VENTILATING SYSTEMS SHALL BE PROVIDED WITH AUTOMATIC OR READILY ACCESSIBLE MANUALLY OPERATED DAMPERS IN ALL OPENINGS TO THE OUTSIDE, EXCEPT FOR COMBUSTION AIR OPENINGS.
- 13. ALL BALANCING: ALL SPACE CONDITIONING AND VENTILATION SYSTEMS SHALL BE BALANCED TO THE QUANTITIES SPECIFIED IN THESE PLANS, IN ACCORDANCE WITH AND PERFORMED BY A COMPANY CERTIFIED BY THE NATIONAL ENVIRONMENTAL BALANCING BUREAU (NEBB) PROCEDURAL STANDARDS (1983), OR ASSOCIATED AIR BALANCE COUNCIL (AABC) NATIONAL STANDARDS (1986).
- 14. OUTSIDE AIR CERTIFICATION: THE SYSTEM SHALL PROVIDE THE MINIMUM OUTSIDE AIR AS SHOWN ON THE MECHANICAL DRAWINGS, AND SHALL BE MEASURED AND CERTIFIED BY THE INSTALLING LICENSED C-20 MECHANICAL CONTRACTOR.
- 15. THE AIR CONDITIONING SYSTEM SHALL BE ENERGIZED 1 HOUR IMMEDIATELY PRIOR TO OCCUPANCY TO PROVIDE THE MINIMUM REQUIRED VENTILATION RATE.

 16. ALL MECHANICAL CERTIFICATE OF ACCEPTANCE FORMS AAND ALL RELATED ACCEPTANCE DOUMENTS SHALL BE SUBMITTED TO THE FIELD INSPECTOR DURING CONSTRUCTION. CERTIFICATE OF OCCUPANCY WILL NOT BE ISSUED UNTIL THESE FORMS ARE REVIEWED AND APPROVED.

CALGREEN MANDATORY MEASURE NOTES

- 1. FOR NEW BUILDING 10,000 SQUARE FEET AND OVER, BUILDING COMMISSIONING SHALL BE INCLUDE IN THE DESIGN AND CONSTRUCTION PROCESSES OF THE BUILDING PROJECT TO VERIFY THAT THE BUILDING SYSTEMS AND COMPONENTS MEET THE OWNER'S OR OWNER REPRESENTATIVE'S PROJECT REQUIREMENTS. THE COMMISSIONING REQUIREMENTS SHALL INCLUDE OWNER'S PROJECT REQUIREMENTS (OPR), BASIS OF DESIGN (BOD), COMMISSIONING MEASURES, COMMISSIONING PLAN, FUNCTIONAL PERFORMANCE TESTING, DOCUMENTATION AND TRAINING AND A FINAL COMMISSIONING REPORT. (CALGREEN SECTION 5.410.2)
- 2. PROVIDE TESTING AND ADJUSTING OF SYSTEMS IN ACCORDANCE WITH CALGREEN SECTION 5.410.4.
- 3. THE PERMANENT HVAC SYSTEM SHALL ONLY BE USED DURING CONSTRUCTION IF NECESSARY TO CONDITION THE BUILDING OR AREAS OF ADDITION OR ALTERATION WITHIN THE REQUIRED TEMPERATURE RANGE FOR MATERIAL AND EQUIPMENT INSTALLATION. IF THE HVAC SYSTEM IS USED DURING CONSTRUCTION, USE RETURN AIR FILTERS WITH A MINIMUM EFFICIENCY REPORTING VALUE (MERV) OF 8, BASED ON ASHRAE 52.2-1999. REPLACE ALL FILTERS IMMEDIATELY PRIOR TO OCCUPANCY, OR, IF THE BUILDING IS OCCUPIED DURING ALTERATION, AT THE CONCLUSION OF CONSTRUCTION. (CALGREEN SECTION 5.504.1)
- 4. AT THE TIME OF ROUGH INSTALLATION, DURING STORAGE ON THE CONSTRUCTION SITE AND UNTIL FINAL STARTUP OF THE HEATING, COOLING AND VENTILATING EQUIPMENT, ALL DUCT AND OTHER RELATED AIR DISTRIBUTION COMPONENT OPENINGS SHALL BE COVERED WITH TAPE, PLASTIC, SHEET METAL OR OTHER METHODS ACCEPTABLE TO THE ENFORCING AGENCY TO REDUCE THE AMOUNT OF WATER, DUST AND DEBRIS, WHICH MAY ENTER THE SYSTEM. (CALGREEN SECTION 4.501 OR 5.504.3)
- 5. ALL PAINTS, ADHESIVES, SEALANTS AND CAULKS SHALL MEET THE REQUIREMENTS OF CALGREEN SECTION 4.504.2 OR 5.504.4.
- 6. IN MECHANICALLY VENTILATED BUILDINGS, PROVIDE REGULARLY OCCUPIED AREAS OF THE BUILDING WITH AIR FILTRATION MEDIA FOR OUTSIDE AND RETURN AIR THAT PROVIDES ATLEAST A MINIMUM EFFICIENCY REPORTING VALUE (MERV) OF 8. MERV 13 SHALL BE INSTALLED PRIOR TO OCCUPANCY, AND RECOMMENDATIONS FOR MAINTENANCE WITH FILTERS OF THE SAME VALUE SHALL BE INCLUDED IN THE OPERATIONS AND MAINTENANCE MANUAL. (CALGREEN SECTION 5.504.5.3)
- 7. FOR BUILDINGS OR ADDITIONS EQUIPPED WITH DEMAND CONTROL VENTILATION, CO2 SENSORS AND VENTILATION CONTROLS SHALL BE SPECIFIED AND INSTALLED IN ACCORDANCE WITH THE REQUIREMENTS OF THE CALIFORNIA ENERGY CODE. (CALGREEN SECTION 5.506.2)
- 8. HVAC, REFRIGERATION AND FIRE SUPPRESSION EQUIPMENT SHALL NOT CONTAIN ANY CHLOROFLUOROCARBONS (CFSs). (CALGREEN SECTION 5.508.1.1)
- 9. HVAC, REFRIGERATION AND FIRE SUPPRESSION EQUIPMENT SHALL NOT CONTAIN ANY HALONS. (CALGREEN SECTION 5.508.1.2)
- 10. LOW-RISE RESIDENTIAL: EACH BATHROOM SHALL BE MECHANICALLY VENTILATED. FANS SHALL BE ENERGY STAR COMPLIANT AND BE DUCTED TO TERMINATE OUTSIDE THE BUILDING. UNLESS FUNCTIONING AS A COMPONENT OF A WHOLE HOUSE VENTILATION SYSTEM, FANS MUST BE CONTROLLED BY A HUMIDITY CONTROL. HUMIDITY CONTROLS SHALL BE CAPABLE OF ADJUSTMENT BETWEEN A RELATIVE HUMIDITY RANGES OF LESS THAN OR EQUAL TO 50% TO A MAXIMUM OF 80%. A HUMIDITY CONTROL MAY UTILIZE MANUAL OR AUTOMATIC MEANS OF ADJUSTMENT. (CALGREEN SECTION 4.506)

HOTEL DEL CORONADO.

Fitness Members Area Renovation

1500 Orange Avenue Coronado, CA 92118



González Architects Hospitality

Mechanical/Electrical/Plumbing Engineer tk1sc Collaborative
4755 Eastgate Mall, Suite150
San Diego, CA 92121
858.362.6800



15231 Laguna Canyon Road, Suite 100
Irvine, California 92618
949.751.5800 www.tk1sc.com
Project Leader - Kenneth McClendon
Mechanical Lead - Kenneth McClendon

tk1sc Job #: 2019-0727



n Seal Address 14 NE 1st Avenue, Suite 507 Miami, FL 33132 T+1 (305) 455 4216

No Date Description

09-17-21 Permit Set

01-05-22 Owner Revisions

Drawing Title

TITLE 24 COMPLIANCE FORMS

Scale

As Noted

Date

09-17-2021

Drawn By

RS

Project No.

19022

Drawing No.

PC

T SET: ISSUED FOR CONSTRUCTION

CA Building Energy Efficiency Standards - 2019 Nonresidential Compliance: http://www.energy.ca.gov/title24/2019standards

September 2020

CONSTRUCT

4. AT THE TIME
AND UNTIL F