

May 6, 2024

CITY OF OCEANSIDE

**Laurel Elementary Safe Routes to School Improvements
CIP22-00003**

ADDENDUM NO. 2

The following additions, modifications and changes are hereby made to the Contract Documents and specifications for **Laurel Elementary Safe Routes to School Improvements CIP22-00003**.

1. This addendum modifies the following:

- Section 8: Special Provisions

a. Specifically, the following is modified for Bid Item 14:

Replace:

8.15 4" PCC SIDEWALK (Bid Item No. 14)

4" PCC Sidewalk shall conform to Section 303-5 from the Standard Specifications and G-07, G-09, G-10, and G-11 from the San Diego Regional Standard Drawings, 2021 Edition.

PCC Sidewalk shall be 4" thick Class 520-C-2500 as specified in Section 201-1.1.2 of the Standard Specifications. Concrete shall be from an approved ready-mix distributor and not be manufactured onsite. Subgrade preparation shall be per Section 301 and compacted to a minimum 95% relative compaction.

Sidewalk shall be constructed to the line, grades and designs shown on the plans or as ordered by the Engineer. Existing surfaces to be joined shall be sawcut on a neat, straight line at the join location. The Contractor shall remove and replace any new concrete work with graffiti markings and blemishes at no additional cost to the City.

Payment - Payment for 4" PCC Sidewalk shall be based on the actual quantity, Square Feet (SF), and shall include all costs for furnishing all labor, materials, equipment, and tools required for doing all work involved in removing sidewalk; at the designated locations in accordance with the plans to the nearest sidewalk joint, ADA requirements, and these Special Provisions complete in place. In addition, all work involved in setting up formwork, pouring and finishing of PCC sidewalk, disposing of PCC liquid residues and mixer wash out, repairing damaged irrigation and utilities resulted by the sidewalk work, restoring landscape to match existing, and all incidentals, and no other additional compensation will be allowed therefor.

With:

8.15A 4" PCC SIDEWALK (Bid Item No. 14)

4" PCC Sidewalk shall conform to Section 303-5 from the Standard Specifications and G-07, G-09, G-10, and G-11 from the San Diego Regional Standard Drawings, 2021 Edition. This bid item shall also include PCC Driveways and shall conform to G-14D from the San Diego Regional Standard Drawings, 2021 Edition, and Caltrans Standard Plan A87A, 2022 Edition.

PCC Sidewalk shall be 4" thick Class 520-C-2500 as specified in Section 201-1.1.2 of the Standard Specifications. Concrete shall be from an approved ready-mix distributor and not be manufactured onsite. Subgrade preparation shall be per Section 301 and compacted to a minimum 95% relative compaction.

Sidewalk and driveways shall be constructed to the line, grades and designs shown on the plans or as ordered by the Engineer. Existing surfaces to be joined shall be sawcut on a neat, straight line at the join location. The Contractor shall remove and replace any new concrete work with graffiti markings and blemishes at no additional cost to the City.

Payment - Payment for 4" PCC Sidewalk shall be based on the actual quantity, Square Feet (SF), and shall include all costs for furnishing all labor, materials, equipment, and tools required for doing all work involved in removing sidewalk; at the designated locations in accordance with the plans to the nearest sidewalk joint, ADA requirements, and these Special Provisions complete in place. In addition, all work involved in setting up formwork, pouring and finishing of PCC sidewalk, disposing of PCC liquid residues and mixer wash out, repairing damaged irrigation and utilities resulted by the sidewalk work, restoring landscape to match existing, and all incidentals, and no other additional compensation will be allowed therefore.

b. Specifically, the following is modified for Bid Item 39:

Replace:

8.25 MAINTENANCE OF THE BRAHEA ARMATA TREE – ONE YEAR PERIOD (Bid Item No. 39)

This bid item shall include furnishing all labor, materials, tools, equipment and incidentals and for doing all the working involved maintaining, establishment, and grow-in of the Brahea Armata (commonly known as the Mexican Blue Palm) Tree (tree).

The CONTRACTOR shall be responsible for keeping the tree healthy through its establishment period while completing all the necessary maintenance for one (1) year. The one-year period for the shall begin upon Acceptance Of Work of Bid Items #1-38. The Acceptance Of Work is not contingent on this bid item.

City review and approval of materials is required prior to the planting of the tree. The tree shall be planted and maintained per manufacturer instructions and the City of Oceanside Landscape Development Manual.

Payment - Payment for the Maintenance of the Brahea Armata Tree – One Year Period shall be on a lump sum basis. Such payment shall be compensated 40% during the 1st month of the one-year period, and compensated for the remaining 60% upon completion of the one-year period, for items of work and all work appurtenant thereto.

With:

8.25A MAINTENANCE OF THE BRAHEA ARMATA TREE – ONE YEAR PERIOD (Bid Item No. 39)

This bid item shall include furnishing all labor, materials, tools, equipment and incidentals and for doing all the working involved maintaining, establishment, and grow-in of the Brahea Armata (commonly known as the Mexican Blue Palm) Tree (tree).

The CONTRACTOR shall be responsible for keeping the tree healthy through its establishment period while completing all the necessary maintenance for one (1) year. The one-year period for the maintenance, establishment, and grow-in period of the tree shall begin upon Acceptance Of Work of Bid Items #1-38.

City review and approval of materials is required prior to the planting of the tree. The tree shall be planted and maintained per manufacturer instructions and the City of Oceanside Landscape Development Manual.

Payment - Payment for the Maintenance of the Brahea Armata Tree – One Year Period shall be on a lump sum basis. Such payment shall be compensated 40% during the 1st month of the one-year period, and compensated for the remaining 60% upon completion of the one-year period, for items of work and all work appurtenant thereto.

Enclosed please find a form to be signed acknowledging the receipt of this addendum. This form is to be returned with your Bid Proposal. Failure to sign and submit this form with your Bid Proposal will be cause for rejection of your bid.

CITY OF OCEANSIDE



BRIAN K. THOMAS
City Engineer



May 6, 2024

ACKNOWLEDGEMENT OF

ADDENDUM NO. 2

CITY OF OCEANSIDE

Laurel Elementary Safe Routes to School Improvements

CIP22-00003

Signing of this form acknowledges that the Contractor has received Addendum No. 2 and that they have read and understand the changes set forth in the Addendum.

This form must be signed by the Contractor's authorized representative and returned with the Bid Documents.

Authorized Representative_____

Name of Contractor_____

Date_____