


	RICAL ABBREVIATION LIST TER LIST, NOT ALL ABBREVIATIONS MAY APPEAR ON DRAWINGS.)
+18"	MOUNTING HEIGHTS ARE TO CENTERLINE OF DEVICE ABOVE FINISH FLOOR OR FINISH GRADE
A AFF AFCI AHJ AL ATS	AMPERE ABOVE FINISH FLOOR ARC FAULT CIRCUIT INTERRUPTER AUTHORITY HAVING JURISDICTION ALUMINUM AUTOMATIC TRANSFER SWITCH
C CEC	CONDUIT WITH PULL-LINE ONLY CALIFORNIA ELECTRICAL CODE
DB DC DN	DISTRIBUTION BOARD DIRECT CURRENT DOWN
(E) EC	EXISTING ELECTRICAL CONTRACTOR
FLA	FULL LOAD AMPS
GFCI GFP GRND	GROUND FAULT CIRCUIT INTERRUPTER GROUND FAULT PROTECTION GROUND
HOA HZ	HAND OFF AUTO HERTZ
IBC	INTERNATIONAL BUILDING CODE
KW	KILOWATT
MAX MCA MCC MIN MOCP MTD MTS	MOTOR CONTROL CENTER MINIMUM MAXIMUM OVER CURRENT PROTECTION
NA NC NEC NEMA NFPA NIC NO NRTL	NATIONAL ELECTRICAL CODE NATIONAL ELECTRICAL MANUFACTURERS ASSOCIATION NATIONAL FIRE PROTECTION ASSOCIATION
OC OFCI OSHPD	ON CENTER OWNER FURNISHED CONTRACTOR INSTALLED OFFICE OF STATEWIDE HEALTH PLANNING AND DEVELOPMENT
PH(ø) PNL	PHASE PANEL
S/N SQFT SWBD	SOLID NEUTRAL SQUARE FEET SWITCHBOARD
TYP	TYPICAL
UL UNO UPS	UNDERWRITERS LABORATORIES UNLESS NOTED OTHERWISE UNINTERRUPTIBLE POWER SYSTEM
V VA VAV VD	VOLT VOLT—AMP VARIABLE AIR VOLUME VOLTAGE DROP
W WP	WATT WEATHER-PROOF (NEMA 3R)
XFMR XP	TRANSFORMER EXPLOSION PROOF


YMBOL	DESCRIPTION	SYMBOL	ER LEGEND, NOT ALL SYMBOLS MAY APPEAR ON DRAWING DESCRIPTION	SYMBOL	DESCRIPTION
	SHEET NOTE REVISION NUMBER	$\rightarrow^{P}$	SINGLE RECEPTACLE WITH INTEGRAL LOW VOLTAGE TRANSFORMER AND (2) USB PORTS	7	FUSIBLE SWITCH
—F—	FIBER OPTIC LIGHTING	⇒P	DUPLEX RECEPTACLE WITH INTEGRAL LOW VOLTAGE	<b>þ</b>	
<b>V—N</b> ⊃—O—	NEON/COLD CATHODE LIGHTING COVE/LOW VOLTAGE LIGHTING		TRANSFORMER AND (2) USB PORTS  RECEPTACLE WITH INTEGRAL LOW VOLTAGE		
-LED-	LED LIGHTING	→P <sup>4</sup>	TRANSFORMER AND (4) USB PORTS		BOLTED PRESSURE SWITCH WITH GROUND FAULT PROTECTION
-0-10V MXDMX	0-10V CONTROL CABLE  DMX CONTROL CABLE	⇒ <sup>TV</sup>	TELEVISION RECEPTACLE		TAGET TROTEGRON
		<b>\text{\Omega}</b>	CEILING MOUNTED SPECIAL RECEPTACLE		
$(\mathbf{o})$	DECORATIVE LIGHT FIXTURE (OWNER FURNISHED AND CONTRACTOR INSTALLED)	<b>8</b>	FLUSH FLOOR SPECIAL RECEPTACLE	® <del>'/</del> /	KIRK-KEY SWITCH
	,		CODE BLUE PATIENT NURSE CALL	60	
	LIGHT FIXTURE	+©,	PATIENT TOILET	<u></u>	GENERATOR
	LIGHT FIXTURE WITH (1) LAMP ON EMERGENCY	T	MULTI-OUTLET PLUGSTRIP	<u>_</u>	GROUNDING ELECTRODE
	LIGHT FIXTURE ON EMERGENCY CIRCUIT OR	FB	FLOOR BOX		CINCLE METER WITH OT
	INTEGRAL BATTERY BACK-UP	OP WE	OPERATIONS PANEL	$\stackrel{M}{\longrightarrow}$	SINGLE METER WITH CT
A	LETTER INDICATES LIGHT FIXTURE TYPE AS INDICATED ON FIXTURE SCHEDULE	<u>₩</u>	WALL BOX JUNCTION BOX	·?	AUTOMATIC TRANSFER SWITCH
0	LIGHT FIXTURE		JUNCTION BOX AND SWITCH WITH CONNECTION TO		SHUNT TRIP DEVICE LOCATED IN METAL ENCLOSURE
	LIGHT FIXTURE	$_{\mathbb{O}}$ FS	FIRE/SMOKE DAMPER. COORDINATE REQUIREMENTS WITH FIRE ALARM SYSTEM AND MECHANICAL CONTROL	o	WITH HINGED AND LOCKABLE COVER
<u> </u>	LIGHT FIXTURE		DIAGRAMS	^	FEEDER OUTE AS INDICATED ON FEEDER CONFINIT
	LIGHT FIXTURE	V	JUNCTION BOX AND SWITCH WITH CONNECTION	$\Diamond$	FEEDER - SIZE AS INDICATED ON FEEDER SCHEDULE
0	DOWNLIGHT FIXTURE	<sub>Φ</sub> V	TO VARIABLE AIR VOLUME BOX. COORDINATE REQUIREMENTS WITH MECHANICAL CONTROL DIAGRAMS	<del>-</del>	MECHANICAL EQUIPMENT - SEE HVAC AND PLUMBING
	DOWNLIGHT FIXTURE ON EMERGENCY CIRCUIT	<sub>⊙</sub> DH		\-/	DRAWINGS
<b>9</b>	OR INTEGRAL BATTERY BACK-UP		DOOR HARDWARE CONNECTION		CAPACITOR
<b>₽</b> Ø	EMERGENCY BATTERY LIGHTING UNIT WITH TWIN HEADS  EMERGENCY BATTERY LIGHTING UNIT WITH TWIN HEADS	⊕ <sup>HO</sup>	DOOR HOLD OPEN		
<u>ro⊠ø</u>	AND EXIT SIGN	m,	NON-FUSED DISCONNECT SWITCH - 30A, 3P UNLESS		METER
1	STEP LIGHT	<u> </u>	NOTED OTHERWISE  FUSED DISCONNECT SWITCH - 304 3P WITH	SPD	SURGE PROTECTION DEVICE
Ю	WALL WASH/ACCENT LIGHT WALL MOUNTED FIXTURE	Ð	FUSED DISCONNECT SWITCH — 30A, 3P WITH 30A FUSES UNLESS NOTED OTHERWISE		
	POLE MOUNTED FIXTURE	C	COMPANY SWITCH	CONT	ELEVATOR/ESCALATOR CONTROLLER
ΦΦ	TRACK LIGHT WITH FIXTURE HEADS		MAGNETIC MOTOR STARTER — FVNR, NEMA SIZE #1	+++	
<b>\Sigma</b>	EXIT LIGHT WITH DIRECTIONAL ARROWS AS INDICATED CEILING MOUNTED		(UNLESS NOTED OTHERWISE) WITH HOA, RED RUN PILOT LIGHT, CONTROL XFMR, SOLID STATE	-	GROUND BUS AND GROUND ELECTRODES
ŀ <b>⊗</b>	EXIT LIGHT WITH DIRECTIONAL ARROWS AS INDICATED		OVERLOADS, (2) NO AND (2) NC CONTACTS	=	
	WALL MOUNTED  DOUBLE FACE EXIT LIGHT WITH DIRECTIONAL 1	⊠ ⊠	COMBINATION FUSED SWITCH AND STARTER AS NOTED ABOVE	<b>***</b>	GROUND GRID
<b>©</b>	ARROWS AS INDICATED CEILING MOUNTED 1	 N	COMBINATION NON-FUSED SWITCH AND STARTER AS	#	· <del>-</del>
S	SINGLE POLE SWITCH AT +44" UNLESS NOTED  DUAL SWITCH AT +44" UNLESS NOTED		NOTED ABOVE	<b>†</b>	
SS		R	RELAY CONTACTOR	/	FUSIBLE MEDIUM VOLTAGE SWITCH
S <sub>3</sub>	3-WAY POLE SWITCH AT +44" UNLESS NOTED 1	P	POWER SUPPLY	5	
S <sub>4</sub>	4-WAY POLE SWITCH AT +44" UNLESS NOTED 1	TS	TIMESWITCH	<u> </u>	
•	SWITCH WITH NEON PILOT LIGHT AT +44"	PC	PHOTOCELL (INSTALL ON ROOF FACING NORTH)		MEDIUM VOLTAGE MODULAR CONNECTORS
S <sub>P</sub>	UNLESS NOTED	нŢ	THERMOSTAT OUTLET AT +44" UNLESS NOTED		
S <sub>L</sub>	BACKLIT SWITCH AT +44" UNLESS NOTED 1		PUSHBUTTON TYPE CONTROL STATION		
	DIMMER SWITCH - SOLID STATE TYPE AT +44"		DOORBELL — CEILING MOUNTED  CIRCUIT BREAKER		
S <sub>D</sub>	UNLESS NOTED	E 22	FOOD SERVICE EQUIPMENT-SEE FOOD SERVICE PLANS		
S <sub>2P</sub>	2 POLE SWITCH		SURFACE MOUNTED PANELBOARD		
c	SWITCH - KEY OPERATED	<u> </u>	FLUSH MOUNTED PANELBOARD		
S <sub>K</sub>	SWITCH REL OF ERATED		MAIN SWITCHBOARD, MOTOR CONTROL CENTER OR DISTRIBUTION BOARD		
$S_{M}$	SWITCH WITH MOTION SENSOR		CONCRETE PULLBOX WITH HEAVY DUTY STEEL TRAFFIC		
S <sub>2M</sub>	DUAL SWITCH WITH MOTION SENSOR		COVER		
<b>2M</b>	CEILING MOUNTED MOTION SENSOR	T	TRANSFORMER		
0	DAYLIGHT OR MOTION SENSOR (INDOORS)	<u> </u>	MOTOR OUTLET		
S <sub>T</sub>	THERMAL OVERLOAD SWITCH		HOMERUN CONDUIT - STROKES INDICATE QUANTITY OF		
•		•	CONDUCTORS  CONDUIT AND/OR WIRE CONCEALED IN WALL OR ABOVE		
S <sub>TM</sub>	SWITCH WITH DIGITAL TIMER		CEILING EXCEPT IN EXPOSED STRUCTURE AREAS		
DM SM	DIMMING MODULE SWITCHING MODULE		CONDUIT AND/OR WIRE BELOW FLOOR OR GRADE  EXISTING CONDUIT AND/OR WIRE TO BE REMOVED		
<del>-</del>	SINGLE RECEPTACLE AT +18" UNLESS NOTED 1		EXISTING CONDUIT AND/OR WIRE TO REMAIN		
<del>-</del>	DUPLEX RECEPTACLE AT +18" UNLESS NOTED		(SHOWN LIGHT LINEWEIGHT)		
<b>⊕</b> <b>-⊕</b>	GFCI RECEPTACLE AT +18" UNLESS NOTED  DOUBLE DUPLEX RECEPTACLE AT +18" UNLESS NOTED		CONDUIT STUB-OUT CONDUIT AND/OR WIRE RISER UP/RISER DOWN		
<b>=</b>	ISOLATED GROUND TYPE (ORANGE) DUPLEX		CIRCUITING - STROKE WITH DOT INDICATES ISOLATED		
+⊚	RECEPTACLE AT +18" UNLESS NOTED  SPECIAL RECEPTACLE AT +18" UNLESS NOTED		GROUND CONDUCTOR  1/2"-2 #12 & 1 #12 GRND THWN UNLESS NOTED		
F <b>Ø</b>	100 AMP PIN AND SLEEVE RECEPTACLE		1/2"-3 #12 & 1 #12 GRND THWN UNLESS NOTED		
Ю	CLOCK RECEPTACLE AT +90" UNLESS NOTED		1/2"-4 #12 & 1 #12 GRND THWN UNLESS NOTED	_	
<u></u> 0	FLUSH FLOOR DUPLEX RECEPTACLE	<del></del>	1/2"-5 #12 & 1 #12 GRND THWN UNLESS NOTED 3/4"-6 #10 & 1 #10 GRND THWN UNLESS NOTED		
⊙ <sup>Q</sup>	FLUSH FLOOR DOUBLE DUPLEX RECEPTACLE	<del>-       </del>	3/4"-7 #10 & 1 #10 GRND THWN UNLESS NOTED		
⊖	CEILING MOUNTED DUPLEX RECEPTACLE  1/2 SWITCHED (BOTTOM HALF) DUPLEX RECEPTACLE	<del></del>	3/4"-8 #10 & 1 #10 GRND THWN UNLESS NOTED		
<del>-</del>	AT +18" UNLESS NOTED	, , , , , , , , , , , , , , , ,	DDIMADY MEDIUM VOLTAGE CHATCH METH CHIT		
<b>-</b>	EMERGENCY TYPE (RED) DUPLEX RECEPTACLE		PRIMARY MEDIUM VOLTAGE SWITCH WITH UNIT SUBSTATION		
	AT +18" UNLESS NOTED  DOUBLE DUPLEX (HALF NORMAL/HALF ISOLATED GRND)	_ <u> </u>			
=	AT +18" UNLESS NOTED		DDIMADY MEDITIM VOLTAGE CONTOUT EXTERIOR DAD		
⇒ <sup>AV</sup>	AV RECEPTACLE		PRIMARY MEDIUM VOLTAGE SWITCH EXTERIOR PAD MOUNT		
⇒B	RECEPTACLE FOR INSECT LIGHT TRAP INSTALL 2'-6"	†			
	BELOW FINISHED CEILING	<u>'</u>	CIRCUIT BREAKER		
<b>⊕</b> C	RECEPTACLE INSTALLED ABOVE COUNTER 1	•			
⇒D	IANIIS DISDIAY DOADD DECEDTAGIE	© <u>-</u> )	SHUNT TRIP CIRCUIT BREAKER		
	JANUS DISPLAY BOARD RECEPTACLE				
⇒ <sup>F</sup>	FOOD CART RECEPTACLE 1		DRAW-OUT CIRCUIT BREAKER - MEDIUM VOLTAGE		
⇒H	PECEDIACIE INICIALIED LICOLIZONITALIA	<b>¥</b>	SININ SOL SINSOLL BINEARLIN - MILDIUM VOLTAGE		
<b>→</b>	RECEPTACLE INSTALLED HORIZONTALLY	<b>1</b>	DDAW OUT OIDOUIT BREAKER COOKS	_	
-	TIMEOLOGIC DECEDITACIE	ر	DRAW-OUT CIRCUIT BREAKER - 600 VOLT		
⇒ <sup>T</sup>	TIMECLOCK RECEPTACLE	•			
₽ <sup>T</sup>	IIMECLOCK RECEPTACLE	<b>-</b>		•	NOTES











Sheet Title
COVER SHEET

City of La Mesa
Police Facility
For Construction

Project Architect Mike Smith

Drawn By ES/GM/SC Project Number 200509.00 Date: 08-17-18

Sheet Number

**E0.00** 



### <u>GENERAL</u>

- GENERAL CONDITIONS, SPECIAL REQUIREMENTS OR GENERAL REQUIREMENTS OF THE PROJECT SPECIFICATIONS MANUAL ARE MADE PART OF THIS SPECIFICATION AND HAVE THE SAME FORCE AND EFFECT AS IF COMPLETELY REPRODUCED.
- DEFINITIONS: THE WORD "WORK" SHALL MEAN LABOR AND ANY INCIDENTAL ITEMS OR SERVICES NECESSARY FOR THE PROPER INSTALLATION AND OPERATION OF THE COMPLETE SYSTEMS NOTED ON THESE DRAWINGS AND ASSOCIATED SPECIFICATIONS. THE WORD "PROVIDE" SHALL MEAN FURNISH AND INSTALL AND MAKE FINAL CONNECTIONS AND LEAVE IN AN APPROVED COMPLETE OPERATING CONDITION.
- WORK SHALL BE PROVIDED IN ACCORDANCE WITH THE LATEST ADOPTED EDITIONS OF THE APPLICABLE CBC (CALIFORNIA BUILDING CODE), CECRS (CALIFORNIA ENERGY COMMISSION REGULATIONS AND STANDARDS), CEC (CALIFORNIA ELECTRICAL CODE), ADA (AMERICANS WITH DISABILITIES ACT), AND OTHER APPLICABLE FEDERAL, STATE, AND LOCAL REGULATIONS: INCLUDING AMENDMENTS.
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR PAYING FEES AND OBTAINING PERMITS AND INSPECTIONS REQUIRED FOR THE WORK.
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROPER FITTING OF MATERIAL INTO THE BUILDING AS INDICATED ON DRAWINGS, WITHOUT INTERFERENCE WITH OTHER WORK, AND SHALL MAKE REASONABLE MODIFICATIONS IN THE LAYOUTS NEEDED TO PREVENT CONFLICT WITH OTHER TRADES, TO PROVIDE ACCESS AND FOR THE PROPER EXECUTION OF THE WORK.
- WORK SHALL BE COORDINATED WITH THE WORK OF OTHER TRADES INCLUDING CONTRACT DOCUMENTS, SHOP DRAWINGS, AND EXISTING SYSTEMS.
- DO NOT SCALE DRAWINGS AS THEY ARE DIAGRAMMATIC AND SCHEMATIC IN NATURE. CONTRACTOR SHALL PROVIDE NECESSARY ITEMS TO COMPLETE THE WORK ACCORDING TO INDUSTRY STANDARDS. IT IS THE INTENT OF THE DRAWINGS AND SPECIFICATIONS TO CALL OUT FOR FINISHED WORK, TESTED AND READY FOR OPERATIONS. ARRANGEMENT OF EQUIPMENT AND ROUTING OF RACEWAYS INDICATED ON DRAWINGS SHALL BE ROUTED PLUMB AND AT RIGHT ANGLES. INSTALLATION OF SYSTEMS MAY REQUIRE MODIFICATION DUE TO UNFORESEEN CONDITIONS.
- VERIFY ALL SIZES. DIMENSIONS. AND CONDITIONS BEFORE STARTING ANY WORK. ANY DEVIATIONS OR PROBLEMS SHALL BE TRANSMITTED TO THE ARCHITECT FOR REVIEW.
- 9. IT IS THE INTENT OF THESE DRAWINGS AND SPECIFICATIONS TO ESTABLISH A STANDARD OF QUALITY.
- 10. WORK SHALL BE PERFORMED IN A WORKMANLIKE MANNER TO THE SATISFACTION OF THE ARCHITECT.
- 11. GUARANTEE THE INSTALLATION AGAINST DEFECTS IN MATERIALS AND WORKMANSHIP WHICH MAY OCCUR UNDER NORMAL USAGE FOR A PERIOD OF ONE YEAR AFTER OWNER'S ACCEPTANCE. DEFECTS SHALL BE PROMPTLY REMEDIED WITHOUT COST TO THE OWNER.
- 12. SYSTEMS SHALL BE TESTED FOR PROPER OPERATION, IF TESTS SHOW THAT WORK IS DEFECTIVE. CONTRACTOR SHALL MAKE CORRECTIONS NECESSARY AT NO COST TO OWNER.
- 13. CONTRACTOR SHALL BE RESPONSIBLE FOR REPLACING EQUIPMENT WHICH IS DAMAGED DUE TO INCORRECT FIELD WIRING PROVIDED UNDER THIS SECTION OR FACTORY WIRING IN EQUIPMENT PROVIDED UNDER THIS SECTION.
- 14. SYSTEMS SHALL BE COMPLETE, OPERABLE AND READY FOR CONTINUOUS OPERATIONS. LIGHTS. SWITCHES, RECEPTACLES, MOTORS, ETC SHALL BE CONNECTED AND OPERABLE.
- 15. ALL ELECTRICAL SYSTEMS COMPONENTS SHALL BE LISTED OR LABELED BY UNDERWRITERS LABORATORY (UL) OR OTHER NATIONALLY RECOGNIZED TESTING LABORATORY (NRTL).
- EXISTING CONDITIONS
- THIS PROJECT INVOLVES CONSTRUCTION INSIDE AN EXISTING STRUCTURE. CONTRACTORS, BY SUBMITTING A BID ARE DEEMED TO BE COMPLETELY FAMILIAR WITH THE EXISTING CONDITIONS OF THE BUILDING AS IT INFLUENCES THE WORK DESCRIBED. NO CLAIMS FOR EXTRA COMPENSATION WILL BE CONSIDERED FOR EXISTING CONDITIONS VISIBLE OR REASONABLY INFERABLE FROM A CAREFUL EXAMINATION OF THE EXISTING BUILDING CONDITIONS.
- CONTRACTOR SHALL INSPECT THE EXISTING FIELD CONDITIONS AT THE SITE AND THE CONTRACT DOCUMENTS PRIOR TO THE START OF ANY WORK TO DETERMINE WHAT EFFECT THE EXISTING CONDITIONS WILL HAVE ON THE WORK. CONTRACTOR SHALL REPORT DISCREPANCIES TO THE ARCHITECT AND INCLUDE IN HIS BID ALL COSTS REQUIRED TO MAKE HIS WORK MEET EXISTING CONDITIONS.
- CONTRACTOR SHALL CONNECT THEIR WORK TO VARIOUS EXISTING ELECTRICAL SYSTEMS. THE NEW WORK SHALL BE COMPATIBLE WITH THE EXISTING SYSTEM CONDITIONS.
- CARE SHALL BE TAKEN DURING INSTALLATION OF THE NEW WORK, AS NOT TO DAMAGE OR INTERRUPT THE EXISTING BUILDING SYSTEMS AND SERVICES INSTALLED. DAMAGE TO EXISTING SYSTEMS AND EQUIPMENT CAUSED BY CONTRACTOR DURING THE INSTALLATION OF THEIR WORK SHALL BE REPAIRED AND/OR REPLACED AT CONTRACTOR'S EXPENSE TO THE SATISFACTION OF THE BUILDING OWNER.
- SHUTDOWN OF EXISTING SYSTEMS FOR CONNECTION TO EXISTING SERVICES SHALL BE COORDINATED WITH THE OWNER. CONTRACTOR SHALL SUBMIT REQUESTS WHERE THEY AFFECT THE OPERATION OF THE BUILDING SYSTEMS AT LEAST ONE (1) WEEK IN ADVANCE OF ANY REQUIRED SHUTDOWN. THE ACTUAL SHUTDOWN PERIOD SHALL BE AS SHORT AS POSSIBLE AND AT A TIME AGREED TO BY THE OWNER.
- DEMOLITION SHALL BE COORDINATED WITH OWNER, ARCHITECT AND CONTRACTOR.
- REPORT ANY EQUIPMENT DISCREPANCIES FOUND TO THE ARCHITECT WITHIN FIVE (5) DAYS OF DISCOVERY.
- REPORT DISCREPANCIES TO THE ARCHITECT AND INCLUDE IN THE BID ALL COSTS REQUIRED TO MAKE NEW WORK MEET EXISTING CONDITIONS.
- PROVIDE ELECTRICAL DEMOLITION REQUIRED. REFER TO ARCHITECTURAL DEMOLITION DRAWINGS FOR LOCATION AND EXTENT OF DEMOLITION REQUIRED. CONTRACTOR SHALL VISIT SITE PRIOR TO BID TO DETERMINE EXTENT OF WORK INVOLVED. PROVIDE LABOR AND MATERIALS AS REQUIRED TO MAINTAIN AND/OR RESTORE CONTINUITY OF SERVICE TO EXISTING CIRCUITS.
- 10. CONTRACTOR SHALL BE RESPONSIBLE TO FIELD VERIFY EXISTING EQUIPMENT OR CIRCUITS THAT ARE REMAINING TO BE RECONNECTED TO NEW OR EXISTING SWITCHBOARDS/ PANELBOARDS. PROVIDE SWITCHES, RECEPTACLES, CONDUIT, WIRE, ETC AS REQUIRED TO RESTORE CONTINUITY OF CIRCUIT(S).
- CONTRACTOR SHALL PROVIDE NECESSARY DEMOLITION TO REMOVE EXISTING UNUSED CONDUIT. WIRE, CABLE, JUNCTION BOXES, RECEPTACLES, SWITCHES, LIGHTS, FIRE ALARM DEVICES, ETC COMPLETE WITH ASSOCIATED CIRCUIT TO SOURCE.
- 12. IMMEDIATELY AFTER AWARD OF CONTRACT, CONTRACTOR SHALL VERIFY AVAILABLE PHYSICAL SPACE AND AMPACITY OF EXISTING PANELBOARDS, SWITCHBOARDS, DISTRIBUTION BOARDS. MOTOR CONTROL CENTERS, ETC AND PROVIDE WRITTEN DOCUMENTATION OF FINDINGS TO THE ENGINEER.

## <u>SUBMITTALS</u>

SUBMIT SHOP DRAWINGS AND TECHNICAL DATA SHEETS FOR EQUIPMENT AND MATERIALS SPECIFIED IN ELECTRONIC PDF FORMAT, SHOP DRAWINGS AND TECHNICAL DATA SHEETS WILL BE REVIEWED BY THE ENGINEER FOR CONFORMANCE WITH THE CONTRACT DOCUMENTS AND ISSUE A WRITTEN ASSESSMENT PRIOR TO COMMENCEMENT OF WORK. SUBMITTALS SHALL INCLUDE BUT NOT BE LIMITED TO: LIGHTING FIXTURES, SWITCHGEAR, PANELBOARDS, WIRING DEVICES, SAFETY SWITCHES, FUSES, MOTOR STARTERS, LAMPS, CONDUIT, CONDUIT FITTINGS AND TRANSFORMERS.

### <u>DRAWINGS</u>

MAINTAIN TWO (2) SETS OF WHITE PRINTS OF DRAWINGS PERTAINING TO THE WORK. ONE (1) SET OF PRINTS SHALL BE KEPT ON SITE AND CHANGES OR DEVIATIONS FROM THE CONTRACT DRAWINGS SHALL BE CAREFULLY NOTED AS CHANGES OR DEVIATIONS ARE MADE. AT THE COMPLETION OF THE PROJECT AND BEFORE FINAL ACCEPTANCE OF THE WORK, COPY THE CHANGES, DEVIATIONS, AND COMPLEMENTARY INFORMATION ON THE OTHER SET OF PRINTS AND RETURN IT TO THE OWNER. THE COST OF PRINTS AND COST INVOLVED IN THE PREPARATION OF THESE RECORD DRAWINGS SHALL BE BORNE BY THE CONTRACTOR.

### PART 2 - PRODUCTS

- <u>GENERAL</u>
- PROVIDE EQUIPMENT AS SPECIFIED AND/OR SCHEDULED AND IN ACCORDANCE WITH MANUFACTURER'S PUBLISHED INSTALLATION INSTRUCTIONS. EQUIPMENT SHALL OPERATE ACCORDING TO THE MANUFACTURER'S "OWNER'S OPERATING AND MAINTENANCE MANUAL" TROUBLE-FREE.

### WIRE AND CABLE

WIRE SHALL BE COPPER, 75°C RATED FOR GENERAL USE. FOR FIXTURE AND EQUIPMENT CONNECTIONS PROVIDE WIRING WITH TEMPERATURE RATING PER MANUFACTURER'S REQUIREMENTS. SIZES INDICATED ARE FOR INSTALLATION IN A MAXIMUM 30°C AMBIENT. CONDUCTOR AMPACITY SHALL BE DE-RATED FOR HIGHER AMBIENT INSTALLATIONS.

#### RACEWAYS AND FITTINGS

- ALL WIRING SHALL BE INSTALLED IN LISTED METALLIC RACEWAYS. EMT FITTINGS SHALL BE STEEL. CONNECTORS SHALL BE INSULATED THROAT TYPE.
- ALL CONDUITS AND RACEWAYS SHALL HAVE A CODE SIZED COPPER GROUNDING CONDUCTOR. INCREASE CONDUIT SIZE AS REQUIRED.

#### DISTRIBUTION EQUIPMENT

- DISCONNECT SWITCHES SHALL BE HEAVY DUTY TYPE. FUSIBLE SWITCHES SHALL ACCEPT CLASS. 'R' FUSES ONLY AND REJECT OTHERS. INSTALL DISCONNECT SWITCH BOLTED TO HVAC UNIT FRAME WHERE POSSIBLE (COORDINATE LOCATION WITH HVAC MANUFACTURER TO AVOID WARRANTY INFRACTIONS). SILICONE SEAL ALL HOLES IN UNIT.
- <u>WIRING DEVICES</u>
- WIRING DEVICES SHALL BE SPECIFICATION GRADE AND RATED AT 20 AMPERES. THE DEVICE PLATES SHALL BE STAINLESS STEEL. THE COLOR OF THE DEVICES AND COVER PLATES SHALL BE AS DIRECTED BY ARCHITECT. EXTERIOR RECEPTACLES SHALL BE TYPE WR. GFCI.
- GROUND FAULT CIRCUIT INTERRUPTERS SHALL BE READILY ACCESSIBLE. WHERE RECEPTACLES ARE NOT READILY ACCESSIBLE. PROVIDE GFCI CIRCUIT BREAKERS AND IDENTIFY THE RECEPTACLES AS GFCI PROTECTED.

# **BOXES**

- PULLBOXES, CABINETS, ETC MOUNTED ON THE EXTERIOR AT GRADE LEVEL, SHALL BE WEATHERPROOF TYPE WITH HINGED LOCKABLE COVERS SECURED WITH TAMPER-PROOF
- BOXES SHALL BE MINIMUM 4" SQUARE WITH REQUIRED EXTENSIONS AND PLASTER OR TILE

# FIRE ALARM

- FIRE ALARM SYSTEM. CONTRACTOR SHALL PROVIDE DEVICES, CONDUIT, WIRES, CABLE, PROGRAMMING AND TESTING AS DIRECTED BY EQUIPMENT MANUFACTURER AND FIRE DEPARTMENT FOR A CODE COMPLIANT FIRE ALARM SYSTEM. MATERIALS, EQUIPMENT AND WORKMANSHIP SHALL BE COMPLETE AND OPERABLE IN EVERY RESPECT. SUBMIT SINGLE LINE OF SYSTEM WITH SHOP DRAWINGS. THIS SINGLE LINE DIAGRAM SHALL SHOW DEVICES, CONDUIT, WIRE AND CABLE SIZES. EQUIPMENT TO BE USED AND SHALL BE STAMPED AND SIGNED BY LOCAL FIRE DEPARTMENT. SYSTEM CALIBRATION AND TESTING SHALL BE BY FACTORY CERTIFIED TECHNICIAN. SUBMIT TO ENGINEER PRIOR TO SUBMITTAL TO FIRE DEPARTMENT.
- DUCT DETECTORS SHALL BE PHOTOELECTRIC TYPE FURNISHED BY CONTRACTOR, INSTALLED IN THE SUPPLY AIR DUCTS BY MECHANICAL CONTRACTOR AND CONNECTED TO THE FIRE ALARM SYSTEM BY CONTRACTOR. DUCT DETECTOR SHALL BE CONNECTED TO SHUT OFF AIR HANDLING UNITS LOCATED WITHIN THE SAME PLENUM. DUCT DETECTORS SHALL NOT BE MOUNTED IN AN ENVIRONMENT WHICH EXCEEDS 122°F. PROVIDE ZERO VELOCITY TYPE DETECTORS WHERE REQUIRED. INSTALLATION SHALL BE COORDINATED WITH MECHANICAL CONTRACTOR TO MAINTAIN AIRFLOW AND ACCESS.

# | PART 3 - EXECUTION

- <u>GENERAL</u>
- FINAL CONNECTIONS AND ROUGH-IN REQUIREMENTS TO EQUIPMENT SHALL BE PER MANUFACTURER'S APPROVED WIRING DIAGRAMS, DETAILS AND INSTRUCTIONS. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO PROVIDE MATERIALS AND EQUIPMENT COMPATIBLE WITH EQUIPMENT ACTUALLY SUPPLIED INCLUDING ALL RACEWAYS, BOXES, WIRING, WIRING DEVICES,
- 9. VERIFY EXACT LOCATION OF EQUIPMENT TO BE FURNISHED BY OTHERS PRIOR TO ROUGH-IN.
- 10. PROVIDE MAINTENANCE RECEPTACLE WITHIN 25'-0" OF ALL MECHANICAL OR MOTORIZED EQUIPMENT.
- . SEE MECHANICAL DRAWINGS FOR LOCATION OF MECHANICAL EQUIPMENT. PROVIDE SERVICE TO AND CONNECT EQUIPMENT AS REQUIRED. PROVIDE FUSES OR HACR-TYPE CIRCUIT BREAKERS FOR AIR CONDITIONING EQUIPMENT SIZED IN ACCORDANCE WITH MANUFACTURER'S NAMEPLATE.
- 12. PANEL DIRECTORIES SHALL BE REMOVABLE. ROOM NAMES AND NUMBERS SHALL BE AS DIRECTED BY OWNER. DIRECTORIES SHALL BE TYPED AND INSTALLED UNDER CLEAR PLASTIC COVERS.
- 13. CONTRACTOR SHALL PROVIDE NEW UPDATED PANELBOARD DIRECTORIES FOR EXISTING AND NEW CIRCUITS BEING UTILIZED FOR COMPLETION OF PROJECT.
- 14. CONDUITS PENETRATING THROUGH ROOF SHALL HAVE ROOF FLASHING WITH CAULK TYPE COUNTER FLASHING SLEEVE. INSTALLATION SHALL BE WATERTIGHT.
- 15. FINAL CONNECTIONS TO MOTORS, TRANSFORMERS AND OTHER VIBRATING EQUIPMENT SHALL BE WITH SEAL-TITE FLEX (3'-0" MAXIMUM LENGTH) AND APPROVED FITTINGS. DO NOT SECURE CONDUITS OR DEVICES TO DUCTWORK OR MECHANICAL EQUIPMENT.

- 16. RECEPTACLES INSTALLED OUTSIDE, ON THE BUILDING EXTERIOR OR ROOF, IN KITCHENS OR WITHIN 6'-0" HORIZONTALLY FROM A SINK OR DRINKING FOUNTAIN UNLESS LOCATED BELOW A COUNTER OR OTHERWISE PROTECTED SHALL BE GFCI TYPE OR PROTECTED BY GFI CIRCUIT BREAKER.
- SEISMIC ANCHORAGE

## **EQUIPMENT ANCHORAGE DETAILING:**

- SHOW THE FOLLOWING NOTE PROMINENTLY ON THESE DRAWINGS:
  - 1.A. ANCHORAGE AND SUPPORTS OF ALL EQUIPMENT TO BE INSTALLED. AS A PART OF THIS PROJECT SHALL BE DETAILED ON CONSTRUCTION DOCUMENTS. EXCEPT THOSE EXEMPT BY 2010 CBC SECTION 1615A.1.12.
- 1.B. EQUIPMENT SUPPORTS AND ANCHORAGE SHALL BE APPROVED BY THE APPROPRIATE DESIGN PROFESSIONAL OF RECORD AND OSHPD AS A PART OF FIELD REVIEWS/OBSERVATIONS. THE INSPECTOR OF RECORD (IOR) SHALL ASSURE THAT THE ABOVE REQUIREMENTS ARE ENFORCED.
- 2. REFERENCE: 2010 CBC SECTIONS 107 AND 1615A.

## **ELECTRICAL**:

WHEN INSTALLING DRILLED-IN ANCHORS AND/OR POWDER DRIVEN PINS IN EXISTING NON-PRESTRESSED REINFORCED CONCRETE, USE CARE AND CAUTION TO AVOID CUTTING OR DAMAGING THE EXISTING REINFORCING BARS. WHEN INSTALLING THEM INTO EXISTING PRE-STRESSED CONCRETE (PRE- OR POST-TENSIONED) LOCATE THE PRE-STRESSED TENDONS BY USING A NON-DESTRUCTIVE METHOD PRIOR TO INSTALLATION. EXERCISE EXTREME CARE AND CAUTION TO AVOID CUTTING OR DAMAGING THE TENDONS DURING INSTALLATION. MAINTAIN A MINIMUM CLEARANCE OF ONE INCH BETWEEN THE REINFORCEMENT AND THE DRILLED-IN ANCHOR AND/OR PIN.

### **EQUIPMENT ANCHORAGE NOTE:**

- ALL ELECTRICAL EQUIPMENT SHALL BE ANCHORED OR BRACED TO MEET THE HORIZONTAL AND VERTICAL FORCES PRESCRIBED IN THE 2010 CBC SECTIONS 1615A.1.20, 1615A.1.21 AND 1615A.1.22 AND ASCE 7-05 SECTIONS 13.3, 13.4, 13.6 AND CHAPTER 6.
- THE ATTACHMENT OF THE FOLLOWING ITEMS SHALL BE DESIGNED TO RESIST THE FORCES PRESCRIBED ABOVE, BUT NEED NOT BE DETAILED ON THE PLANS, AND THE PROJECT INSPECTOR WILL VERIFY THAT THESE ITEMS (EQUIPMENT) HAVE BEEN ANCHORED:
- 2.A. EQUIPMENT WEIGHING LESS THAN 400 POUNDS SUPPORTED DIRECTLY ON THE FLOOR OR ROOF.
- 2.B. FURNITURE REQUIRED TO BE ATTACHED IN ACCORDANCE WITH ASCE 7-05, SECTION
- 2.C. TEMPORARY AND MOVABLE EQUIPMENT WITH FLEXIBLE CONNECTION TO POWER OR UTILITIES.
- 2.D. EQUIPMENT WEIGHING LESS THAN 20 POUNDS SUPPORTED BY VIBRATION ISOLATORS.
- 2.E. EQUIPMENT WEIGHING LESS THAN 20 POUNDS SUSPENDED FROM A ROOF OR FLOOR OR HUNG FROM A WALL
- FOR THOSE ELEMENTS THAT DO NOT REQUIRE DETAIL ON THE APPROVED DRAWINGS, THE INSTALLATION SHALL BE SUBJECT TO THE APPROVAL OF THE MECHANICAL/ELECTRICAL

## DISTRIBUTION SYSTEM BRACING NOTE:

- ELECTRICAL DISTRIBUTION SYSTEMS SHALL BE BRACED TO RESIST THE FORCES PRESCRIBED IN ASCE 7-05 SECTION 13.3 AS DEFINED IN ASCE 7-05 SECTION 13.6.8, 13.6.7, 13.6.5.5 ITEM 6 AND 2010 CBC SECTIONS 1615A.1.20, 1615A.1.21 AND 1615A.1.22.
- THE STRUCTURAL ENGINEER OF RECORD SHALL VERIFY THE ADEQUACY OF THE STRUCTURE TO SUPPORT THE HANGER AND BRACE LOADS.



Corrections PLN CHK 08-17-18


cility  $\rightarrow$ City o Polic

> Project Architect Mike Smith

> Drawn Bv ES/GM/SC **Project Number**

Date: 08-17-18 Sheet Number

**E0.01** 





riangle PLN CHK 08-17-18

City of
Police
For Cor

Project Architect Mike Smith Drawn By ES/GM/SC Project Number 200509.00



# NOTICE

- 1. EXISTING ELECTRICAL DEVICES SHOWN LIGHT, NEW SHOWN BOLD, DEMO SHOWN LIGHT CROSSED.
- INTERLOCK INDOOR UNITS WITH OUTDOOR UNITS PER MANUFACTURER'S WIRING DIAGRAM

# **NOTES**

- 1"C-3 #8 & 1 #10 GRND.
- 2 CONNECT TO EXISTING RECEPTACLE CIRCUIT
- 3 INTERLOCK WITH INDOOR UNIT. CONDUIT AND WIRE PER MANUFACTURES WIRING DIAGRAM



Corrections


riangle PLN CHK 08-17-18


City of
Police
For Col

Drawn By ES/GM/SC

Project Number 200509.00 Date: 08-17-18

5155 W PATRICK LANE LAS VEGAS, NV 89118 702.362.9200 NV5.COM





P	ΔN	FI ·	,	Н3			VOLT			/ 277		3Ø 4	-W		CIRCUIT	CODE:	blank	or		N: NON-CONTINUOUS				
•	***								225A											L: LONG-CONTINUOUS				
				: 8/16/18 3:41 PM				INS:						FILES 22	24					R: DEMANDABLE RECEPTACLE				
		,	JOB:	: 018.0405.000		Alc	CRAT	TING:	14,000			UNTIN								K: KITCHEN NO. OF E	QUIPME	NT:		0
오	اسا		ш	LOAD DESIGN	ATION					C O	N N	E C	T	E D	V A					LOAD DESIGNATION		ш.	سا	2
CKT NO	CODE	TRIP	POLE	DESCRIPTION	(NOT	E) N	vi R	L	ØA	ØВ	ØC	АВ	С	ØA	ØB	ØС	LR	۱ ۱	м (N	OTE) DESCRIPTION	물	POLE	戹	CKT NO
1		20	1	(E) DETECTIVES			+	40	2600			1.		1320			4	$^{+}$	1	(E) ATRIUM LIGHTS	20		Ť	2
3		20		(E) CORRIDORS		$\top$		45		3250			$\top$		_			$^{+}$		SPARE	20	_	$\vdash$	4
5		20		(E) MECH. YARD				4			200					_		Ť		SPARE	20	_		6
7		20	1	(E) CHIEF. CAPT.				40	2600	] '				_				$^{\dagger}$		SPARE	20	_		8
9		20		(E) ATRIUM				14		500					_	]		Ť		SPARE	20	1		10
11		20	1	SPARE							_		•	'		_		Ť		SPARE	20	1		12
13		20		SPARE					_	] '		1.		-				Ť		SPARE	20	1		14
15		20	_	SPARE						_					_			$\top$		SPARE	20	1		16
17		20	1	SPARE							_		•	'		_		$\top$		SPARE	20	1		18
19		20	1	SPARE					_	] '				-				T		SPARE	20	1		20
21		20	1	SPARE						- 1		•			_					SPARE	20	1		22
23		20	1	SPARE							_		•			_				SPARE	20	1		24
25		20	1	SPARE					_	] '				-						SPARE	20	1		26
27		20	1	SPARE						-		·			-					SPARE	20	1		28
29		20	1	SPARE							-		•			_				SPARE	20	1		30
31		20	1	SPARE					-			•		7344					1 (1)	CU-1-9	40	/	N	3:
33		20	1	SPARE						_		•			7344							7		34
35		20	1	SPARE							-		•			7344						3	N	36
37		20	1	SPARE					-			•		-					1 (1)	CU-1-10	40		N	
39		20	1	SPARE						_		•			-							1	N	40
41		20	1	SPARE							-		•			_						3	N	42
1A <sup>c</sup>	NEL	NOT	ES:		P	HASE	T01	ALS	ØA:	3864	9	ØB: 11	094		ØC:	7544				TOTAL CONNECTED	VA	325	02	
1)	REN	/OVE	EX	KISTING (3) 20A, 1P SPARE (	CIRCUIT	BRE	EAKEF	RS AI	ND PRO	VIDE 40A	, 3P CI	RCUIT	BRE	EAKER.				Т		CONNECTED VA (CODE	N)	325	502	
٠,				ER SHALL MATCH EXISTING N														t		CONNECTED VA (CODE		(	)	
				JITS IN JUNCTION BOX ADEQU					•	•	-		TIIR	F				$\perp$		CONNECTED VA (CODE				
					JAILLI	JIZI		JI	OKKLIVI	IIIAIII OI	VIMITIA I	JIK 1 0	1010	_				ŀ		· · · · · · · · · · · · · · · · · · ·				
Ш	ILE	Z4 I	ME II	ERING														L		CONNECTED VA (CODE	<del>-</del> +-	(		
																		L		PANEL CONNECTED K	VA	32	.5	
																				PANEL DEMAND K	VA	32	.5	
																				PANEL DEMAND AM	PS	39	).1	
																		_		· ···· · · · · · · · · · · · · ·			.0	

PA	N	FI:		L3		V	OLTAGE		/ 120		3Ø 4	W		CIRCUIT	CODE:	blo	ınk	or	N: NON-CONTINUOUS				
• • •								S: 225A											L: LONG-CONTINUOUS				
				8/17/18 8:53 AM			MAINS				OCATIO								R: DEMANDABLE RECEPTACLES				
		J	OB:	18.0405		AIC	RATING	; 10,000			DUNTIN								K: KITCHEN NO. OF EQU	JIPMEI	<u> 1T:</u>	_	0
일	ᆈ	_	ш	LOAD DI	ESIGNATION				СО	N N	E C	T	E D	V A					LOAD DESIGNATION		<u>س</u> ا		٦
CKT NO	CODE	TRIP	POLE	DESCRIPTION	(NOTE	E) M	RL	. ØA	ØB	ØC	AB	С	ØA	ØB	ØC	L	R	М	 · · · · · · · · · · · · · · · · · · ·	_ ₽	POLE		3
1		20		(E) PATROL 130				720					540						(E) MAINT 149	20	1		
3		20		(E) PATROL 129					1260	]				540					(E) MAINT 149	20	1	T	
5		20		(E) PATROL 129						540		•			360				(E) BOOKING 137	20	1	T	
7		20		(E) PATROL 129				540	7				540	]					(E) BOOKING 137	20	1	T	Ī
9		20		(E) PATROL 129					540	]				1080					(E) TECH 123	20	1	T	
11		20		(E) GEN REC'S						720		•			720				(E) TECH 123	20	1	T	
13		20	1	(E) GEN REC'S				900					1080	]					(E) TECH 123	20	1	$\top$	
15		20		(E) CRIME 127					720	]				900					(E) DATA ENTRY 124	20	1	T	
17		20		(E) INTERVIEWS						720		•			360				(E) RM 133 RECEPT	20	1	T	
19		20		(E) REPORT				720					720	]					(E) ARMORY	20	1	T	
21		20	1	(E) REPORT					720					720					(E) ARMORY	20	1	T	
23		20		(E) REPORT						720		•			_				(E) EXAM/JUV BKG 146	20	1	T	
25		20	1	(E) PATROL 135				360	7		1.		200	]				2	DAMPERS COMPUTER 122	20	1	N	ī
27		20		(E) PATROL 135					720	]				100				1	FIRE SUPRESSION PANEL	20	1	N	i
29		20		(E) PATROL 135						540		•			_				SPARE	20	1	$\top$	
31		20		(E) PATROL 135				540	7		-		-	]					SPARE	20	1	T	
33		20		(E) PATROL 135					540	]				_					SPARE	20	1	T	
35		20		(E) GEN REC'S						540		•			_				SPARE	20	1	T	
37		20		(E) MAINT 149				180	7		-		3160	]					(E) PANEL 'L3A'	20	1	T	
39		20	1	(E) MAINT 149					540					3600						20	1	T	
41		20	1	(E) BOOKING 137						720		•			2928					20	1	Т	
PAN	EL	NOTE	S:		PH	ASE	TOTAL	S ØA:	10200		ØB: 11	980		ØC:	8868				TOTAL CONNECTED VA		310	048	, -
														•					CONNECTED VA (CODE N)		310	048	, <del>-</del>
																			CONNECTED VA (CODE L)	)		0	-
																			CONNECTED VA (CODE R)	)		0	-
																		┢	CONNECTED VA (CODE K)	_		0	-
																		H	PANEL CONNECTED KVA	_		1.0	-
																		┢	PANEL DEMAND KVA	+		1.0	-
																		$\vdash$	PANEL DEMAND AMPS			5.2	-
																			I MILL DEMINITURANT	1			_

# NOTICE

Corrections

SINGLE LINE DIAGRAM

City of
Police
For Col

E5.00

 $\stackrel{\frown}{\Delta}$  PLN CHK 08-17-18

1. ALL EXISTING EQUIPMENT AND FEEDERS TO REMAIN SHOWN LIGHT, NEW SHOWN BOLD

LOAD CALCU	LA	TIOI	NS
MAIN SWITCHBOARD	'MSB-	-1'	
LOAD ADDED			
PANEL 'H2'	=	5	KVA
PANEL 'H3'	=	22	KVA
DP-1 (PANELS 'L6','L3')	=	0.48	KVA
TOTAL	=	27	KVA
/480V ,3ø	=	33	Α
		,	

LOAD CALCU	LA	101T	NS
DISTRIBUTION BOARI	D 'DP-	-1'	
LOAD ADDED			
PANEL 'L6'	=	0.18	KVA
PANEL 'L3'	=	0.30	KVA
TOTAL	=	0.48	KVA
/208V ,3ø	=	1.33	Α

5155 W PATRICK LANE LAS VEGAS, NV 89118 702.362.9200 NV5.COM

9282.09