

**BID SCHEDULE**

**BASE BID**

No.	Description	Estimated Qty	Unit of Measure	Unit Price	Total
<b>Mobilization &amp; Contractor's Facilities</b>					
1	Mobilization	LS	LS	LS	
2	Temporary Site Utilities - Water & Power	LS	LS	LS	
3	Temporary Sanitary Facilities	LS	LS	LS	
4	SWPPP Program Requirements & BMPs	LS	LS	LS	
5	Construction Survey Staking	LS	LS	LS	
<b>Civil/Sitework – Demolition</b>					
6	Demo – Appurtenances	LS	LS	LS	
7	Demo – Perimeter Fencing	4,540	LF		
8	Demo – Utilities	LS	LS	LS	
<b>Civil/Sitework - Intersection Plan</b>					
9	R1 'STOP' and R1-3 'ALL WAY' Signs & Posts	3	EA		
10	12" White Limit Line per CALTRANS Std. Plan A24E	4	EA		
11	"STOP" Marking per CALTRANS Std. Plan A24D	6	EA		
12	Type IV(L) Arrow per CALTRANS Std. Plan A24A	3	EA		
13	8" Wide White Stripe per Plan A20D / Detail 38A	50	LF		
14	W17 ' STOP AHEAD' Sign	2	EA		
15	AHEAD' Marking per CALTRANS Std. Plan A24D	2	EA		
16	Dashed 6" White Line per CALTRANS Std. Plan A20D / Detail 39A	98	LF		
17	Removal of Conflicting Markings, Sandblasting/Grinding and Sand Sealing	LS	LS	LS	
18	6" Yellow Line per Plan A20A / Detail 22	540	LF		
<b>Civil/Sitework - Site Improvements</b>					
19	6' Vinyl-Coated Chain-Link Fence per SDRSD M-06 (Site Perimeter)	2,945	LF		
20	6'x25' Vinyl-Coated Chain-Link Gate per SDRSD M-05 with Fire Dept. Lock (Main & South)	2	EA		
21	County of San Diego Day Use Sign	LS	LS	LS	
22	Peeler Pole Fence - Base Bid	552	LF		
23	County of San Diego Entrance Monument Sign	LS	LS	LS	
<b>Civil/Sitework - Grading Plan</b>					

24	Earthwork - Clear & Grub including Disposal of Vegetation Off-Site	14	ACRE		
25	Earthwork - Grading - CUT	23,200	CY		
26	Earthwork - Grading - FILL	17,000	CY		
27	Earthwork - Grading - NET SURPLUS (Haul Off Site)	6,287	CY		
28	Public Trail 4" D.G. - Rough/Fine Grading	14,985	SF		
29	Public Trail - Import 4" D.G., Place, Grade & Compact	185	CY		
30	Temporary Parking Lot Surfacing - Rough/Fine Grading	374,693	SF		
31	Temporary Parking Lot Surfacing - Import & Compact 2" DG & 2" AB	4,626	CY		
32	Minor Concrete - Main Driveway Concrete SOG	LS	LS	LS	
33	Minor Concrete - South Gate Driveway Concrete SOG	LS	LS	LS	
34	Minor Concrete - Helix Easement Overlay 9" Concrete SOG	LS	LS	LS	
35	Minor Concrete - Type A Curb Ramp per SDRSD G-27	1	EA		
36	Minor Concrete - Type B Curb Ramp per SDRSD G-27	1	EA		
<b>Civil/Sitework - Biofiltration Basins and Other Site Improvements Including Drainage Control Facilities</b>					
37	<b>Biofiltration Basin 1:</b>				
38	24"x6'-0" PVC Riser with PVC Trash Rack	1	EA		
39	3/4"-2" Clean Angular Gravel (18" Layer)	246	CY		
40	8" PVC Perforated Subdrain with Cleanout & Cap	828	LF		
41	Pea Gravel (4"-6" Layer)	82	CY		
42	Permeable Media (18" Layer)	246	CY		
43	10" PVC Solid Overflow Pipe	76	LF		
44	Aged Non-Floatable Hardwood Mulch (3" Layer)	41	CY		
45	<b>Biofiltration Basin 2:</b>				
46	24"x6'-0" PVC Riser with PVC Trash Rack	1	EA		
47	3/4"-2" Clean Angular Gravel (18" Layer)	88	CY		
48	8" PVC Perforated Subdrain with Cleanout & Cap	50	LF		
49	Pea Gravel (4"-6" Layer)	30	CY		
50	Permeable Media (18" Layer)	88	CY		
51	10" PVC Solid Overflow Pipe	79	LF		
52	Aged Non-Floatable Hardwood Mulch (3" Layer)	15	CY		
53	<b>Biofiltration Basin 3:</b>				
54	24"x6'-0" PVC Riser with PVC Trash Rack	2	EA		
55	3/4"-2" Clean Angular Gravel (18" Layer)	282	CY		

56	8" PVC Perforated Subdrain with Cleanout & Cap	177	LF		
57	Pea Gravel (4"-6" Layer)	94	CY		
58	Permeable Media (18" Layer)	282	CY		
59	12" PVC Solid Overflow Pipe	97	LF		
60	Aged Non-Floatable Hardwood Mulch (3" Layer)	47	CY		
61	<b>Site Drainage Improvements:</b>				
62	Apron East Side 7" Concrete Lining	18	CY		
63	Low Flow Channel 7" Concrete-Lined	96	CY		
64	Concrete-Lined Swale (Northeast)	27	CY		
65	Box Culvert Complete	LS	LS	LS	
66	Rip-Rap, Class No. 2 Backing, 1.5' Thick (approx. 2,500 SF) - South Side	123	CY		
67	Rip-Rap, Class No. 2 Backing, 1.5' Thick (approx. 2,000 SF) - Southeast Curve	115	CY		
68	Rip-Rap, Class No. 2 Backing, 1.5' Thick (approx. 1,000 SF) - East Side	49	CY		
69	Rip-Rap, Class No. 2 Backing, 1.5' Thick (approx. 1,000 SF) - Southwest Corner	37	CY		
<b>Civil/Sitework - Site Utilities</b>					
70	<b>Fire Water System:</b>				
71	6" PVC C-900 Class-200 Pipe	900	LF		
72	6" DI MJ 90 Ell - Epoxy Lined & Coated w/Accessories	1	EA		
73	6" DI MJ 45 Ell - Epoxy Lined & Coated w/Accessories	2	EA		
74	6" DI MJ Tee - Epoxy Lined & Coated w/Accessories	2	EA		
75	6" Flex Coupling - Epoxy Lined & Coated w/Accessories	2	EA		
76	Fire Hydrant Assembly	LS	LS	LS	
77	Fire Service Backflow Preventer Assembly	LS	LS	LS	
78	Connections - 6" PVC to 8" ACP (Lakeside Irrigation District)	LS	LS	LS	
79	Connections - 6" Meter Assembly with Concrete Pad	LS	LS	LS	
<b>Civil/Sitework - Erosion Control Plan</b>					
80	SC-05 Fiber Rolls with Staking - Biofiltration Basin 1	519	LF		
81	SC-05 Fiber Rolls with Staking - Biofiltration Basin 2	181	LF		
82	SC-05 Fiber Rolls with Staking - Biofiltration Basin 3	335	LF		
83	SC-04/06 Gravel Bag Berm (Check Dam and Inlet Protection)	333	LF		

84	SC-01 Silt Fence with Staking	3,077	LF		
85	TC-01 Construction Entrance/Exit with Rattle Strips	2	EA		
<b>Civil/Sitework - Sump Pump Station at Biofiltration Basin No. 2</b>					
86	Sump Pump Assembly	LS	LS	LS	
<b>Site - Electrical</b>					
87	SDG&E Service Planning & Permitting Fee ALLOWANCE	ALLOW	ALLOW	ALLOW	\$250,000.00
88	Primary Conduit Duct Bank from Existing SDG&E Point of Connection to Transformer Pad	LS	LS	LS	
89	Utility Transformer Concrete Pad (Assume Transformer by SDG&E) Including Grading & Precast Concrete Pad	LS	LS	LS	
90	Service Meter Switchboard 'MSB' Concrete Pad/Foundation	LS	LS	LS	
91	Service Meter Switchboard 'MSB' Grounding	LS	LS	LS	
92	Service Meter Switchboard 'MSB' 600A, 120/208V, NEMA 3R	LS	LS	LS	
93	Panel 'A' 200A - Covered Arena	LS	LS	LS	
94	Panel 'A1' 200A - Covered Arena	LS	LS	LS	
95	Panel 'E' 200A - Shop Building	LS	LS	LS	
96	Panel 'LCP' 15A - Duplex Sump Pump Local Control Panel	LS	LS	LS	
97	Pole-Mounted Light Fixtures - P1 LED Solar-Powered Area Light Fixture (5230 Lumens) - Carmanah EC-340-5230	1	EA		
98	Pole-Mounted Light Fixtures - P3 LED Solar-Powered Area Light Fixture (6060 Lumens) - Carmanah EC-340-6060	5	EA		
99	24"x8'-0" Light Pole Reinforced Concrete Bases w/Anchor Bolts	6	EA		
100	Concrete Pull Boxes (PB-1 through PB-3) - 2'x3' with Galv Steel H20-Loading Bolt-Down Cover & SS Bolts	3	EA		
101	Duct Bank PB-1 to PB-3 including Conduit, Spacers, Encasement, Wire	433	LF		
<b>Area 1 Improvements - Covered Arena</b>					
102	1.1 Structure - Column Footings/Foundations - Excavation, Form, Rebar, Set Anchor Bolts, Backfill, Ready for Building CONTRACTOR ALLOWANCE	LS	LS	LS	
103	1.1 Structure - Pre-Engineered Metal Building (incl. Sales Tax & Freight)	LS	LS	LS	
104	1.1 Structure - Pre-Engineered Metal Building (Installation)	LS	LS	LS	
105	1.6 Electronic Scoreboard	LS	LS	LS	
106	1.7 Bleachers	LS	LS	LS	

107	1.7 Bleachers Concrete Pad/Foundation/Walkways	LS	LS	LS	
108	1.8 Patio Area	LS	LS	LS	
109	1.9 Arena Fencing, Gates & Chutes (Kovac Ranch Equipment)	LS	LS	LS	
110	Arena Equipment – Footing Material - Import, Place and Compact	LS	LS	LS	
111	Arena Equipment - Electronic Public Address System	LS	LS	LS	
112	Lighting - LED High-Bay Luminaire Pendant-Mounted - Litetronics HB220W140DL	96	EA		
113	Lighting - Conduit, Wire, Hangers, J-Boxes and Misc.	LS	LS	LS	
114	Lighting - Spare Conduit Below Surface	LS	LS	LS	
115	Lighting - 0-10VDC Lighting Dimmer Controls Station	1	EA		
116	Lighting - Ceiling Fan Controls Station	1	EA		
117	Electrical Terminations, Ring-Out, Testing & Misc.	LS	LS	LS	
118	Fire Protection - Sprinkler System including Fire Riser	540	HEADS		
119	HVAC - Ventilation Fans and Control System	8	EA		
120	Picnic Tables	8	EA		
121	Trash Receptacles	6	EA		
122	Recycling Receptacles	6	EA		
<b>Area 4 Improvements - Warm-Up Area</b>					
123	4.1 Shop / Storage Pre-Engineered Structure including SOG and Single-Story PEMB	LS	LS	LS	
124	4.1 Shop / Storage Pre-Engineered Structure FF&E (Furnished and Installed)	LS	LS	LS	
125	4.1 Shop / Storage Structure - Utility Connections to Building	LS	LS	LS	
126	4.1 Shop / Storage Structure - Misc. Concrete Exterior Slabs at Garage Entrances	LS	LS	LS	
<b>Area 5 Improvements - Day Use Area / Trail Staging Area</b>					
127	5.3 Trash Bin for Horse Manure (Area 5)	1	EA		
128	Horse Hitch (Area 5)	1	EA		
129	Water Spigot (Including Potable Water Plumbing from Underground System)	1	EA		
130	Plumbing - Exterior Water Connection	LS	LS	LS	
<b>Project Close-Out</b>					
131	Testing, Start-Up and Commissioning (All Facilities)	LS	LS	LS	
132	Special Final Inspections / Inspection Participation (County, SDG&E and Others)	LS	LS	LS	

133	Spare Parts, Lubricants, Oils and Other Special Tools and Materials	LS	LS	LS	
134	O&M Manuals & Warranties	LS	LS	LS	
135	All Project Completion Documents (As-Built Drawings, Schedules, Test Reports)	LS	LS	LS	
136	Cleanup and Demobilization	LS	LS	LS	
<b>Base Bid Total:</b>					

**ADDITIVE ALTERNATE 1**

No.	Description	Estimated Qty	Unit of Measure	Unit Price	Total
<b>Civil/Sitework - Grading Plan</b>					
137	Minor Concrete - Kitchen Pad 9" Concrete SOG & Parking Area	LS	LS	LS	
138	Minor Concrete - Restrooms Pad 9" Concrete SOG & Parking Area	LS	LS	LS	
139	Minor Concrete - Dumpster Pad 9" Concrete SOG & Parking Area	LS	LS	LS	
<b>Civil/Sitework - Site Utilities</b>					
140	<b>Potable Water System:</b>				
141	4" PVC C-900 Class-200 Pipe	1,674	LF		
142	4" DI MJ 90 Ell - Epoxy Lined & Coated w/Accessories	3	EA		
143	4" DI MJ 45 Ell - Epoxy Lined & Coated w/Accessories	1	EA		
144	4" DI MJ Tee - Epoxy Lined & Coated w/Accessories	5	EA		
145	4" Flex Coupling - Epoxy Lined & Coated w/Accessories	4	EA		
146	4" PVC to 8" ACP (Lakeside Irrigation District)	LS	LS	LS	
147	4" Meter Assembly with Concrete Pad, Valves, Bollards and Painting	LS	LS	LS	
148	Water Service Backflow Preventer Assembly	LS	LS	LS	
149	Encase in Red Concrete Over Helix Water District Easement	LS	LS	LS	
150	<b>Sanitary Sewer System:</b>				
151	6" PVC SDR-35 Gravity Sewer Pipe	1,080	LF		
152	6" PVC SDR-35 Gravity Sewer 45 Ell	2	EA		
153	6" PVC SDR-35 Gravity Sewer Wye	2	EA		
154	6" PVC SDR-35 Sewer Pipe Cleanout Assembly including Box & Cover	3	EA		

155	6" Flex Coupling - Epoxy Lined & Coated w/Accessories	3	EA		
156	Connections - 6" PVC to Existing SDRSD Sewer with SS-04 Connection & SC-01 Cleanout	LS	LS	LS	
157	<b>Natural Gas System:</b>				
158	2" Polyethylene Gas Piping/Flex Tubing per Local Codes	620	LF		
159	Connections - 2" Gas Service Connection & Fees including Metering	LS	LS	LS	
160	Gas Line Connection to Main	LS	LS	LS	
161	Encase in Red Concrete Over Helix Water District Easement	LS	LS	LS	
<b>Site – Electrical</b>					
162	Panel 'B' 100A - Kitchen / Meeting Room Building	LS	LS	LS	
163	Panel 'D' 50A - Restrooms Building	LS	LS	LS	
<b>Area 1 Improvements – Covered Arena</b>					
164	1.4 Pre-Engineered Announcer's Booth Structure	LS	LS	LS	
165	1.4 Pre-Engineered Announcer's Booth - FF&E (Furnished and Installed)	LS	LS	LS	
<b>Area 4 Improvements - Warm-Up Area</b>					
166	1.2 Meeting Room / Kitchen Pre-Engineered Structure	LS	LS	LS	
167	1.2 Meeting Room / Kitchen - FF&E (Furnished and Installed)	LS	LS	LS	
168	1.3 Restroom Pre-Engineered Structure	LS	LS	LS	
169	1.3 Restroom - FF&E (Furnished and Installed)	LS	LS	LS	
170	1.4 Dumpster Trash Enclosure - Pre-Engineered Structure	LS	LS	LS	
171	1.4 Dumpster Trash Enclosure – FF&E (Furnished and Installed)	LS	LS	LS	
<b>Additive Alternate 1 Total:</b>					

**ADDITIVE ALTERNATE 2**

No.	Description	Estimated Qty	Unit of Measure	Unit Price	Total
<b>Site – Electrical</b>					
172	Panel 'RV' 30A & 50A - RV Parking Power Pedestals	LS	LS	LS	

173	Panel 'HOST' 50A - Host Pad RV Power Pedestal	LS	LS	LS	
174	Pole-Mounted Light Fixtures - P1 LED Solar-Powered Area Light Fixture (5230 Lumens) - Carmanah EC-340-5230	3	EA		
175	Pole-Mounted Light Fixtures - P3 LED Solar-Powered Area Light Fixture (6060 Lumens) - Carmanah EC-340-6060	8	EA		
176	24"x8'-0" Light Pole Reinforced Concrete Bases w/Anchor Bolts	11	EA		
<b>Area 4 Improvements - Warm-Up Area</b>					
177	4.3 Host Pad - 50'x50' Concrete Pad/Foundation	LS	LS	LS	
178	4.3 Host Pad - 50'x50' Pre-Engineered Shade Structure (Includes Installation)	LS	LS	LS	
179	4.4 RV Hook-Up Pedestal Connections (Water, Sewer and Power)	5	EA		
180	4.5 Heated Wash Racks (Including Misc. Metals & Plumbing)	LS	LS	LS	
181	Corrals (10'x10', Corral Fencing & Gates with Concrete Footings)	5	EA		
182	Trash Receptacles	2	EA		
183	Recycling Receptacles	2	EA		
<b>Area 5 Improvements - Day Use Area / Trail Staging Area</b>					
184	5.1 Pavilion - Concrete Pad/Foundation	LS	LS	LS	
185	5.1 Pavilion – Pre-Engineered Shade Structure	LS	LS	LS	
186	5.1 Pavilion – Pre-Engineered Shade Structure Installation	LS	LS	LS	
187	5.2 Picnic Tables (Area 5)	4	EA		
188	Trash Receptacles	1	EA		
189	Recycling Receptacles	1	EA		
<b>Additive Alternate 2 Total:</b>					

**ADDITIVE ALTERNATE 3**

No.	Description	Estimated Qty	Unit of Measure	Unit Price	Total
<b>Civil/Sitework - Site Improvements</b>					
190	Grand Entrance Gateway & Sign	1	EA		
191	DEDUCT: 6'x25' Vinyl-Coated Chain-Link Gate per SDRSD M-05 with Fire Dept. Lock (Main Gate replaced by Grand Entrance Sign)	1	EA	-	-
192	Peeler Pole Fence - East Side	1,140	LF		



193	Peeler Pole Fence - Biofiltration Basin 1 Perimeter	521	LF		
194	Peeler Pole Fence - Biofiltration Basin 2 Perimeter	207	LF		
195	Peeler Pole Fence - Biofiltration Basin 3 Perimeter (2 Sides Only)	188	LF		
196	Peeler Pole Fence - South Side Public Trail	900	LF		
197	Peeler Pole Fence - South Side Equestrian Trail	691	LF		
198	Peeler Pole Fence - West Side Equestrian Trail	815	LF		
199	Peeler Pole Fence (Tree Guards)	352	LF		
<b>Civil/Sitework - Grading Plan</b>					
200	Final Parking Lot Surfacing - Rough/Fine Grading	230,467	SF		
201	Final Parking Lot Surfacing - Import & Compact Additional 2" DG & 4" AB	4,268	CY		
<b>Site - Irrigation &amp; Landscaping</b>					
202	<b>Irrigation Systems:</b>				
203	Hot Tap Connection Service	LS	LS	LS	
204	1" Potable Irrigation Meter and Installation	LS	LS	LS	
205	1" Backflow Preventer on Concrete Pad	LS	LS	LS	
206	Backflow Preventer Enclosure	LS	LS	LS	
207	1" Master Valve	1	EA		
208	1" Flow Meter	1	EA		
209	Calsense Irrigation Controller, Conventional, 24 Sta.	1	EA		
210	Rain Shut Off Device and Enclosure	1	EA		
211	Pressure Mainline 1.5"	2,002	LF		
212	Pressure Mainline 1"	275	LF		
213	Quick couplers for hand watering and wash down.	11	EA		
214	Shrub Bed and Basin Irrigation	23,842	SF		
215	Drainage Channel Irrigation	14,840	SF		
216	Tree Bubblers	106	EA		
217	1" Meter Capacity Fee - Lakeside Water District	1	EA		
218	1" Meter Capacity Fee – SDCWA	1	EA		
219	Water District Plan Check Fees	1	EA		
220	<b>Landscape / Planting:</b>				
221	36" Box Trees	27	EA		
222	24" Box Trees	9	EA		
223	15 Gallon Trees	11	EA		
224	5 Gallon Shrubs	128	EA		
225	1 Gallon Shrubs	552	EA		
226	Boulders	108	EA		
227	River Cobble	1,920	SF		

228	Hydroseed	32,619	SF		
229	Fine Grading Landscape Areas	28,705	SF		
230	Bark Mulch Shrub Beds (not bio-basins)	10,737	SF		
231	Root Barriers	565	LF		
232	Landscape Maintenance Period	3	MO		
233	Grass-Lined Channel	32,619	SF		
<b>Site – Electrical</b>					
234	Pole-Mounted Light Fixtures - P1 LED Solar-Powered Area Light Fixture (5230 Lumens) - Carmanah EC-340-5230	1	EA		
235	Pole-Mounted Light Fixtures - P2 LED Solar-Powered Area Light Fixture (4480 Lumens) - Carmanah EC-340-4480	3	EA		
236	Pole-Mounted Light Fixtures - P3 LED Solar-Powered Area Light Fixture (6060 Lumens) - Carmanah EC-340-6060	2	EA		
237	24"x8'-0" Light Pole Reinforced Concrete Bases w/Anchor Bolts	6	EA		
<b>Additive Alternate 3 Total:</b>					

**ADDITIVE ALTERNATE 4**

No.	Description	Estimated Qty	Unit of Measure	Unit Price	Total
<b>Civil/Sitework - Grading Plan</b>					
238	Final Parking Lot Surfacing - Rough/Fine Grading	53,680	SF		
239	Final Parking Lot Surfacing - Import & Compact Additional 2" DG & 4" AB	994	CY		
240	Minor Concrete - Type B Curb Ramp per SDRSD G-27	1	EA		
<b>Civil/Sitework - Site Utilities</b>					
241	4" PVC C-900 Class-200 Pipe	2,253	LF		
242	4" DI MJ 90 Ell - Epoxy Lined & Coated w/Accessories	4	EA		
243	4" DI MJ 45 Ell - Epoxy Lined & Coated w/Accessories	1	EA		
244	4" DI MJ Tee - Epoxy Lined & Coated w/Accessories	4	EA		
245	4" Flex Coupling - Epoxy Lined & Coated w/Accessories	3	EA		
<b>Site – Electrical</b>					

246	Pole-Mounted Light Fixtures - P1 LED Solar-Powered Area Light Fixture (5230 Lumens) - Carmanah EC-340-5230	5	EA		
247	Pole-Mounted Light Fixtures - P2 LED Solar-Powered Area Light Fixture (4480 Lumens) - Carmanah EC-340-4480	-	EA		
248	Pole-Mounted Light Fixtures - P3 LED Solar-Powered Area Light Fixture (6060 Lumens) - Carmanah EC-340-6060	-	EA		
249	24"x8'-0" Light Pole Reinforced Concrete Bases w/Anchor Bolts	5	EA		
250	Concrete Pull Boxes (PB-4 through PB-9) - 2'x3' with Galv Steel H20-Loading Bolt-Down Cover & SS Bolts	6	EA		
251	Duct Bank PB-3 to PB-9 including Conduit, Spacers, Encasement, Wire	1,450	LF		
<b>Area 2 Improvements - Outside Arena</b>					
252	2.1 Bleachers – Pre-Engineered Shade Structure (Including Installation)	LS	LS	LS	
253	2.2 Bleachers	LS	LS	LS	
254	2.2 Bleachers Concrete Pad/Foundation	LS	LS	LS	
255	2.3 Announcers Booth – Pre-Engineered Structure	LS	LS	LS	
256	2.3 Announcers Booth – FF&E (Furnished and Installed)	LS	LS	LS	
257	2.4 Covered Viewing Box – Pre-Engineered Structure	LS	LS	LS	
258	2.4 Covered Viewing Box – FF&E (Furnished and Installed)	LS	LS	LS	
259	2.5 Electronic Scoreboard	LS	LS	LS	
260	2.6 Arena Fencing & Equip. – Fencing & Gates (Kovac Ranch Equipment)	LS	LS	LS	
261	Arena Equip. – Footing Material - Import, Place and Compact	LS	LS	LS	
262	Light Fixtures, Conduit, Wire, Subpanels/Disconnects, Grounding	LS	LS	LS	
263	Water Spigots (Including Potable Water Plumbing from Underground System)	5	EA		
264	Electronic Public Address System	LS	LS	LS	
265	Trash Receptacles	2	EA		
266	Recycling Receptacles	2	EA		
<b>Area 3 Improvements - Livestock Corrals</b>					
267	3.1 Livestock Corrals Pre-Engineered Alley Shade Structure (with installation)	LS	LS	LS	
268	3.2 Covered Compost Area (6 Bins)	LS	LS	LS	
269	3.3 Water Truck Filling Station	LS	LS	LS	
270	3.4 Cattle Alley (Kovac Ranch Equipment)	LS	LS	LS	
271	Feeder Troughs (Galv Steel Troughs)	4	EA		

**COUNTY OF SAN DIEGO  
 BIDDER/OFFER DVBE INFORMATION**

**ATTACHMENT B**

272	Water Trough with Automatic Float Valve	4	EA		
273	Water Spigots (Including Potable Water Plumbing from Underground System)	5	EA		
274	Livestock Corrals - Fencing, Gates & Chutes (Kovac Ranch Equipment)	LS	LS	LS	
<b>Additive Alternate 4 Total:</b>					

**TOTAL BASE BID** \$ \_\_\_\_\_

**TOTAL ADDITIVE ALTERNATE 1** \$ \_\_\_\_\_

**TOTAL ADDITIVE ALTERNATE 2** \$ \_\_\_\_\_

**TOTAL ADDITIVE ALTERNATE 3** \$ \_\_\_\_\_

**TOTAL ADDITIVE ALTERNATE 4** \$ \_\_\_\_\_

**TOTAL BID (Base Bid + Add. Alt. 1 + Add. Alt. 2 + Add. Alt. 3 + Add. Alt .4)\$** \_\_\_\_\_

Name of Bidder \_\_\_\_\_

**BID COMPARISON AND AWARD**

If this Proposal shall be accepted and the undersigned shall fail to contract as aforesaid and to give in sums as stated in the Notice to Contractors Inviting Bids, both a faithful Performance Bond, and a Payment Bond as required by Chapter 5 (commencing at Section 3225) and Chapter 7 (commencing at Section 3247), Title 15, Part 4, Division 3, of the California Civil Code, with surety satisfactory to the Owner within the time specified in Section 3-1.03 of the Standard Specifications after the undersigned has received notice of the award of the Contract from the Owner and that the Contract is ready for signature, the Owner may, at its option, determine that the bidder has abandoned the Contract, and thereupon this Proposal and the acceptance thereof shall be null and void, and the forfeiture of the security accompanying this Proposal shall operate and the same shall be the property of the Owner.

Bids are required for the entire work shown in the Base Bid and Additive Alternates 1, 2, 3 and 4 Bid Schedules. The lowest bid shall be the lowest total bid price (base bid and additive alternates 1-4):

1. Base Bid Total
2. Base Bid + Additive Alternate 1 Bid Total
3. Base Bid + Additive Alternate 1 + Additive Alternate 2 Bid Total
4. Base Bid + Additive Alternate 1 + Additive Alternate 2 + Additive Alternate 3 Bid Total
5. Base Bid + Additive Alternate 1 + Additive Alternate 2 + Additive Alternate 3 + Additive Alternate 4 Bid Total

The bidder shall set forth for each item of work, in clearly legible figures, a unit price and a total for the item in the respective spaces provided for this purpose. In the case of unit basis items, the amount set forth under the "Total" column shall be the extension of the unit price bid on the basis of the estimated quantity for the item.