
City of Vista
2023 Pedestrian Mobility Sidewalk Project (CIP No. 8290)

Attachments:

A - CIP 8290 Avenida de Benito Juarez Spec - Final

B - CDBG-Pedestrian Mobility Sidewalk-Ave De Benito Juarez-Plans

1. Introduction

1.1. Summary

Public notice is hereby given that sealed bids will be received by the City Clerk of the chartered City of Vista (“Agency”) for furnishing all plant, labor, services, materials, tools, equipment, supplies, transportation, utilities and all other items and facilities necessary therefore, as provided in the Contract Documents, for the “ 2023 Pedestrian MOBILITY SIDEWALK PROJECT - Avenida De Benito Juarez from W. California Ave to W. Connecticut Ave. (C.I.P. No. 8290) “ in strict accordance with the Project Specifications, Plans and Appendix D exhibits on file in the City of Vista Engineering Department.

1.2. Contact Information

Erin Adams

Management Analyst

Email: eadams@ci.vista.ca.us

Phone: [\(760\) 643-5415](tel:(760)643-5415)

Department:

Engineering

1.3. Timeline

| | |
|---------------------------------------|--------------------------|
| Release Project Date | October 12, 2023 |
| Question Submission Deadline | October 20, 2023, 2:00pm |
| Submission Deadline | October 26, 2023, 2:00am |
| City Council Award (tentative) | December 12, 2023 |

2. Vendor Questionnaire

2.1. [Bid Proposal*](#)

Please upload your complete bid proposal here

*Response required

2.2. [W-9*](#)

Please upload your W-9 Here.

*Response required

3. Pricing Proposal

BID SCHEDULE

| Line Item | Description | Quantity | Unit of Measure | Unit Cost | Total |
|-----------|---|----------|-----------------|------------|-------|
| 1 | Mobilization, Demobilization, bonds & insurance. (5% maximum of Total Base Bid) | 1 | LS | | |
| 2 | Project Information Sign | 1 | EA | | |
| 3 | Public Notification per Supplementary General Provisions, Section 7-12.2 | 1 | LS | | |
| 4 | Storm Water Pollution Prevention and Erosion Control | 1 | LS | | |
| 5 | Traffic Control and Construction Staging for all work | 1 | LS | | |
| 6 | Utility Potholing and coordination | 1 | LS | | |
| 7 | Record Drawing ("As-Built") Plans (stipulated amount) | 1 | EA | \$2,000.00 | |
| 8 | Clearing, Grubbing, tree trimming, Sawcutting, and Removals of existing vegetation, roots, concrete, asphalt, and other existing improvements interfering with new work | 1 | LS | | |
| 9 | Relocate, Reconstruct, Rotate or Replace existing mailbox and post per City of Vista Standard Drawing SRF-04 including reflective address numbers in front and side of mailbox (2" minimum) | 4 | EA | | |
| 10 | Reconfigure Existing Private Irrigation Systems and Replace Turf and Groundcover to Match Existing Private Landscaping Disturbed by Construction. | 1 | LS | | |
| 11 | Unclassified excavation and fill | 1 | LS | | |

| Line Item | Description | Quantity | Unit of Measure | Unit Cost | Total |
|-----------|--|----------|-----------------|-----------|-------|
| 12 | 6" wide (or per plan) x 4" thick infiltration swale, small aggregate pervious concrete with Mirafi 180N fabric on 4" of aggregate base per Plans | 97 | SF | | |
| 13 | 6" Asphalt concrete pavement for full depth pavement restoration, 1' wide slot patch (Use 160 lbs/cf for estimating quantities) | 25 | TN | | |
| 14 | 4' wide 2-inch-Deep Cold Mill adjacent to new curb and gutter, cross gutter and ADA ramps | 862 | SF | | |
| 15 | 4' wide 2" overlay adjacent to new curb and gutter, cross gutter and ADA ramps per plan | 12 | TN | | |
| 16 | PMAC 2" overlay from W. Connecticut to Ave. De La Plaza with Pacific Geosource Forta-Fi Fibers or Ace XP Polymer Fiber (Appendix D & H): | 91 | TN | | |
| 17 | 4-foot Wide Header Cut (2.0-inch to 0-inch) between W Connecticut and Avenida De La Plaza (Appendix D) | 1,496 | SF | | |
| 18 | 15-foot Wide Header Cut at W. Connecticut Ave cross gutters and adjacent to Avenida De La Plaza (Appendix D) | 1,092 | SF | | |
| 19 | 1.5-inch Thick Leveling Course - Avenida De Benito Juarez from W. Connecticut and Avenida De La Plaza (Appendix D) | 30 | TN | | |
| 20 | 6" Type 'G' curb and gutter per SDRSD No. G-2 with 6" aggregate base | 454 | LF | | |
| 21 | Concrete Crossgutter with spandrel per SDRSD No.G-12 on 12" aggregate base | 672 | SF | | |

| Line Item | Description | Quantity | Unit of Measure | Unit Cost | Total |
|-----------|---|----------|-----------------|-----------|-------|
| 22 | 4" PCC sidewalk per SDRSD G-07, and 6" monolithic retaining curb per plan with 4" aggregate base | 176 | SF | | |
| 23 | 4" PCC sidewalk per SDRSD G-07 with 6" aggregate base | 1,194 | SF | | |
| 24 | PCC Driveway Entrance per SDRSD Nos. G-14D confined driveway per plan with 6" aggregate base | 517 | SF | | |
| 25 | PCC Driveway Entrance per SDRSD Nos. G-14F Type B per plan with 6" aggregate base @ 517 | 179 | SF | | |
| 26 | Remove & replace private PCC driveway transition, 4" PCC on 6" aggregate base | 346 | SF | | |
| 27 | PCC curb ramp with detectable warning surface per G-29 Type C on 6" aggregate base | 3 | EA | | |
| 28 | PCC curb ramp with detectable warning surface per plan on 6" aggregate base at Avenida De La Plaza | 2 | EA | | |
| 29 | Geogrid fabric for poor soil condition | 120 | SF | | |
| 30 | Document existing striping to replace in kind, remove conflicting markings, replace striping, paint red curb, relocate signs per Plan | 1 | LS | | |
| 31 | Adjust VID Water Valve Cover to Finish Grade (stipulated amount) | 3 | EA | \$150.00 | |
| 32 | Adjust VID Water Meter to Finish Grade | 1 | EA | | |
| 33 | Adjust City of Vista 36" manhole to Finish Grade | 1 | EA | | |

| Line Item | Description | Quantity | Unit of Measure | Unit Cost | Total |
|--------------|---|----------|-----------------|-----------|-------|
| 34 | Adjust City of Vista Sewer clean out lid to Finish Grade | 1 | EA | | |
| 35 | Hydroseeding with bonded fiber matrix for erosion control for areas disturbed by construction | 100 | SF | | |
| TOTAL | | | | | |

